

GOVERNMENT OF INDIA
ARCHÆOLOGICAL SURVEY OF INDIA
CENTRAL
ARCHÆOLOGICAL
LIBRARY

ACCESSION NO. 20302

CALL No. 721.1/501/101

D.G.A. 79

GOVT

SECRET

LIBRARY

CLASS T SECTION 6 No. 39

DATE OF RECEIPT



PRINCIPLES
OF
REINFORCED CONCRETE
CONSTRUCTION

BY
F. E. TURNEAURE
Dean of the College of Engineering, University of Wisconsin
AND
E. R. MAURER
Professor of Mechanics, University of Wisconsin

351.97741
Turn/Maurer
FIRST EDITION

FIRST THOUSAND

B359

NEW YORK
JOHN WILEY & SONS
London: CHAPMAN & HALL, Limited
1907

Copyright, 1907

BY

F. E. TURNEAURE AND E. R. MAURER


CENTRAL ARCHAEOLOGICAL
LIBRARY, NEW DELHI

Acc. No. 20302

Date... 11: .. 4: .. \$5.

Call No. 721: 975011: Tur/Mau

The Scientific Press
Robert Drummond and Company
New York



PREFACE.

IN the present volume the authors have endeavored to cover, in a systematic manner, those principles of mechanics underlying the design of reinforced concrete, to present the results of all available tests that may aid in establishing coefficients and working stresses, and to give such illustrative material from actual designs as may be needed to make clear the principles involved.

The work is essentially divided into two parts: Chapters I to VI treat of the theory of the subject and the results of experiments, while the remaining chapters treat of the use of reinforced concrete in various forms of structures. In Chapter II the properties of plain concrete and of steel are considered to a sufficient extent to give accurate notions of their relation to the general subject in hand. The subjects of adhesion and of relative contraction and expansion are also discussed in this chapter. In Chapter III is given a full theoretical treatment of reinforced concrete, avoiding so far as possible empirical rules and methods; and in Chapter IV are presented the most important available tests on beams and columns, analyzed and correlated, so far as may be, with reference to theoretical principles. The subjects of working stresses and economical proportions are considered in Chapter V. In Chapter VI are brought together in convenient form all the formulas and diagrams needed for practical use. There are also included tables relating to reinforcing bars and a comprehensive table


of the strength of floor slabs. This chapter is, for most purposes, complete in itself, so that the reader need not refer to any other portion of the work in order to use it in designing.

Following the theoretical portions are chapters on the application of reinforced concrete to building construction, arches, retaining walls, dams, and miscellaneous structures. In these chapters the analysis of various features is given, where the use of reinforced concrete involves problems new and unfamiliar. A complete general analysis of the solid arch rib is also given, which, the authors believe, offers advantages over the usual graphical method. It is primarily an analytical method, but may be shortened by obvious simple, graphical aids. Stresses in the concrete and steel are readily calculated by the use of diagrams in Chapter VI. In the chapters on the application of reinforced concrete it has not been the aim to cover practical construction in all its phases; for this the reader is referred to the more voluminous works on the subject. It is hoped, however, that as a treatment of the principles of design the work may prove of service to the student and the engineer.

F. E. TURNEAURE.

E. R. MAURER.

MADISON, WIS., Sept., 1907.



CONTENTS.

	PAGE
CHAPTER I.	
INTRODUCTORY	1
Historical Sketch. Use and Advantages of Reinforced Concrete.	
CHAPTER II.	
PROPERTIES OF THE MATERIAL	8
<i>Concrete</i> : General Requirements. Cement. Sand. Broken Stone or Gravel. Proportion of Ingredients. Consistency. Compressive Strength. Tensile Strength. Transverse Tests. Shearing Strength. Elastic Properties. Stress-strain Curve in Compression. Modulus of Elasticity. Elastic Limit. Stress-strain Curves. Coefficient of Expansion. Contraction and Expansion. Weight. Properties of Cinder Concrete. <i>Reinforcing Steel</i> : General Requirements. Special Forms of Bars. Quality of the Material. Tensile Strength. Modulus of Elasticity. Elastic Elongation. Coefficient of Expansion. <i>Properties of Concrete and Steel in Combination</i> : Adhesion. Mechanical Bond. Ratio of Moduli of Elasticity. Tensile Stress and Elongation of Concrete when Reinforced. Relative Contraction and Expansion.	
CHAPTER III.	
GENERAL THEORY	43
Kinds of Members. Relation of Stress Intensities in Concrete and Steel. Distribution of Stress in a Homogeneous Beam.	

	PAGE
Purpose and Arrangement of Steel Reinforcement. The Common Theory of Flexure and its Modification for Concrete. Resisting Moment and Inefficiency of Concrete Beams. Varieties of Flexure Formulas. Flexure Formulas for Working Loads. Flexure Formulas for Ultimate Loads. Flexure Formulas for any Load up to Ultimate. Comparison of Flexure Formulas. Flexure Formulas for T-Beams. Beams Reinforced for Compression. Flexure and Direct Stress. Shearing Stresses in Reinforced Beams. Bond Stress. Strength of Columns.	

CHAPTER IV.

TESTS OF BEAMS AND COLUMNS.	113
-------------------------------------	-----

Beams: Methods of Failure of a Reinforced Concrete Beam. Tests of Beams giving Steel-tension Failures. Position of Neutral Axis and Value of n . Observed and Calculated Stresses in the Steel. Compressive Stresses in Concrete. Conclusions Regarding Moment Calculations. Tests in which Failure Occurred by Diagonal Tension. Methods of Web Reinforcement. Action of Web Reinforcement. Effect of Stirrups. Results of Tests. Tests on T-Beams. Conclusions as to Shearing Strength. Beams Reinforced in Compression. *Columns*: Plain Concrete Columns. Tests on Columns with Longitudinal Reinforcement. Hooped Concrete Columns. Fatigue Tests.

CHAPTER V.

WORKING STRESSES AND GENERAL CONSTRUCTIVE DETAILS	166
---	-----

Working Stresses and Factors of Safety. Relative Effect of Dead and Live Loads. *Beams*: Working Formulas. Working Stresses in Concrete and Steel. Quality of Steel. Bond Stress. Shearing Stresses. Calculation of Web Reinforcement. Spacing of Bars. Economical Proportions and Working Stresses. T-Beams. *Columns*: Working Stresses. Economy in the Use of Reinforced Columns. Use of Steel of High Elastic Limit. Use of Steel at Ordinary Working Stresses. *Durability of Reinforced Concrete*: Protection of Steel from Corrosion. Fireproofing Effect of Concrete. Reinforcing Against Shrinkage and Temperature Cracks.

CHAPTER VI.

FORMULAS, DIAGRAMS AND TABLES	PAGE 197
Rectangular Beams. T-Beams. Beams Reinforced for Compression. Flexure and Direct Stress. Shearing and Bond Stress. Columns. Shrinkage and Temperature Stresses. Coefficients and Working Stresses. Tables.	

CHAPTER VII.

BUILDING CONSTRUCTION	237
Division of the Subject. General Arrangement of Concrete Floors. Stresses in Continuous Beams. Effect of Rigid Supports. Slabs Reinforced in Two Directions. Reinforcement to Prevent Cracks. Floor Slabs Supported on Steel Beams. Floor Slabs in All-Concrete Construction. Beams and Girders. Columns. Examples of Floor and Column Design. Footings. Walls and Partitions.	

CHAPTER VIII.

ARCHES	263
Advantages of the Reinforced Arch. Methods of Reinforcement. <i>Analysis of the Arch</i> : General Method of Procedure. Thrust, Shear, and Moment at the Crown. Thrust, Shear, and Moment at Any Point. Partial Graphical Calculation. General Observations. Division of Arch Ring to give Constant $\partial s/I$. Temperature Stresses. Stresses Due to Shortening of Arch from Thrust. Deflection of the Crown. Unsymmetrical Arches. Applications. Maximum Stresses in the Arch Ring. Illustrative Examples of Design.	

CHAPTER IX.

RETAINING-WALLS AND DAMS	289
Advantages of Reinforced Concrete. <i>Retaining Walls</i> : Method of Determining Stability. Equivalent Fluid Pressure for Ordinary Masonry Walls. Stability of Reinforced Concrete Walls. Design of Wall. Illustrative Examples. Rectangular Walls Supported at the Top. <i>Dams</i> : Stability and Examples.	

CHAPTER X.

	PAGE
MISCELLANEOUS STRUCTURES	304
Simple Beam Bridges. Concrete Trestles. Pipe and Box Culverts. The Circular Culvert. The Rectangular Culvert. Arrangement of Reinforcement. Illustrative Examples. Conduits and Pipe Lines. Tanks, Reservoirs, Bins, etc.	

REINFORCED-CONCRETE CONSTRUCTION.

CHAPTER I.

INTRODUCTORY.

1. Historical Sketch.—The invention of reinforced concrete is usually credited to Joseph Monier, but his first constructions are antedated by those of Lambot, who in 1850 constructed a small boat of reinforced concrete and in 1855 exhibited the same at the Paris Exposition. In this latter year Lambot took out patents on this form of construction; it was regarded by him as especially well adapted to shipbuilding, reservoir work, etc.

In 1861, Monier, who was a Parisian gardener, constructed tubs and tanks of concrete surrounding a framework or skeleton of wire. In the same year Coignet announced his principles for reinforcing concrete, and proposed construction of beams, arches, pipes, etc. Both he and Monier executed some work in the new material at the Paris Exposition of 1867. In this year Monier took out patents on his reinforcement. It consists of two sets of parallel bars, one set at right angles to and lying upon the other, thus forming a mesh of bars. This system, and slight modifications of it, are extensively used at the present time, particularly for slab reinforcement. Though even the early Monier patents covered principles of wide application, still the early work in reinforced concrete was confined to a comparatively narrow field.

In 1884-5 the German and American rights of the Monier patents fell into the hands of German engineers. One of these, G. A. Wayss, and J. Bauschinger at once began an experimental investigation of the Monier system, and in 1887 they published their findings. The investigation proved reinforced concrete a valuable means of construction, and furnished some formulas and methods for design. From this time on, the use of reinforced concrete in Austria spread rapidly, and a few years ago the engineers of that country were credited with having done more to develop the new construction than those of any other country. Among these engineers should be mentioned Melan, who in the early 90's originated a system in which I or T beams are the principal element of strength, providing compressive as well as tensile strength. In Germany government regulations hindered the application of reinforced concrete for a time, but now it is widely used in that country. Over two hundred systems of reinforcement, it has been stated, have been developed in Germany alone.

In France the Monier system was never developed as in countries already mentioned. Here, as elsewhere, many other systems of reinforcement were invented from time to time, among which should be mentioned that of Hennebique, who was probably the first to use stirrups and "bent-up" bars. This system is in general use, and the elements of Hennebique's system are probably more widely used than those of any other.

In England and America the first use of iron or steel with concrete arose in the effort to fireproof the former by means of the latter. Attempting to utilize also the strength of concrete, Hyatt built beams of concrete reinforced with metal in various ways, and with Kirkaldy of London performed tests on such beams and published the results of the investigation in 1877. The first reinforced-concrete work in the United States was done in 1875 by W. E. Ward, who constructed a building in New York state in which walls, floor-beams, and roof were made of concrete reinforced with metal to provide tensile strength. But

the Pacific Coast saw the actual early development of this form of construction. H. P. Jackson, G. W. Percy, and E. L. Ransome were the pioneer workers. Jackson has been credited with reinforced constructions dating as far back as 1877, but Ransome executed the most notable early examples. Among these are a warehouse (1884 or '85), a factory building a few years later, the building of the California Academy of Science (1888 or '89), and the museum building of Leland Stanford Junior University (1892). Percy was the architect of the last two. The museum building contains spans of 45 feet and is reinforced throughout. This and the Academy building withstood the recent earthquake remarkably well—the museum better than its two brick annexes.

Other pioneer constructors in reinforced concrete in this country were F. von Emperger and Edwin Thacher. The former introduced the Melan system (1894) and built the first reinforced arch bridges of considerable span. Thacher also was—and still is—a bridge-builder. His first large reinforced-concrete bridge was built in 1896 and was without precedent here or in Europe.

America is the home of the “patent bar”. Both Ransome and Thacher invented bars known by their respective names, the patented feature of which is to furnish a “grip” between bar and concrete; besides these two there are several others on the market designed to give additional grip or bond. There are also patented bars for supplying “shear reinforcement”. Some of these forms have been introduced into Europe.

Reinforced-concrete construction has had a remarkable development, particularly in the last decade, and is now regarded by engineers and architects generally as a safe form of construction with a wide field of economical application. Common practice has already established itself in some directions, and rational principles are available for much design work. Outstanding uncertainties are under investigation in many quarters, and the time is not far distant when “good practice” in reinforced concrete will have been established.

2. Use and Advantages of Reinforced Concrete.—A combination of steel and concrete constitutes a form of construction possessing to a large degree the advantages of both materials without their disadvantages. It will be desirable at the outset to consider briefly these advantages in order better to appreciate the field in which this type of construction is likely to be most successful.

Steel is a material especially well suited to resist tensile stresses, and for such purposes the most economical form—the solid compact bar—is well adapted. To resist compressive stresses steel must be made into more expensive forms, consisting of relatively thin parts widely spread, in order to provide the necessary lateral rigidity. A serious disadvantage in the use of steel in many locations is its lack of durability; and, again, a comparatively low degree of heat destroys its strength, thus rendering it necessary to add a protective covering where a fire-proof structure is demanded. Steel is a relatively expensive building material, and its cost tends to increase.

Concrete is characterized by low tensile strength, relatively high compressive strength, and great durability. It is a good fire-proof material, and therefore serves as a good fire-proof covering for steel. It is also found that steel well covered by concrete is thoroughly protected from corrosion. Concrete is also a comparatively cheap material and is readily available in almost any location.

In the design of structural members these qualities of steel and concrete will lead to the use of the two materials about as follows: For those structural members carrying purely tensile stresses steel must be employed, but it may be surrounded by concrete as a protection against corrosion and fire, or merely for the sake of appearance. For those members sustaining purely compressive stresses concrete is fundamentally the better and cheaper material. With concrete costing 30 cents per cubic foot, for example, and steel 4 cents per pound, or about \$20.00 per cubic foot, and with working stresses of 400 and 15,000 lbs/in², respectively, the relative cost of the

two materials for carrying a given load is as $\frac{30}{400}$ is to $\frac{2000}{15,000}$, or as 45 is to 80. For large and compact compressive members plain concrete will therefore naturally be used, especially where durability is a factor. For more slender members, however, such as long columns, plain concrete is too brittle a material, and therefore too much affected by secondary and unknown stresses to be satisfactory; and for such members steel alone, or the two materials in combination, will preferably be used. Steel may be used with concrete in the form of small rods to reinforce the concrete; or it may be used in larger sections and simply surrounded and held rigidly in place by the concrete, most of the load being carried by the steel; or, finally, a steel column may be used and merely fireproofed by the concrete. As the cost of steel in the form of rods is much less than in the form of built members, and as compressive stresses can, in general, be carried more cheaply by concrete than by steel, economical construction will lead to the use of the maximum amount of concrete and the minimum amount of steel consistent with safety, although this principle will be modified by various practical considerations.

For those structural forms in which both tension and compression exist, that is to say, in all forms of beams, the combination of the two materials is particularly advantageous. Here the tensile stresses are carried by steel rods embedded in the concrete near the tension side of the beam. The steel is thus used in its cheapest form, it is thoroughly protected by the concrete, and the compressive stresses are carried by the concrete. Concrete alone cannot be used to any appreciable extent to carry bending stresses on account of its low and uncertain tenacity, but a concrete beam with steel rods embedded in it to carry the tensile stresses is a strong, economical, and very durable form of structure.

From these considerations it follows that reinforced-concrete construction is advantageous to varying degrees in different types of structures. Some of the most important of

these types will here be noted, together with the advantages accompanying the use of reinforced concrete in their design.

3. *Buildings*.—This type of construction is especially useful for floor-slabs and to a somewhat less degree for beams, girders, and columns. It is also well adapted for footings in foundations, being more economical than I-beam footings embedded in concrete.

4. *Culverts and small Girder Bridges*.—Very satisfactory on account of its simplicity and economy as compared to masonry arches, and because of its durability as compared to steel bridges.

5. *Retaining-walls, Dams, and Abutments*.—Often economical for such structures as compared to ordinary masonry. Plain masonry structures of this kind are designed to resist lateral forces by their weight alone, the resulting compressive stresses, except in extremely large structures, being very small and much below safe values. By the use of reinforced concrete these structures can be designed of a more economical type and so arranged as to utilize the concrete in the form of beams, thus developing more nearly the full compressive strength of the material. The steel reinforcement is fully protected from corrosion, a factor which prevents the use of all-steel frames for structures of this class.

6. *Arch Bridges*.—In this form of structure reinforced concrete possesses less advantage over ordinary masonry than in those forms where the compressive stresses are less important. In an arch the stresses are principally compressive, and these do not require steel reinforcement; it is only to provide for the relatively small bending stresses due to moving loads, or as a precaution against undesirable cracks, that steel is serviceable. No large economy can be obtained through its use. By reason of greater simplicity and the less expensive abutments required, a flat-top culvert or beam bridge, with abutments of reinforced concrete, is more advantageous for short spans than the arch.

7. *Reservoir Walls, Floors, and Roofs*.—Very well adapted as a durable material and lending itself to lighter design than common masonry.

8. *Conduits and Pipe Lines*.—Reinforced concrete can often be used to great advantage in a water-conduit or large sewer. It is also sometimes used for pipe lines and tanks under pressure, the steel being relied upon to resist the tensile stresses, while the concrete serves as a protection and as a water-tight covering. The amount of steel may thus be determined by considerations of strength alone, where otherwise a much larger amount of metal would be needed and in a more expensive form.

9. *Elevated Tanks, Bins, etc.*—Advantageous because of its durability and its adaptability in the construction of heavy floors and walls subjected to lateral pressure. Of especial value for coal-bins, either for flooring and lining alone, or for the entire structure.

10. *Chimneys and Towers*.—Possesses advantages over brick or stone masonry in the fact that it forms a structure of monolithic character, resulting in greater certainty in the stresses and economy in design.

11. *Piles, Railroad Ties, etc.*—The use of a moderate amount of steel with concrete so as to give to this material a reliable tensile and bending resistance has opened the way for its use in a great variety of forms, not only as complete structures, or important members of structures, but also in many special individual forms. Concrete piles are valuable substitutes for piles of wood where the latter would be subject to deterioration. Reinforced-concrete ties offer some evident advantages over ties of wood or steel. This material is also well adapted to many other special uses, particularly where durability is an important factor.

CHAPTER II.

PROPERTIES OF THE MATERIALS.

12. In a design where two or more materials are combined in the same member the stresses in the different materials depend upon the elastic properties as well as upon the super-imposed loads. Therefore in making such designs a knowledge of these elastic properties is quite as necessary as a knowledge of the strength of the materials.

CONCRETE.

13. **General Requirements.**—The conditions to be met in reinforced-concrete construction require the use, generally, of a concrete of relatively high grade. In this type of construction the strength of the material is of much greater importance than it is in many forms of plain concrete design, as the dimensions of the structures are more directly dependent upon strength and less upon weight. A comparatively strong concrete is therefore found to be economical.

It is especially important, also, that the concrete be of uniform quality and free from voids, as the sections are comparatively small and the stability of the structure, to a much greater extent than is the case with massive concrete, is dependent upon the integrity of every part. Thoroughly sound concrete is also required in order to insure good adhesion to the steel reinforcement and adequate protection of the steel from corrosion and from fire. These requirements call for great care in the preparation and placing of the material.

Concrete is subject to great variations in its properties, owing to the great variations in the character and proportions of its ingredients and in its preparation. It is therefore difficult to judge from results of tests made under certain conditions as to what may fairly be expected of a concrete prepared under other conditions; so that it is very important that regular and systematic tests of the material as actually used be made during the progress of the work.

14. Cement.—Portland cement only should be used; it should meet such standard specifications as those of the American Society of Civil Engineers. The rapidity of hardening of different cements varies considerably and may be an element requiring special attention where the structure is to receive its load very early or where such load is to be long deferred.

15. Sand.—The sand should be free from clay and preferably of coarse grain. A fine sand requires more cement than a coarse sand for equal strength, and more water for a like consistency. In the case of a very fine sand the difference may be very marked, so that unless care is taken and special tests made, the resulting concrete is likely to be porous and deficient in strength and adhesive power. Where the use of fine sand is contemplated, tests of strength may show that a considerable extra cost may be justified in securing a coarser material. The effect of size of sand is shown in Art. 19.

16. Broken Stone and Gravel.—Both materials are satisfactory, but they should be screened to remove the dust or sand and to remove particles larger than the maximum size desired. Beyond this, the screening of stone to size is undesirable unless an artificial mixture is to be made, as it tends to increase the proportion of voids. Gravel may be sufficiently uniform in quality so that the sand need not be removed, but it will usually require screening in order to insure a concrete of definite proportions.

The maximum desirable size of stone or gravel depends upon the size of the structural forms and the size and spacing of the reinforcement, it being desirable to use as large a size of aggre-

gate as will admit of convenient working. Maximum sizes of stone of $\frac{3}{4}$ inch to $1\frac{1}{4}$ inches are common, but on heavy work, with rods widely spaced, there is no objection to still larger sizes.

The crushing strength of a gravel concrete is usually a little less than one of broken stone of the same proportion of voids, but the difference is unimportant. The difference in tensile strength is not well determined, but the few tests available indicate about the same relative difference as in compressive strength.

17. Proportions of Ingredients.—The proportions commonly used vary from about 1:2:4 to 1:3:6 of cement, sand, and broken stone respectively; or the equivalent proportions if gravel be used. Richer mixtures than 1:2:4 are not common, nor poorer mixtures than $1:2\frac{1}{2}:5$, although with a well-graded sand a very satisfactory concrete can be made of 1:3:6 proportions. Occasionally where the design is determined by other considerations than strength and cost, a very rich mixture or a poor one may be desirable, but where these elements determine the design, the most economical concrete will be a rich concrete of about the proportions above indicated. Customary proportions, such as 1:2:4, should not be blindly adopted. In any important work a careful study of the materials and of the best proportions to use for economy and strength will be well repaid. To secure sound and reliable work, with good adhesion and tensile strength, there must be no unfilled voids in the stone and little or none in the sand. The former is of more importance than the latter, and if cost and strength are to be reduced it should be done by using a poorer mortar to fill the voids in the stone. For a more detailed study of this subject the reader is referred to special works on concrete.

18. Consistency.—The tendency in all kinds of concrete construction is to use a wetter mixture than formerly. Relatively dry concrete thoroughly tamped will give slightly greater strength than a wet mixture; however, if not too wet the

difference is not great, and considering the difficulty and expense of securing the necessary amount of tamping of the dry mixture, better results can usually be secured by using a plastic mixture. This is especially true with reference to obtaining a dense, homogeneous concrete. The usual practice now is to make the consistency such that the concrete will require only moderate tamping or puddling to bring the mass to a homogeneous condition. Such concrete, while somewhat weaker than the ideal compacted concrete, will, under actual conditions, be much more reliable and will be free from voids. In the case of reinforced-concrete work reliability is more important than maximum strength, and is promoted by using concrete of such consistency that it can readily be worked into place in the forms and around the reinforcing steel. In practice the consistency varies. Some use a concrete which requires considerable tamping and working, while others use a concrete which will practically flow into place. The dryer the concrete the closer the inspection required when the material is placed; on the other hand very wet concrete is not as strong and needs to be promptly poured to prevent segregation of the materials.

19. Compressive Strength.—The compressive strength of concrete is dependent upon many factors so that it is difficult and at the same time somewhat misleading to present "average values". Obviously, in any important work, the strength should be determined under the actual conditions under which the concrete is used. Uniformity is quite as important as average strength.

One of the best series of tests is that made at the Watertown Arsenal for Mr. George A. Kimball, Chief Engineer of the Boston Elevated Railway Company.* The concrete was made of five brands of Portland cement, coarse, sharp sand, and broken stone up to 2½-inch size. The concrete was well rammed into the molds, water barely flushing to the surface.

* Tests of Metals, 1899, p. 717.

The specimens were buried in wet ground after being taken from the molds. The average results were as follows:

TABLE NO. 1.
COMPRESSIVE STRENGTH OF CONCRETE.
WATERTOWN ARSENAL, 1899.

Mixture.	B and of Cement.	Strength, Pounds per Square Inch.			
		7 Days.	1 Month.	3 Months.	6 Months.
1 : 2 : 4	Saylor.....	1724	2238	2702	3510
	Atlas.....	1387	2428	2966	3953
	Alpha.....	904	2420	3123	4411
	Germania.....	2219	2642	3082	3643
	Alsen.....	1592	2269	2608	3612
	Average.....	1565	2399	2896	3826
1 : 3 : 6	Saylor.....	1625	2568	2882	3567
	Atlas.....	1050	1816	2538	3170
	Alpha.....	892	2150	2355	2750
	Germania.....	1550	2174	2486	2930
	Alsen.....	1438	2114	2349	3026
	Average.....	1311	2164	2522	3088

In a series of tests made at the Watertown Arsenal for Mr. George W. Rafter, the following average values were obtained on concrete about 20 months old.* The voids in the broken stone were practically filled. The mixture was of damp-earth consistency:

Cement.	Sand.	Strength.
1	1	4467 lbs/in ²
1	2	3731 "
1	3	2553 "

Results as high as indicated by the preceding values cannot be safely counted upon in practice. Wet concrete will show a lower strength than concrete as dry as that in the above tests, especially for the earlier periods, but the difference becomes less with lapse of time, and a fairly soft plastic con-

* Tests of Metals, 1898.

crete will acquire about the same strength as dry concrete within three or four months. A very wet concrete will, however, continue to be somewhat weaker than one containing less water, and while such a concrete may, on the whole, be desirable, its deficiency in strength as compared to maximum values should not be overlooked. Other variations in conditions, such as rapid drying out, or the use of very fine sand, for example, may give results materially below those here quoted.

The following average results of a large number of tests in the series made for Mr. Rafter, already referred to, show the relative strengths of dry, plastic, and wet concrete at the age of about twenty months. The dry mixtures were only a little more moist than damp earth and required much ramming; the plastic mixtures required a moderate amount of ramming to bring water to the surface; the wet mixtures quaked like liver under moderate ramming. Five brands of cement were used:

Consistency.	Mean Compressive Strength.
Dry.....	2348 lbs/in ²
Plastic.....	2203 “
Wet.....	2129 “

In actual practice results are very likely to be less favorable to dry mixtures on account of the great difficulty of securing adequate tamping.

The effect of size of sand has been thoroughly investigated by Feret. Fig. 1, from Johnson's "Materials of Construction", shows results obtained by Feret on 1:3 mortar after hardening one year in fresh water. The sand used consisted of mixtures of various proportions of fine (.0 to .5 mm.), medium (.5 to 2 mm.), and coarse (2 to 5 mm.) sand, and in the figure the result from any particular mortar is recorded in the triangle at such distances from the three base-lines as will represent the proportions of each size sand used. Lines of equal strength were then drawn in the diagram. Thus the strength of the mortar

in which only fine sand was used was only 1400 lbs/in². The maximum strength of 3500 lbs/in² was obtained from a mixture containing about 85% of coarse sand and 15% of fine, with a very little sand of medium size. This diagram shows in a striking manner the effect of size of sand.

As illustrating, further, the variation in results that may be expected, due to variation in conditions, 60-day tests on




FIG. 1.—Effect of Size of Sand.

6-inch cubes mixed wet and left exposed in a room are thus reported by Professor Talbot:*

1:2:4 mixture, average strength 1520 lbs/in².

1:3:6 mixture, average strength 1230 lbs/in².

These low results were probably due to too rapid drying.

Thirty-day tests on thirty-eight 4-inch cubes of 1:2:4 wet concrete, made at the University of Wisconsin in 1906, gave an average strength of 1785 lbs/in², with many values below 1500. The cubes were stored in air in a basement room. The average result of tests on cylinders 6 inches in diameter by 18 inches high of the same material was 1780 lbs/in². That a less strength was not shown for the cylinders than for the cubes was probably due to the greater effect of rapid drying

* University of Illinois, Bulletin No. 4, 1906.

on the small cubes. A fine sand was used. In another test of the same material, two 4-inch cubes cured in water averaged 1600 lbs/in², while two similar cubes hardened in air averaged 1370. Of four beams tested which failed by crushing, two which were cured in water failed at an average load of 8380 lbs., and two cured in air at a load of 7400 lbs., thus showing a less relative difference in strength than in the case of the cubes. Other compression tests in which a very fine though commonly used sand was employed gave results but little more than 1000 lbs/in² in 30 days.

Considering the various results noted it may be concluded that under reasonably good conditions as to character of material and workmanship an average strength of 2000–2200 lbs/in² may be expected of a 1:2:4 concrete in 30 to 60 days, the rate of hardening depending upon the consistency and the temperature; and for a 1:3:6 concrete a strength of 1600 to 1800 lbs/in². It will be noted that these values are but little less than the minimum averages given in Table No. 1 (page 12) for 30-day tests.

It is important that the strength be determined by actual tests of the material proposed to be used, and if the results are too low the ingredients or proportions should be modified until a satisfactory result is obtained. Where the usual proportions give low results it will generally be advisable to increase the richness of the concrete rather than to reduce the working stresses.

20. Tensile Strength.—Comparatively few tests have been made on the tensile strength of concrete. This property is, however, important, and should receive more attention, as it is closely involved in the most common and most dangerous type of failure of reinforced-concrete beams. The tensile strength of concrete is usually stated as approximately one-tenth to one-eighth of the compressive strength, although there is no fixed relation between the two values. The character of the sand and the aggregate has probably a greater influence on the tensile strength than upon the compressive, and poor

workmanship undoubtedly has. Tests by Mr. W. H. Henby * gave results as follows:

Mixture.	Compressive Strength.	Tensile Strength.
1:2:4	3000 lbs/in ²	180 lbs/in ²
1:3:6	1800 "	115 "

Tests by Professor W. K. Hatt † gave the following results:

Kind of Concrete.	Age, days.	Compressive Strength, lbs/in ² .	Tensile Strength, lbs/in ² .
1:2:4 (broken stone)	30	—	311
1:2:5 "	90	2413	359
1:2:5 "	28	2290	237
1:5 (gravel)	90	2804	290
1:5 "	28	2400	253

Tests by Professor Ira H. Woolsen ‡ on 1:2:4 mixtures 5 to 7 weeks old gave an average tensile strength of 161 lbs/in², compared to 1753 lbs/in² compressive strength.

Professor Talbot obtained values for 1:3:6 concrete from 50 to 84 days old of 178, 160, and 170 lbs/in².§

21. Tensile Strength as Determined by Transverse Tests.—

The transverse strength of plain concrete depends almost entirely upon its tensile strength, although the modulus of rupture is considerably greater than the strength in plain tension owing to the curved form of the stress-strain diagram. Feret || found a very nearly constant ratio of 1.95 of modulus of rupture to tensile strength. The value of this ratio will ordinarily range from 1.5 to 2. Transverse tests of different concretes should therefore show about the same relative results as tensile tests. They are in fact quite as significant in this connection.

Some of the best tests on transverse strength are those made by William B. Fuller, and given in full in Taylor and

* Jour. Assn. Eng. Soc., Sept. 1900.

† Jour. West Soc. Eng., Vol. IX, 1904, p. 234.

‡ Eng. News, Vol. LIII, 1905, p. 561.

§ Bulletin No. 1, Univ. of Ill., 1904.

|| Étude Expérimentale du Ciment Armé. Paris, 1906.

Thompson's work on Concrete.* The following average results were obtained for 33-35-day tests.

Mixture by Volume.	Average Modulus of Rupture.
1:2.16:4.08	439 lbs/in ²
1:2.16:5.1	380 "
1:3.24:5.1	285 "
1:3.24:6.12	226 "
1:3.24:7.14	239 "

Here we find the strength of the 1:3.24:6.12 mixture only about one-half that of the 1:2.16:4.08 mixture, indicating the relative weakness in tension of the lean mixture.

The results herein given, both of tensile and of transverse tests, indicate that the quality of the concrete has a greater relative effect on the tensile strength than on the compressive strength, the strength of a 1:3:6 mixture being not more than two-thirds that of a 1:2:4 mixture. Reasonable values for ultimate tensile strength would appear to be about as follows:

1:2:4 mixture.....	160-200 lbs/in ²
1:3:6 "	100-125 "

22. Shearing Strength.—There is a lack of uniformity among writers as to just what is meant by the term "shearing strength", resulting in a wide variation in the suggested values for working stresses. In this work the authors will use the term as it is commonly thought of among American engineers, to denote the strength of the material against a sliding failure when tested as a rivet or bolt would be tested for shear; that is, when the maximum shearing stresses are confined to a single plane.

Tests made under the direction of Professor C. M. Spofford on cylinders 5 inches in diameter with ends securely clamped in cylindrical bearings gave results as follows:

Mixture.	Shearing Strength, lbs/in ² .	Compressive Strength, lbs/in ² .	Ratio of Shearing to Comp. Strength.
1:2:4	1480	2350	.63
1:3:5	1180	1330	.89
1:3:6	1150	1110	1.04

* Concrete, Plain and Reinforced. N. Y., 1906.

Tests made at the University of Illinois on rectangular specimens tested in a similar manner gave the following average results:

Mixture.	Shearing Strength, lbs/in ² .	Compressive Strength, lbs/in ² .	Ratio of Shearing to Comp. Strength.
1:2:4	1418	3210	.44
1:3:6	1250	2290	.57

Tests made by punching through plates gave shearing strengths varying from 37 to 90 per cent of the compressive, the value depending upon the form of test-piece.*

Tests by M. Feret on mortar prisms gave results for shearing strength equal to about one-half the crushing strength.

The ordinary crushing failure is really a failure by shearing, and under such conditions the crushing stress is, theoretically, twice the shearing stress, the angle of shear being 45°. Results of tests give a somewhat greater inclination than 45°, so that the crushing stress is somewhat greater than twice the actual shearing stress.

We may then conclude, both from theory and from tests, that the shearing strength of concrete, in the sense here used, is nearly one-half the crushing strength. It is in fact so large that it will need to be considered only in exceptional cases.

Some writers used the term "shearing stress" to mean quite a different thing from that discussed above, namely, the complex action which occurs in the web of a beam. In this case there exist direct tensile and compressive stresses which at the neutral axis are equal in intensity to the vertical and horizontal shearing stresses. The limit of distortion in the concrete will be reached, and failure will occur, when the tensile strength of the material is exceeded. Such a failure may perhaps be called a shearing failure, but is more strictly a failure in tension in a diagonal direction, and is so considered in this work. Treated as a shearing failure the strength should be very nearly the same as the tensile strength of the material determined in the usual way. In practice the diagonal tensile

* Bulletin No. 8, Univ. of Ill., 1906.

stresses in a beam must often be considered, but shearing stresses, as such, will be dangerous only in exceptional circumstances, such as exist where a heavy load is applied close to a support.

23. Elastic Properties of Concrete.—*Stress-strain Curve in Compression.*—In the design of combination structures, such as those of steel and concrete, it is necessary to know the relative stresses under like distortions. These will depend upon the moduli of elasticity of the two materials. For purposes of safe design we need to know also the elastic-limit strength.

Fig. 2 represents typical stress-strain curves for concrete in compression. Curves *C*, *D*, *E*, and *F* were obtained at the University of Wisconsin from tests on cylinders 6 inches in diameter by 18 inches high. The concrete was 1:2:4 limestone concrete 30 days old. The ultimate strengths ranged from 1500 to 2300 lbs/in². Curves *A* and *B* are typical curves selected from the Watertown Arsenal tests already quoted, and represent 1:2:4 and 1:3:6 concrete respectively.

Unlike the elastic line for steel, the line for concrete is slightly curved almost from the beginning, the curvature gradually increasing towards the end. There is, however, no point of sharp curvature as for ductile materials. A release of load at a moderate stress, such as 500 to 600 lbs/in², will usually show a small set indicating imperfect elasticity. A second application of the load will, however, give a straighter line than the first and there will be much less permanent set following the release of load. After a few repetitions of load there will be no further set and the stress-strain line will become a straight line up to the load applied. There is a limit of stress, however, beyond which repeated applications of load will continue to add to the permanent deformation and the specimen will ultimately fail. The general behavior under repeated stress is indicated in Fig. 3, from tests on concrete similar to those represented in Fig. 2. For a very exhaustive study of this subject the reader is referred to the work of Bach.*

* Zeit. V. dt. Ing., 1895, etc.

24. *Modulus of Elasticity in Compression.*—The stress-strain line being curved almost from the beginning, the proper




FIG. 2.—Compressive Stress-strain Diagrams of Concrete.

method of calculating the modulus of elasticity needs to be considered. Fig. 4 is a typical stress-strain diagram for com-

pression (somewhat simplified), B and C being points where the loads have been removed and reapplied. For very low stresses, up to perhaps 300 to 400 lbs/in² (a low working stress), the variation of the curve from a straight line is so small




FIG. 3.—Stress-strain Diagram under Repeated Loads.

that it may be considered as straight, and an average straight line may be drawn, as OT , and its slope taken as the modulus of elasticity. This line may be considered the same as the tangent at the origin. For higher stresses, reaching to a point along

the curved portion such as point B , it is usual to deduct the permanent set Oa from the deformation Ob and divide the stress by the remaining elastic deformation ab . This gives the slope of the line aB , and may be considered to represent the law of elastic deformation for stresses within the limit of the stress bB after the first few applications of load. A modified "elastic" curve, $OB'C'$, can thus be drawn by deducting from the deformation for each load the subsequent set, giving a steeper curve and one more nearly approaching a straight line. On the basis




FIG. 4.

of this "elastic" curve the modulus of elasticity for stresses up to any given maximum would then be equal to that maximum stress divided by the elastic deformation at that stress.

There being no general agreement as to the exact definition of the word "modulus" for such materials as concrete, the method which should be employed in calculating its value should depend upon the purpose for which it is to be used. The principal use of the modulus of elasticity in reinforced-concrete design is to determine the relative stresses carried by the concrete and the steel in compression members, and to find the neutral axis in beams. After the neutral axis is once found the modulus does not enter into the calculations.

Consider the action in the case of a column. Assuming no initial stress in the steel or concrete, suppose that the column is loaded so as to cause a shortening equal to Ob , Fig. 4. The stress in the concrete will be bB , and that in the steel will be equal to the deformation Ob multiplied by its modulus of elasticity. Upon removal of the load there may be a permanent set Oa , which means that there is some residual compression in the steel (with an equal amount of tension in the concrete). A second application of the load will cause a deformation ab , but, measuring from the original position, the deformation is Ob , and this again fixes the stress in the steel. Hence, for the determination of the relative stresses in steel and concrete by the use of their moduli of elasticity, the modulus for the concrete should be the ratio of Bb to Ob , or the slope of the chord OB . That is to say, it is the load divided by the maximum total deformation for that load. This ratio will be less than the slope of the line OT , or of the elastic line aB .

In the case of a beam the stresses in the concrete at any section will vary from zero at the neutral axis to the value Bb , for example, at the extreme fibre. At intermediate points the stresses follow approximately the law of the curve OB . In this case a chord OB does not exactly represent the facts, but the error is small, and it is the best line to use if the rectilinear variation of stress be assumed. If a curvilinear law is used, then the modulus is supposed to be the slope of the tangent at the origin. In neither case is it correct to use the slope of the line aB .

The value of the modulus for concrete varies greatly as determined by different experimenters and for different kinds of concrete. As a rule the denser and older the concrete the higher the modulus.

Among the most careful experiments are those by Bach,* in which he repeated the loads at each increment until there was practically no increase of set.

* Zeit. V. dt. Ing., 1895.

The following are some average results:

Kind of Concrete.	Modulus of Elasticity, lbs/in ² .		
	Based on Elastic Deformation.		Based on Total Deformation.
	At 114 lbs/in ² .	At 570 lbs/in ² .	At 570 lbs/in ² .
1:2½:5 (broken stone).....	4,660,000	3,590,000	3,440,000
1:2½:5 (gravel).....	3,170,000	2,520,000	2,200,000
1:3:6 (broken stone).....	3,870,000	2,990,000	2,570,000
1:3:6 (gravel).....	3,000,000	2,240,000	2,110,000

The specimens were 25 cm. in diameter and 100 cm. high and were from three to four months old.

The average values of the modulus obtained in the Watertown Arsenal tests mentioned in Art. 19 were as follows:

TABLE NO. 2.
MODULUS OF ELASTICITY OF CONCRETE.
WATERTOWN ARSENAL TESTS, 1899.

Mixture.*	Brand of Cement.	Modulus of Elasticity between Loads of 100 and 600 lbs/in ² , Based on Elastic Deformation.		
		7-10 Days.	1 Month.	3 Months.
1:2:4 {	Saylor.....	1,667,000	2,500,000	3,571,000
	Atlas.....	2,778,000	3,125,000	4,167,000
	Alpha.....	1,000,000	2,083,000	4,167,000
	Germania.....	2,500,000		3,571,000
	Alsen.....	2,500,000	2,778,000	2,778,000
	Average.....	2,089,000	2,621,000	3,651,000
1:3:6 {	Saylor.....	2,273,000	2,778,000	4,167,000
	Atlas.....	1,667,000	3,125,000	2,778,000
	Alpha.....		2,083,000	3,571,000
	Germania.....	2,273,000	2,273,000	2,778,000
	Alsen.....	1,667,000	2,273,000	2,778,000
	Average.....	1,970,000	2,506,000	3,214,000

These results were calculated by using the total deformation minus the set. If the total deformation be used the values would be reduced in most cases 10 to 20 per cent.

The average value of the modulus obtained from tests made at the University of Wisconsin of 30 cylinders of 1:2:4 concrete, 30 days old, 6 in. in diameter and 18 in. high, calculated at a stress of 600 lbs/in² and using the total deformation, was 2,560,000 lbs/in². The average compressive strength was 1780 lbs/in².

Values considerably higher than most of those already quoted have been found by some experimenters, some using the tangent at the origin and some the elastic deformation in their calculations.

Considering the various results obtained and the significance of total deformation, the authors would suggest for working loads a minimum value of 2,000,000 and a maximum value of 3,000,000, depending upon richness of mixture and age of concrete for which the calculations are made. A large number of tests on beams noted in Chapter IV, in which the neutral axis was carefully determined, gave results corresponding closely to a value of 2,000,000 for the modulus. As a large variation in the assumed value of the modulus results in but small variation in design, no great accuracy in this matter is needed. Where ordinary concrete is used a general average value of 2,500,000 is sufficiently close for all practical purposes.

25. Elastic Limit.—As stated in the preceding article, concrete shows a permanent set under small loads so that, in the usual sense, the material can hardly be said to have an elastic limit. There appears to be, however, a limit to the stress which can be repeated indefinitely without continuing to add to the deformation, and this limit may be taken as the elastic limit for practical purposes. From experiments by Bach and others, this limit seems to be from one-half to two-thirds the ultimate strength. In repeated-load experiments on neat cement and on concrete made by Professor J. L. Van Ornum * it has been shown that the maximum load which may be repeated an indefinite number of times without rupture does

* Trans. Am. Soc. C. E., Vol. LI, p. 443. Proc. Am. Soc. C. E., Dec. 1906.

not much exceed 50% of the ultimate strength.* These results show a close relation to those obtained by Bach, and it may therefore be concluded that the limit of permanent elasticity for repeated loads is from 50 to 60% of the ultimate strength.

26. *Comparison of Stress-strain Curve with the Parabola.*—As the parabola is often used in theoretical analyses to represent the stress-strain curve it will be useful to compare some typical curves with the parabola. The form of parabola used has its axis vertical and its vertex at the point of the curve representing the ultimate strength. In Fig. 5 the curves shown in Fig. 2 are compared with parabolas (shown in dotted lines). In the case of curves *C*, *D*, *E*, and *F* the agreement is very close.

27. *Stress-strain Curve for Tension.*—Comparatively few tests have been made on the elasticity of concrete in tension. Professor Hatt found the average value of the modulus for 1:2:4 concrete, 30 days old, to be 2,100,000 and the average total elongation at rupture $1/7000$ part, with a tensile strength of 311 lbs/in².† Later tests by him gave for the modulus the high values of 3–5,000,000, which were about the same as the values in compression. These and other tests indicate that the initial modulus in tension and in compression are about the same, and as the working limit in tension is very low they may be assumed as equal without material error. The relative strength and deformation of concrete in compression and tension is illustrated by a typical curve in Fig. 6.

28. *Coefficient of Expansion.*—Experiments by Professor W. D. Pence ‡ on 1:2:4 concrete gave an average value of the coefficient of expansion of .0000055 per degree Fahrenheit, there being little variation among the several tests. Tests made at Columbia University on 1:3:6 concrete gave values of about .0000065. Other experiments have shown somewhat higher results. A value of .000006 may be assumed.

* See also Art. 117.

† Proc. Am. Soc. Test. Mat., 1902.

‡ Jour. West Soc. Eng., Vol. VI, 1901, p. 549.

29. Contraction and Expansion in Hardening.—Many experiments have been made relative to shrinkage and swelling




FIG. 5.—Stress-strain Curves Compared with Parabolas.

of cement-mortar in hardening. In general the results show that when hardened in air there will be more or less shrinkage,

but when hardened in water there is likely to be some swelling, although results on this point are not entirely consistent. The richer the mortar (or concrete) the greater the change in dimensions. Experiments by Considère and others indicate that 1:3 plain mortar will shrink .05 to .15% when hardened




FIG. 6.—Relative strength and deformation in compression and tension.

in air for 2 to 4 months, and neat cement from two to three times as much. Considère found the shrinkage of a 1:3 mortar reinforced with 5½% of steel to be only .01%, or one-fifth the amount his tests showed on plain mortar. The few tests available show that the shrinkage of concrete is less than that

of mortar, and it would appear that the shrinkage should be nearly proportional to the amount of cement per unit volume, as the sand and stone are unaffected.

30. Weight of Concrete.—The weight of concrete of the usual proportions will vary from 140 to 150 lbs/ft³, depending upon the degree of compactness and the specific gravity of the materials. Variation of proportions will affect the weight but little if the proper ratio of sand and stone be maintained, but a wet concrete when dried out will weigh less than a well-compacted concrete containing originally less water. For practical purposes an average value of 145 lbs/ft³ may be taken. The addition of reinforcing steel in the usual proportions will add from 3 to 5 pounds, so that the weight of reinforced concrete may be taken at 150 lbs/ft³.

31. Properties of Cinder Concrete.—The following table of results indicates fairly well the strength and modulus of elasticity of cinder concrete. The age of the specimens varied from 30 to 100 days. Cinder concrete will weigh from 110 to 115 lbs/ft³.

TABLE NO. 3.

CRUSHING STRENGTH AND MODULUS OF ELASTICITY OF CINDER CONCRETE.

WATERTOWN ARSENAL TESTS, 1898.

Mixture.			Average Crushing Strength, lbs./in. ² .		Average Modulus of Elasticity between Loads of 100 and 600 lbs./in. ² .
Cement.	Sand.	Cinders.	One Month.	Three Months.	
1	1	3	1540	2050	2,540,000
1	2	3	1098	1634	
1	2	4	904	1325	
1	2	5	724	1094	1,040,000
1	3	6	529	788	

REINFORCING STEEL.

32. General Requirements.—In general, reinforcing steel must be of such form and size as to be readily incorporated into the concrete so as to make a monolithic structure. To provide the necessary bond strength and to distribute the steel where needed without concentrating the stresses on the concrete too greatly, requires the use of the steel in comparatively small sections. This requirement, as well as that of economy and convenience, leads to the use of the steel in the form of rods or bars. These will vary in size from about $\frac{1}{4}$ to $\frac{3}{8}$ inch for light floors up to $1\frac{1}{2}$ to 2 inches as maximum sizes for heavy beams or columns. Under certain conditions a riveted skeleton work is preferred for the steel reinforcement, but this is usually where for some reason it is desired to have the steelwork self-supporting or where it is to carry an unusually large proportion of the load.

33. Forms of Bars.—Plain round rods have been used generally in Europe for many years, and also very largely in this country, adhesion being depended upon for the transmission of stress. Square rods show about the same adhesive strength as round rods, but are not so convenient to use or so readily obtained. Flat bars are undesirable, as their adhesion to the concrete is much below that of round or square bars.

Many special forms of bars have been devised, the principal object of which is to furnish a bond with the concrete independent of adhesion,—a “mechanical bond” as it is usually called. Some of the most common types of such bars are illustrated in Fig. 7. Fig. (a) is the twisted square bar invented by Mr. Ransome and called by his name. It is usually twisted cold. Figs. (b), (c), and (d) illustrate various well-known types of deformed bars which are shaped in the rolling. Fig. (e) illustrates the Kahn bar, formed by turning up strips sheared from the thin part of the bar. Many other devices are employed to a greater or less extent to provide a mechanical bond, and a great variety of combinations of forms




FIG. 7.—Deformed Bars.

are used in the construction of beams, floors, and columns as patented "systems". It is the purpose here to mention only the most common types of bar element.

34. General Quality of the Steel.—Steel used in reinforced work is not usually subjected to as severe treatment as that used in ordinary structural work. Bars must be capable of being bent to the desired form, but this is the only treatment to which the ordinary bars are subjected. In many concrete structures the impact effect is also likely to be less than in all-steel structures; consequently it is considered that a somewhat less ductile material may safely be used, but to what extent these considerations should permit the use of steel of cheaper grade or of higher elastic limit is an open question on which there is much difference of opinion. The question of elastic limit as related to working stresses and stresses in the concrete is discussed in Chapter V.

35. Tensile Strength.—Various grades of steel are used in reinforced concrete ranging from soft to quite hard. Classifying the material under three heads, soft, medium, and hard, the elastic limit and ultimate strength will range about as follows:

	Soft.	Medium.	Hard.
Elastic limit, lbs/in ²	30-35,000	35-40,000	50-60,000
Ultimate strength, lbs/in ² ..	50-60,000	60-70,000	80-100,000

In some forms of rods used the elastic limit is artificially raised by cold working.

36. Modulus of Elasticity.—The modulus of elasticity of all grades of steel is very nearly the same and will be taken at 30,000,000 lbs/in².

37. Elastic Elongation.—As bearing upon deformations the elongation of the steel at its elastic limit will be here noted. Using the above value of the modulus of elasticity the elongation per unit length of the three grades of steel at their elastic limit will be as follows:

Soft.....	0.0010-0.0012
Medium.....	.0012- .0013
Hard.0017- .0020

38. Coefficient of Expansion.—The coefficient of expansion of steel may be taken at .0000065 per 1° F.

PROPERTIES OF CONCRETE AND STEEL IN COMBINATION.

39. Adhesion of Concrete and Reinforcing-bars.— The high value of the tangential adhesion, or grip, of concrete to steel rods embedded therein has long been known and has been utilized in the placing of anchor-rods, etc. It is somewhat remarkable, however, that only recently has this property been made use of in the design of combination structural forms. Experience has shown this adhesion to be sufficiently reliable and permanent to be utilized in such combination structures, and plain smooth bars have been entirely successful. Bars of irregular section in which adhesion is not entirely depended upon for the bond are also used to a large extent. Some form of mechanical bond is necessary where the adhesion area is deficient, and some engineers consider such a bond desirable in all cases.

Numerous tests have been made by various experimenters to determine the adhesion between concrete and plain rods of different forms, with results varying from about 200 to about 750 lbs/in². The adhesive strength is largely frictional resistance and varies greatly with the roughness of the bars. It also varies with the quality of the concrete and the method of conducting the test. Usually the test is made by embedding the rod in a block of concrete and pulling it therefrom, the rod being stressed in tension and the concrete in compression. This causes a maximum of elongation in the steel at the point where it enters the concrete, while the concrete is subjected to a maximum compression at this same point. This brings very unequal stresses upon the adhering surfaces, tending to a progressive separation until the entire rod has started to slip, after which friction alone holds the rod. This unequal action is greater the deeper the embedment. If the rod is *pushed* out, both rod and concrete are compressed, although not the same

amount at the same point. Tests made in this way should therefore give higher results than where the rods are pulled out. Experimental results accord in general with these principles.

In a beam, conditions are more favorable than in tests conducted by either method, as both steel and concrete are elongated, thus tending to distribute the stress more equally. Results of tests made in the usual way may then be taken as well within the limit of what may be expected in a beam.

The following table contains in condensed form the results of the most important tests on adhesion:

TABLE NO. 4.

ADHESION TESTS.

Authority.	Kind of Concrete.	Steel Rods.		Depth Embedded, Inches.	Adhesive Strength, lbs./in ² .
		Kind.	Size, Inches.		
Feret; <i>Ciment Armé</i> , p. 755.	1:2:4	Plain round	0.8	2 $\frac{3}{4}$	237
	1:2:5	" "	0.8	2 $\frac{3}{4}$	190
	1:3:4 $\frac{1}{2}$	" "	0.8	2 $\frac{1}{2}$	237
	1:3:6	" "	0.8	2 $\frac{3}{4}$	195
Hatt; <i>Proc. Am. Soc. Test Mat.</i> , 1902.	1:2:4	Plain round	$\frac{5}{16}$	6	756
	1:2:4	" "	$\frac{5}{16}$	6	636
Emerson; <i>Eng. News</i> , Vol. LI, 1904, p. 222.	1:3	Plain round	$\frac{1}{2}$	6	512
	1:3	Plain flat	$\frac{1}{2} \times 1$	6	293
	1:2:4	Plain square	1×1	10	587
	1:3:6	" "	1×1	10	478
Talbot; <i>Bull. No. 8, Univ. of Ill.</i> , 1906.	1:2:4	Plain round	$\frac{1}{2}$ and $\frac{5}{8}$	6	438
	1:2:4	" "	$\frac{1}{2}$ and $\frac{5}{8}$	12	409
	1:3:5 $\frac{1}{2}$	" "	$\frac{1}{2}$ and $\frac{5}{8}$	6	364
	1:3:5 $\frac{1}{2}$	" "	$\frac{1}{2}$ and $\frac{5}{8}$	12	388
	1:3:5 $\frac{1}{2}$	Cold rolled shafting	1 and $\frac{1}{2}$	6	146
	1:3:5 $\frac{1}{2}$	Mild steel flat	$\frac{3}{8} \times 1\frac{1}{2}$	6	125
	1:3:6	Tool-steel round	$\frac{3}{4}$	6	147
Withey; <i>Bull. Univ. of Wis.</i> , 1907.	1:2:4	Plain round	$\frac{3}{16}$ to $\frac{1}{2}$	6	401
	1:2:4	" "	$\frac{3}{16}$	6	504

Tests at the University of Wisconsin gave the following results for rods of different sizes and for 6-inch depth:

$\frac{3}{8}$ in.	329 lbs/in ²	$\frac{1}{8}$ in.	387 lbs/in ²
$\frac{1}{4}$ "	535 "	$\frac{5}{8}$ "	391 "
$\frac{3}{8}$ "	454 "	$\frac{3}{4}$ "	327 "
$\frac{1}{2}$ "	382 "		

These results show little or no effect due to difference in size.

Feret found an increase of strength at age of two years of about 50% over that at three months, and a maximum value for quite wet concrete; further, that a small amount of corrosion increased the value. Bach found smaller values the greater the depth, the average value for a 4-inch minimum depth in 1:4 gravel concrete, 3 months old, being 470 lbs/in². He also found greater values when the rods were pushed out than when pulled out.

Hatt found a frictional resistance, after starting, of 50% to 70% of the initial strength, and Mörsch reports such resistance as about two-thirds the initial. Talbot determined the frictional resistance in a large number of tests, finding it to range quite uniformly from about 55% to 65% of the initial or bond strength, in the case of plain round or flat rods. In the case of cold-rolled steel the friction was only 40% of the bond strength.

A study of the various results leads to the conclusion that for ordinary round or square bars, not too smooth, the adhesive strength may be taken at from 300 to 400 lbs/in², with a frictional resistance of about two-thirds this amount; a much smaller value must be taken for very smooth bars and also for flat bars.

40. Mechanical Bond.—The bond strength of bars with indented surfaces depends upon the adhesive resistance and the shearing strength of the concrete. Under heavy stresses there is also a tendency for the concrete to split, owing to the tensile stresses developed. The bars cannot be pulled through the concrete without shearing off an area equal to the total

area of the indented portion and in addition overcoming considerable friction or adhesion. If one-half the area is indented, the bond strength can then be placed at least equal to one-half the shearing strength (see Art. 22), or about one-fourth the compressive strength of the material. For a 1:2:4 concrete this would equal 500 to 600 lbs/in². In tests of such bars failures have usually occurred by the splitting of the specimen or the breaking of the bar, but the results indicate that the actual bond strength is fully equal to the above figures.

An important phase of the question of bond relates to the amount of movement which may take place under loads below the ultimate. Tests made on smooth, twisted, and corrugated bars and reported by Mr. T. L. Condron* showed that in the case of the plain bars and most of the twisted bars the ultimate strength was very nearly reached under a movement of $\frac{1}{100}$ inch. In the case of the corrugated bars the load causing ultimate failure (usually due to the splitting of the concrete) was in some cases considerably beyond that giving a movement of $\frac{1}{100}$ inch. The actual stress for $\frac{1}{100}$ inch of movement was 400–600 lbs/in² for the corrugated bars, 250–400 lbs/in² for the twisted bars, and 175–300 lbs/in² for the smooth bars. These results for smooth bars are notably less than most of those given in Table No. 4.

41. Ratio of Moduli of Elasticity, $E_s:E_c$.—So long as the adhesion between steel and concrete is unimpaired the distortion of the two materials will be equal. Their stresses will then be proportional to the moduli of the elasticity for the load in question, or as the ratio of $E_s:E_c$. Taking E_s at 30,000,000 and E_c at from 2,000,000 to 3,000,000, the ratio varies from 15 to 10. In practice various values of this ratio are used. As will be seen in Chapter IV, the value 15 corresponds closely to actual determinations of neutral axes in beams. It is the value commonly used in German regulations and is also used in the building laws of some American cities.

* Jour. West. Soc. Eng., 1907, Vol. XII, p. 100.

A value of 12 is also common and from the values of E_c obtained from compression tests as given in Art. 24, the lower value would seem to be more nearly correct.

The effect of a variation in this ratio is relatively small. Thus a compression member containing 1% of steel, and with a working stress in the concrete of f_c , will have a strength of $P = f_c A + f_c (E_s/E_c) .01 A$, where A = area of concrete. If $E_s/E_c = 12$, $P = f_c A (1.12)$; if $E_s/E_c = 15$, $P = f_c A (1.15)$, an increase of only 2.7% for a change in E_s/E_c of 25%.

Equal ratios of moduli may be assumed for both tension and compression.

42. Tensile Strength and Elongation of Concrete when Reinforced.—We have seen that plain concrete has an ultimate tensile strength of about 200 lbs/in² and a total elongation of perhaps $1/7000$ part, corresponding to a value of 1,400,000 for E_c . Steel stretches this amount under a stress of $30,000,000/7000 = 4300$ lbs/in². Again, the safe working tensile stress of concrete is about 50 lbs/in², and if we use a value of $E_s/E_c = 15$, the corresponding stress in the steel will be but 750 lbs/in². From these relations it is evident that in reinforced tension members we must either use very low and uneconomical working stresses for steel, or else expect the concrete to be of no assistance in carrying stress.

In studying the behavior of reinforced concrete under tension, and especially when constituting the tensile side of a beam, results of some experiments indicate that the concrete in this condition elongates more before final rupture occurs than when not reinforced, and that the resistance of the concrete is nearly constant and at its maximum value for some time previous to rupture. The first to announce this principle was Considère, whose tests indicated that the ultimate stretch of reinforced concrete was as much as ten times that of plain concrete. Kleinlogel,* however, was unable to check these results, he finding an elongation of practically

* Beton u. Eisen, No. 2, 1904.

the same amount as for plain concrete. In experiments of this sort it is extremely difficult to determine just when the concrete begins to crack. The steel forces it to elongate practically uniformly, even after rupture begins, so that a crack will open up very slowly and will therefore remain almost invisible for some time.

In some experiments made at the University of Wisconsin in 1901-2 a very delicate method of detecting incipient cracks was accidentally discovered. It was found that beams cured in water which were only partially dried before testing would, when tested, show very fine hair-cracks at an early stage, and moreover, by watching closely, it was observed that preceding the appearance of a crack there would appear a dark wet line across the beam. Such a line would soon be followed by a very fine crack. A larger series of tests were undertaken in the following year by a different set of experimenters, who observed the same phenomenon. Careful measurements of extension showed that these streaks or "water-marks", as they were named, occurred at practically the same deformation at which the concrete ruptured when not reinforced. Some of the results are given in Table No. 5.* The beams were of 1:2:4 mixture by weight and were 6"×6" in cross-section by 60 inches span.

That these water-marks were incipient cracks was determined by sawing out a strip of concrete along the outer part of the beam. Fig. 8. is a photograph showing the results of this experiment. Very close observation also in many cases showed hair-like cracks appearing very soon after the appearance of the water-marks.

Comparing the observed and calculated elongations of the reinforced concrete with those of the plain concrete at rupture it will be seen that the initial cracking in the former occurs at an elongation practically the same as reached by the latter at rupture.

* Bulletin No. 4, Engineering Series, Univ. of Wis., 1906.

TABLE NO. 5.

TESTS OF BEAMS SHOWING EXTENSIBILITY OF CONCRETE.

No.	Age.	Method of Loading.	Proportionate Extension.		Compressive Strength of Cubes, lbs/in ² .
			At First Water-mark.	At First Visible Crack.	
8	3 months	At third points	.00011	.00064	4250
10	"	"	.00024	.00046	2500
22	"	"	.00025	.00065	2775
26	"	"	.00016	.00056	3000
30	"	"	.00012	.00064	2600
7	1 month	At center	.00015	.00036	3500
5	"	"	.00020	.00031	3500
13	"	"	.00009	.00011	2350
23	"	"	.00020	.00060	2500
35	"	"	.00013	.00053	3150
2*	"	"		At rupture	
1*	"	"		.00013	3000
				.00010	2500

* Nos. 2 and 1 were plain concrete beams. The extensions of the beams loaded at the third points were measured by extensometers; those of the center loaded beams were calculated from deflections.




FIG. 8.

It should be said that in many cases the first "water-marks" did not extend entirely across the beam (the beam was observed on the tension face), so that presumably the concrete as a whole would still possess some tensile strength. It would seem, however, that these experiments on a large number of beams show quite clearly that the initial failure begins at the same elongation as in plain concrete. In the plain concrete total failure ensues at once; in the reinforced concrete rupture occurs gradually, and many small cracks may develop simultaneously, so that the total elongation at final rupture will be greater than in the plain concrete. In other words, the steel develops the full extensibility of a non-homogeneous material that otherwise would have an extension corresponding to the weakest section.

The presence of these cracks of course seriously affects the tensile strength of the concrete, and as they appear at an elongation corresponding to a stress in the steel of 5000 lbs/in² or less, it would seem that no allowance should be made for the tensile resistance of the concrete.*

It will be assumed therefore in this work that the strength of concrete in tension may be considered only when the deformations are well within the ultimate deformations of plain concrete. Assuming a maximum value of the tensile stress of 200 lbs/in², and a value of $E_s/E_c = 15$, the corresponding stress in the steel would be $200 \times 15 = 3000$ lbs/in². Usually the steel is stressed to 10,000 lbs/in² or more, in which case it must be assumed that the concrete is more or less ruptured and of no value as a tension member.

In practical design the most important question which arises is how far a concrete may be cracked without exposing the steel to corrosive influences. In this respect it seems to the authors that the minute cracks which appear in the early stages of the tests can have very little influence.

43. Relative Contraction and Expansion.—Temperature changes affect both the steel and the concrete. But as the coefficient of expansion of steel is .0000065 and of concrete

* These conclusions have recently been further substantiated by Bach. See Zeit. Ver. Dt. Ing., 1907.

.000006, the two materials will be but slightly stressed because of any difference in their rates of expansion.

The effect of shrinkage in hardening is more serious. As shown in Art. 29, the hardening of concrete is accompanied by more or less contraction if in air, or expansion (to a less degree) if in water. Concrete which is unrestrained either by steel reinforcement or by exterior attachment will shrink or swell proportionally and no stresses will thereby be developed. If restrained by reinforcing material only, a shrinkage will develop tensile stresses in the concrete and compressive stresses in the steel.

If it be assumed that concrete when reinforced tends to shrink the same amount as plain concrete, and that such shrinkage is prevented only so far as the stresses developed in the steel react upon the concrete and cause an opposite movement, then it will be found, using the ordinary values of the modulus of elasticity, that the stresses developed in both the concrete and the steel will be large. These stresses would be determined as follows:

Let c = coefficient of contraction of the concrete;

f_c = unit stress in concrete (tensile);

f_s = unit stress in steel (compressive);

p = steel ratio;

$n = E_s/E_c$.

Then the net contraction per unit length as measured by the concrete will be $c - f_c/E_c$, and as measured by the steel will be f_s/E_s . These values are equal. Also, for equilibrium, $f_c = pf_s$. From these equations we get

$$f_c = cE_c \frac{np}{1 + np} \quad (1)$$

and

$$f_s = \frac{f_c}{p} \quad (2)$$

If, for example, $c = .0003$, $E_c = 2,000,000$, $n = 15$, $p = 1\%$, then $f_c = 80$ lbs/in² tension and $f_s = 8000$ lbs/in² compression. If $p = 2\%$, $f_c = 140$ and $f_s = 7000$ lbs/in².

It is doubtful if such large initial stresses actually occur in reinforced concrete due to shrinkage in hardening.

The experiments of Considère on the actual contraction of reinforced concreté, already quoted in Art. 29, indicate that the deformation is less than the above theory would call for. For example, the observed contraction of .01% of reinforced mortar would call for a stress in the steel of only about 3000 lbs/in², and in the concrete of only 30 to 60 lbs/in². In slowly hardening, with the steel in place, there is probably a gradual adjustment in the concrete which results in less internal stress than the experiments on plain concrete would indicate. Where the structure is restrained by outside supports which are relatively more rigid than the reinforcing steel, the stresses in the concrete become greater and may easily reach the limit of the tensile strength, thus causing cracks. (For further discussion of reinforcement under such conditions, see Chapter V, Art. 142.)

CHAPTER III.

GENERAL THEORY.

44. Kinds of Members.—Structural members are, for convenience, usually divided into *tension members*, *compression members*, and *beams*, according as the forces to be resisted produce in the member simple tension, simple compression, or simple bending. Bending moment is often accompanied by tension or compression, producing what are called *combined stresses of bending and tension*, or *bending and compression*. Since reinforced concrete is not used for plain tension members the analysis will be confined to the beam, both under plain bending and under combined stresses, and to the compression member or column. The flat slab supported on four sides will be considered as a special case of beam. In reinforced-concrete construction the beam is the most important element, being used under a great variety of conditions.

45. Relation of Stress Intensities in Concrete and Steel. In the following discussion it will be assumed that the concrete and steel adhere perfectly and therefore deform equally. Nearly all reinforced-concrete construction is dependent upon this equal action of the two materials, although simple adhesion is not always entirely depended upon. Many types of deformed, or roughened, bars are used so as to give the steel a grip independent of the adhesion, and in other cases bars are bent or anchored at the ends, but in all cases it is assumed that the materials adhere perfectly and therefore deform equally. Many tests show that under proper design this is for all practical purposes true.

Since the modulus of elasticity of a material is the ratio of stress to deformation, it follows that for *equal* deformations the stresses in different materials will be as their moduli of elasticity. If

f_s = unit stress in steel,

f_c = unit stress in concrete,

E_s = modulus of elasticity of steel, and

E_c = modulus of elasticity of concrete,

we have the fixed relation

$$f_s/f_c = E_s/E_c. \quad (1)$$

46. Distribution of Stress in a Homogeneous Beam.—To assist in forming correct notions of the action of steel reinforcement in a concrete beam, it will be desirable to consider, at the outset, the nature of the stresses due to bending moment in a plain concrete or homogeneous beam of any material. Considering a vertical section at any point there will exist in general certain normal stresses (tensile and compressive) and certain tangential or shearing stresses. A knowledge of these stresses on a vertical section, together with the well-known principle that the shearing stress at any point is of equal intensity vertically and horizontally, is sufficient for the designing of ordinary beams.

In accordance with the common theory of flexure, the normal stress on a vertical section varies in intensity as the distance from the neutral axis, and therefore the variation is represented by the ordinates to a straight line as in Fig. 9.

The shearing-stress intensity is a maximum at the neutral axis and is zero at the outer fibres. At any given point in the section it is given by the equation

$$v = VS/Ib, \quad (1)$$

in which V denotes the entire shear at the section containing the point under consideration, I the moment of inertia of the section with respect to the neutral axis, b the breadth of the section at the point, and S the statical moment of the part of

the section above (or below) the point with respect to the neutral axis. For a rectangular beam the intensity of shear varies as the ordinates to a parabola, as shown in Fig. 10, the maximum value being $3/2$ times the average, or equal to $\frac{3}{2} \frac{V}{bd}$.

If the stresses on *inclined* planes are analyzed, it is found that the normal and shearing stresses will not be the same as on vertical planes; and, furthermore, that wherever shearing stress exists on a vertical plane the *maximum* normal stress



FIG. 9.



FIG. 10.

will not be on a vertical section, but on an inclined one. It is proved in treatises on mechanics that if f represents the horizontal unit tensile stress and v the vertical or horizontal unit shearing stress at any point in a beam, the maximum tensile stress will be given by the formula

$$t = \frac{1}{2}f + \sqrt{\frac{1}{4}f^2 + v^2}, \quad (2)$$

and the direction of this maximum tension is given by the formula $\tan 2\theta = 2v/f$, where θ is the angle of the maximum tension with the horizontal.

A study of these formulas shows that at all points in a beam where the shear is zero, the direction of the maximum tension is horizontal, as at points of maximum bending moment and along the outer fibres of the beam. Wherever the horizontal fibre stress is zero (at the neutral surface and at all sections of zero bending moment), the direction of the maximum tension is inclined 45° to the horizontal, and its intensity is equal to the unit shearing stress at the same place. Above the neutral axis of a section where the bending moment is not zero, the inclination of the maximum tension is greater than 45° , becom-

ing 90° at the upper or compressive fibre. Fig. 11 illustrates the variation in normal stress, shearing stress, and maximum tensile stress throughout the entire depth of a rectangular beam. The outer normal or fibre stress is assumed at 200 lbs/in^2 , and the shearing stress at the neutral axis at 150 lbs/in^2 . The




FIG. 11.—Showing Variation of Intensities of Normal Stress, Shear, and Maximum Tension.

variation in the fibre stress is shown by the straight line DE , and that in the shearing stress by the parabolic curve ACB . By means of eq. (2) the maximum tensile stresses have been computed; these are represented by the line $AHCJE$.

Fig. 12 illustrates the direction of the maximum tensile




FIG. 12.—Lines of Maximum Tension.

stresses in a rectangular beam. The exact direction at any point depends upon the relation between shear and bending moment. Lines of maximum compression would run at right angles to the lines shown and lines of maximum shear at angles of 45° therewith.

47. Purpose and Arrangement of Steel Reinforcement.—

The purpose of steel reinforcement is to carry the principal tensile stresses, the concrete being depended upon for the com-

pressive and shearing stresses, its resistance to such stresses being large. If no steel were present the concrete would tend to rupture on lines perpendicular to the direction of maximum tension, as shown in Fig. 12, and hence we may conclude that the ideal tension reinforcement would require the steel to be distributed in the beam along the lines of maximum tension. At the centre of the beam, or place of maximum moment, this direction is horizontal for the entire depth of the beam, and horizontal rods placed near the lower edge of the beam constitute proper and sufficient reinforcement. As we approach the ends of the beam, where the shear is large, the intensity of the inclined tensile stresses becomes of importance, and in many cases these stresses require special attention. Horizontal rods at the bottom are still necessary, but do not entirely reinforce the concrete against tension, so that special consideration must be given to reinforcement in the body of the beam. The arrangement of this reinforcement demands careful consideration.

For purposes of discussion, the subject of beams will first be treated with reference only to the horizontal reinforcement. The inclined tensile stresses will be considered separately.

48. The Common Theory of Flexure and its Modification for Concrete.—The common theory of flexure is based on two main assumptions, namely, (1) a plane cross-section of an unloaded beam will still be plane after bending (Navier's hypothesis); (2) the material of the beam obeys Hooke's law, which is, briefly stated, "stress is proportional to strain". From the first assumption it follows that—*The unit deformations of the fibres at any section of a beam are proportional to their distances from the neutral surface.* In the case of simple bending (all forces at right angles to the beam) the neutral axis lies at the centre of gravity of the section; in the case of bending combined with direct tension or compression, the neutral axis may lie in the section or be merely an imaginary line without the section. From the second assumption it follows that—*The unit stresses in the fibres at any section of a beam also are*

proportional to the distances of the fibres from the neutral surface. This may be called the linear law of the distribution of stress.

The linear law is the basis of all practical flexure formulas excepting some for reinforced-concrete beams. It is true that wrought iron and steel are the only important structural materials which closely obey Hooke's law, and they only within their elastic limits. But under working conditions these materials are not stressed beyond these limits, and so the formulas ordinarily hold. Timber, stone, and cast iron can hardly be said to obey Hooke's law, yet for working conditions the common flexure formulas for these materials are roughly correct and they are in general use.

In the case of those materials which do not obey Hooke's law, as concrete, and for all materials when stressed beyond their elastic limit, the common theory does not strictly apply. An exact analysis requires the use of the actual tension and compression stress-strain diagrams for the materials up to the limit of the actual stresses involved. It will be assumed still that plane sections remain plane during bending so that deformations will be proportional to the distances of the fibres from the neutral surface. The experiments by Talbot,* though not conclusive, bear out this assumption in the more important case of reinforced beams. Experiments by Schüle,† however, seem to show that original plane sections do not remain plane. Nevertheless Navier's hypothesis will probably remain a basis of flexure formulas for reinforced-concrete beams.

The variation of the normal stress on the cross-section can then be represented graphically in the following manner: Let Fig. 13*a* be the stress-strain diagram, compression above the x axis and tension below, for the material in question as determined by direct compression and tension tests. These curves are plotted with unit stresses as abscissas and unit strains as ordinates. Let Fig. 13*b* represent the beam, cut

* Univ. of Ill. Bull., Vol. II, No. 1, p. 28.

† Mitteilungen der Materialprüfungs-Anstalt am Polytechnikum in Zürich, Vol. X (1906), p. 40.

on section AB where the stresses are to be investigated. The neutral axis is at N . Since the deformations of the fibres are proportional to the distances of the fibres from the neutral axis, these distances themselves, $N1$, $N2$, $N3$, etc., will represent to some scale the deformations. If the unit deformation at point 1 is then represented by $N1$ the corresponding stress can be determined from the diagram of Fig. 13a, using the proper scale in both cases. Lay off the distance $1a$ to represent that stress. Proceeding similarly for all points and connecting, we have the stress curve $A'NB'$, which is nothing more than




FIG. 13.

a portion of the diagram of Fig. 13a plotted to a different scale.

49. Resisting Moment and Inefficiency of Concrete Beams.—For use in the following and other discussions on flexure three important principles from the mechanics of beams are now recalled:

(1) For beams rectangular in section, the average unit tensile and compressive fibre stresses on any cross-section are represented by the average abscissas in the tensile and compressive parts of the stress diagram, NBB' and NAA' , respectively (Fig. 13b). Also the whole tension T and whole compression C on the cross-section are proportional to the areas NBB' and NAA' ; hence, according to some scale, the areas represent T and C respectively.

(2) The resultant tension T and resultant compression C act through the centroids of the tensile and compressive areas in the stress diagram.

(3) When all the forces (loads and reactions) applied to

the beam act at right angles to it, then the resultant tension T equals the resultant compression C ; hence the two stresses constitute a couple—"the resisting couple".

Fig. 14 is a stress-strain diagram of a gravel concrete for both tension and compression.



FIG. 14.

made of this concrete, the stress diagram is a certain part of the stress-strain diagram, the exact part depending on the loading. Suppose that the loads produce in the lower fibre at the section in question a unit stress represented by bb' say, then T is represented by Nbb' and C by an area Naa' determined from the principle that it must equal the area Nbb' .

Hence the stress diagram is

$aa'Nb'b$, and the unit stress on the upper fibre is represented by aa' . Furthermore, ab represents the depth of the beam, and N the position of the neutral axis. Likewise, when the unit stress on the lower fibre is BB' (the ultimate tensile strength) and the beam is on the point of failing, T is represented by the area NBB' , and C by the equal area NAA' ; hence the stress diagram for the failure stage is $AA'NB'B$, and the unit stress on the upper fibre is AA' .

50. Resisting Moment.—The resisting moment of a section is the moment of the resisting couple which acts at that section. Its value is the product of the tension (or compression) and the distance between the centroids of these stresses. For example, at the failure stage of the beam above referred to the average unit tensile stress scales 128 lbs/in², and $\overline{NB} = 0.6\overline{AB} = 0.6d$, d denoting depth of beam. Hence if b denotes the breadth of the section,

$$C = T = 128 \times 0.6d \times b = 76.8bd.$$

The vertical distance between the centroids of the shaded parts (NAA' and NBB') of the diagram is $0.64\bar{A}B$; hence the arm of the resisting couple is $0.64d$, and the computed ultimate resisting moment of a beam made of the concrete under consideration is $76.8bd \times 0.64d = 49.2bd^2$ in-lbs., b and d to be expressed in inches.

Partly to test the correctness of the theory of flexure of concrete beams, Professor Mörsch* made three beams 15×20 cm. in section and several tension and compression specimens of the same mix of concrete. From tests on the specimens he obtained a stress-strain diagram from which he computed the probable resisting moment of the beams to be $3.45bd^2 = 3.45 \times 15 \times 20^2 = 21,700$ kg-cm. The average of the actual resisting moments of the beams (determined from tests to destruction) was 22,100 kg-cm., an agreement to be regarded as highly satisfactory.

The working resisting moment of a rectangular beam can be computed from the stress-strain diagram for the material in this same manner. Fortunately, engineers are not called upon to compute resisting moments by this method. It is here set forth principally as a means of introducing important ideas bearing on reinforced-concrete beams.

51. Inefficiency of Concrete Beams.—When a beam of the concrete above referred to is loaded to the breaking point, the greatest unit compressive stress in the beam is the stress AA' , which is in this case about 375 lbs/in². This is very low compared to the ultimate compressive strength (2500 lbs/in²), and the difference indicates a wasteful use of concrete.

The unshaded portion of the stress-strain diagram (Fig. 14) is also significant in this connection, for it indicates the unused compressive strength of the concrete above the neutral surface when the tensile strength of that below is fully developed and the beam is about to fail.

Another way to express the inefficiency of a concrete beam

* Der Eisenbetonbau.

is to compare its ultimate resisting moment with that which it would have if the tensile strength and elastic properties were the same as the compressive. On this supposition the tensile stress-strain diagram would be like the compressive; and for the concrete of Fig. 14, the ultimate C and T are represented by the area $NY Y'$, and the arm of the resisting couple by twice the vertical distance of the centroid of the area $NY Y'$ above N . Actual measurement of the area and distance gives $C=775bd$ and $arm=0.64d$; hence the ideal ultimate resisting moment is $775bd \times 0.64d = 496bd^2$ as against $49.2bd^2$, the actual value.

To supply the deficiency in tensile strength of concrete is the main purpose of steel reinforcement. A comparatively small amount of steel (rods or bars whose combined sectional area is from 1 to 2 per cent of the total sectional area of the beam) properly embedded will so strengthen the tensile side of the beam that the great strength of the compressive side can be utilized. The exact amount of steel required in any case depends on the elastic properties of the concrete and steel.

52. Varieties of Flexure Formulas.—Many formulas have been proposed for the strength of reinforced-concrete beams. The differences among them arise principally from three sources, namely: (1) The method of applying the factor of safety, (2) the law of distribution of the compressive fibre stress in the concrete, and (3) the value of the tensile fibre stress in the concrete. In regard to:

(1) Two views are held as to the proper method of applying the factor of safety. For example, to ascertain the safe load for a given beam, some engineers assume working strengths for the concrete and steel, with which, by means of a suitable flexure formula, they compute the safe load directly; other engineers compute the breaking load of the beam by a suitable formula and then, with reference to this load, they decide upon the safe load. (The pros and cons of these two methods are discussed in Art. 118.) Formulas for working conditions (for use in the first method) are explained in Arts. 54-9; those

for ultimate conditions (for use in the second method) in Arts. 60-4; and those for both conditions in Arts. 65-70.

(2) As already explained in Art. 48, the distribution of the compressive fibre stress can be represented by a portion of the stress-strain diagram for the concrete. As shown in Art. 23, the stress-strain curve for concrete up to and even beyond working stresses is nearly straight, and the most widely used flexure formulas for working conditions are based on the assumption that the stress-strain curve is practically straight up to working stresses. Formulas of Arts. 54-9 and all other flexure formulas of this book (except those of Arts. 60-70) are based on this assumption. When the curvature of the stress-strain curve has been taken into account, it has generally been assumed to be an arc of a parabola, the vertex




FIG. 15.—Distribution of Fibre Stress in Concrete According to Various Assumptions.

being taken, by some, at the end of curve (the ultimate strength end) and, by others, beyond that point. The formulas of Arts. 60-70 are based on a parabolic stress-strain curve, the vertex being at the end.

(3) As explained in Art. 42, when a reinforced-concrete beam is being loaded, the concrete adjoining the steel fails (cracks) probably always before the stress in the steel reaches 5000 lbs/in², and when the stress reaches working values the cracks will have extended well-nigh to the neutral surface. The amount of tension remaining in the concrete at the section

of the crack is comparatively small, and this tension being near the neutral surface, the resisting moment due to it is also small compared to that due to the tension in the steel. In a certain formula for ultimate resisting moment in which this residual tension in the concrete is allowed for, the value of the term expressing the contribution of this tension is less than $\frac{1}{2}$ per cent of the total moment. It is the almost universal practice to neglect this tension entirely in flexure formulas; this practice is followed in this book.

An idea of the variety of flexure formulas proposed can be gained from Fig. 15, which shows nine distributions of fibre stress in the concrete according to as many different formulas.

53. Notation.—Fuller explanations of some of these symbols are given in subsequent articles where the formulas are derived; see also Fig. 16.

f_s	denotes unit fibre stress in steel;
f_c	“ “ “ “ “ concrete at its compressive face;
e_s	“ “ elongation of the steel due to f_s ;
e_c	“ “ shortening of the concrete due to f_c ;
E_s	“ modulus of elasticity of the steel;
E_c	“ “ “ the concrete in compression;
n	“ ratio E_s/E_c ;
T	“ total tension in steel at a section of the beam;
C	“ total compression in concrete at a section of the beam;
M_s	“ resisting moment as determined by steel;
M_c	“ resisting moment as determined by concrete;
M	“ bending moment or resisting moment in general;
b	“ breadth of a rectangular beam;
d	“ distance from the compressive face to the plane of the steel;
k	“ ratio of the depth of the neutral axis of a section below the top to d ;
j	“ ratio of the arm of the resisting couple to d ;
A	“ area of cross-section of steel;
p	“ steel ratio, A/bd .

54. Flexure Formulas for Working Loads Based on Linear Variation of the Compression and Neglecting Tension in the Concrete.—The loads being working loads, the unit stress in the steel is within the elastic limit, and the unit stresses in the concrete vary as the ordinates to the compressive stress-strain curve for concrete up to working stresses. This curve is nearly straight; it will be assumed straight to simplify the formulas. The resulting errors are small, as is explained in Art. 70.

55. Neutral Axis and Arm of Resisting Couple.—It follows from the assumption of plane sections that the unit deformations of the fibres vary as their distances from the neutral axis; hence, $e_s/e_c = (d - kd)/kd$ (see Fig. 16). Also $e_s = f_s/E_s$ and $e_c = f_c/E_c$; hence, introducing the abbreviation n ,

$$\frac{f_s}{nf_c} = \frac{d - kd}{kd} = \frac{1 - k}{k} \quad (a)$$




FIG. 16.

When the loads and reactions are vertical—beam horizontal

—the total tension and compression on the section are equal, i.e.,

$$f_s A = \frac{1}{2} f_c b k d. \quad (b)$$

Eliminating f_s/f_c between equations (a) and (b) and introducing the abbreviation p gives $2pn(1 - k) = k^2$; this if solved for k gives

$$k = \sqrt{2pn + (pn)^2} - pn. \quad (1)$$

This formula shows that the neutral axes of all beams of a given concrete and of a given percentage of reinforcement are at the same proportionate depth, k , for all working loads. The lower group of curves in Fig. 17 gives k for different values of p and n ; thus for $p = 0.015$ (percentage of steel = 1.5) and $n = 15$, $k = 0.48$. The curves show that k increases as p or n increases.

The distance of the centroid of the compressive stress from the compressive face of the beam is $\frac{1}{3}kd$; therefore the arm of the resisting couple, TC , is given by

$$jd = d - \frac{1}{3}kd, \quad \text{or} \quad j = 1 - \frac{1}{3}k. \quad \dots \dots (2)$$

As k increases, j decreases, but not in the same ratio. Fig. 17 shows how j changes with p for four different values of n . It should be noticed that j does not vary much with p , and that for $n=15$ and p between 0.75 and 1.0%—common values—the average value of j is about $\frac{7}{8}$.

56. Resisting Moment for Given Working Stresses f_s and f_c .— If the beam is under-reinforced, its resisting moment depends on the steel and its value then is

$$M_s = T \cdot jd = f_s A \cdot jd = f_s p j b d^2. \quad \dots \dots (3)$$

If over-reinforced, the resisting moment depends on the concrete and its value then is

$$M_c = C \cdot jd = \frac{1}{2} f_c b k d \cdot jd = \frac{1}{2} f_c k j b d^2. \quad \dots \dots (4)$$

To find the resisting moment in a given case, these values of M must be compared, and the lesser one taken; but it may be noticed that a comparison of the quantities $f_s p$ and $\frac{1}{2} f_c k$ is sufficient to determine which of the values is the lesser.

For approximate computations one may use the average values $j = \frac{7}{8}$ and $k = \frac{3}{8}$; then formulas (3) and (4) become respectively

$$M_s = f_s A \cdot \frac{7}{8} d, \quad \dots \dots (3)'$$

$$M_c = f_c \cdot \frac{3}{8} b d^2. \quad \dots \dots (4)'$$

57. Unit Fibre Stresses for a Given Bending Moment.— Formulas for these may be obtained from equations (3) and (4) by solving them for f_s and f_c respectively; M will denote bending moment. Or, one may reason as follows: Since the resisting moment is Tjd ,

$$T = \frac{M}{jd} \quad \text{and} \quad f_s = \frac{T}{A}; \quad \dots \dots (5)$$




FIG. 17.

also, since f_c equals twice the average unit compressive stress on the section, and $C=T$,

$$f_c = \frac{2T}{kbd} = \frac{2f_s p}{k} \quad \dots \dots \dots (6)$$

Approximating as before, i.e., using average values $j = \frac{7}{8}$ and $k = \frac{3}{8}$, formulas (5) and (6) become respectively

$$T = \frac{M}{\frac{7}{8}d} \quad \text{and} \quad f_s = \frac{T}{A}, \quad \dots \dots \dots (5)'$$

and
$$f_c = \frac{2T}{\frac{3}{8}bd} = \frac{16}{3}f_s p. \quad \dots \dots \dots (6)'$$

58. Determination of Amount of Steel and Cross-section of Beam for a Given Bending Moment.—If k be eliminated between equations (a) and (6), the following formula for steel ratio results:

$$p = \frac{1/2}{\frac{f_s}{f_c} \left(\frac{f_s}{nf_c} + 1 \right)} \quad \dots \dots \dots (7)$$

It shows that for given concrete and ratio of working stresses, p has the same value for all sizes of beams. Fig. 18 gives graphically the proper values of p for different ratios f_s/f_c and four different values of n .

If a value of p less than that given by (7) is adopted then the cross-section, or bd^2 rather, should be determined from the first of equations (8); if greater, from the second. (These are (3) and (4) solved for bd^2 respectively.)

$$bd^2 = \frac{M}{f_s p j}, \quad bd^2 = \frac{M}{\frac{1}{2} f_c k j} \quad \dots \dots \dots (8)$$

Values of k and j can be obtained from (1) and (2) or Fig. 17; then inserting an assumed value of b , d can be obtained by direct solution of the formula.

For Approximate Design.—To determine the percentage of steel, use (6)' in this form, $p = \frac{1}{16} f_c / f_s$. If a smaller percentage than this is decided upon, use the first of equations (8)' to determine b and d ; and if a larger then the second one.

$$bd^2 = \frac{M}{\frac{7}{8} f_s p}, \quad bd^2 = \frac{M}{\frac{1}{6} f_c} \quad \dots \dots (8)'$$

59. Diagrams and Examples.—Some numerical examples illustrating the preceding principles will now be given, and




FIG. 18.

then some diagrams will be explained by means of which computations in such examples can be wholly avoided or nearly so.

(1) A concrete beam is 10×16 inches in cross-section and the tension reinforcement consists of four $\frac{3}{4}$ inch steel rods, their centres being two inches above the lower face of the beam. The working stress of the concrete being 600 lbs/in² and that of the steel 15,000, what is the safe resisting moment of the beam?

Solutions. The cross-section of one steel rod is 0.442 in², hence $A = 1.768$; and as $b = 10$ and $d = 14$, $p = 1.768/140 = 0.0126$. Therefore, n being taken as 15, from (1) $k = 0.453$; also from (2) $j = 0.849$. As determined by the steel, the resisting moment is (see eq. 3)

$$M_s = 15,000 \times 1.768 \times 0.849 \times 14 = 315,000 \text{ in-lbs.}$$

As determined by the concrete, the resisting moment is (see eq. 4)

$$M_c = 300 \times 10 \times 0.453 \times 14 \times 0.849 \times 14 = 227,000 \text{ in.-lbs.}$$

The safe resisting moment is the latter value.

The approximate formulas, (3)' and (4)', give respectively

$$M_s = 15,000 \times 1.768 \times \frac{7}{8} \times 14 = 325,000$$

and

$$M_c = 600 \times \frac{7}{8} \times 10 \times 14^2 = 196,000 \text{ in.-lbs.}$$

The approximate formula relating to the steel always gives a closer result than the other.

(2) Suppose that the beam of the preceding example is 19 in. deep and is subjected to a bending moment of 350,000 in.-lbs. Compute the greatest unit stresses in the steel and concrete.

Solutions. The steel ratio is $1.768/170 = 0.0104$; and with $n = 15$, eq. (1) gives $k = 0.424$, and eq. (3) gives $j = 0.859$. Therefore $T = 350,000/0.859 \times 17 = 24,000$ lbs., and $f_s = 24,000/1.768 = 13,600$ lbs/in². Also see eq. (6), $f_c = 48,000/0.424 \times 10 \times 17 = 665$ lbs/in².

The approximate formulas (5)' and (6)' give respectively

$$f_s = 13,500 \quad \text{and} \quad f_c = 750 \text{ lbs/in}^2.$$

Again, of the approximate formulas, the one relating to the steel gives the closer result.

(3) A beam is to be figured to withstand a bending moment of 135,000 in.-lbs., the working strength of the concrete and steel being taken at 700 and 12,000 lbs/in² respectively.

Solutions. For $n = 15$, eq. (7) gives $p = 0.0136$. With this value of p , eq. (1) gives $k = 0.462$, and hence $j = 0.846$. Eq. (8) now gives

$$bd^2 = \frac{135,000}{12,000 \times 0.0136 \times 0.846} = 978.$$

Many different values of b and d will satisfy the last equation. If b is taken as 7 in., then

$$d^2 = 978/7 = 140, \quad \text{or} \quad d = 12 \text{ in.}$$

Finally

$$A = 0.0136(7 \times 12) = 1.14 \text{ in}^2.$$

The approximate formula 6' gives for a suitable steel ratio $p = \frac{1}{8} \times 700/12,000 = 0.0109$. Adopting 0.011, then 8' gives $bd^2 = 135,000/\frac{1}{8} \times 700 = 1157$. Taking $b = 7$ in. as before, $d^2 = 1157/7 = 165.3$, or $d = 12.8, 13$ in. say. Finally $A = 0.011 \times 7 \times 13 = 1.00 \text{ in}^2$.

The construction of the diagrams (Plates I-IV, pages 213 to 216) referred to will now be explained and then their use. It will be convenient to have names for the quantities $f_s p j$ and $\frac{1}{2} f_c k j$

(see eqs. 3 and 4) and single symbols for them. We shall call them *coefficients of resistance* relative to the steel and the concrete and will denote them by R_s and R_c respectively; that is,

$$(a) \quad R_s = f_s p j \quad \text{and} \quad (b) \quad R_c = \frac{1}{2} f_c k j.$$

Then the formulas for resisting moments of a given beam with particular working strengths f_s and f_c may be written thus:

$$M_s = R_s b d^2 \quad \text{and} \quad M_c = R_c b d^2. \quad . \quad . \quad . \quad (1)$$

Similarly for any particular beam subjected to a bending moment M ,

$$R_s = R_c = M / b d^2. \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Likewise for any particular bending moment and working strengths f_s and f_c , the necessary section is given by

$$b d^2 = M / R, \quad . \quad . \quad . \quad . \quad . \quad (3)$$

R being the smaller of the two coefficients of resistance.

In the four diagrams values of p are given at the upper and lower margins and values of R_s and R_c at the sides. The diagrams are drawn for four different values of n , i.e., 10, 12, 15, and 18, as noted on the plates.

The f_s curves of the diagrams are merely the plots, or graphs, of equation (a) for certain values of f_s as marked on the curves. The f_c curves are the graphs of equation (b) for various values of f_c as marked. For example, when $n=15$, $f_s=14,000$, $f_c=600$, and $p=1\%$ (see page 215), $R_s=120$ and $R_c=108$.*

The foregoing three examples will now be solved by means of the diagram, page 215 ($n=15$).

(1) The percentage of steel being 1.26, we first find that value on the lower margin; then trace vertically, stopping at the first of the two curves $f_c=600$ and $f_s=15,000$; then trace horizontally to either side

* These diagrams are modeled after those contributed by Prof. French in Trans. Am. Soc. C. E., Vol. LVI, 1906, pp. 362-4.

margin and read off the value $R=115$. Finally $M=115 \times 10 \times 14^2=225,400$ in.-lbs.

(2) $R=M/bd^2=350,000/10 \cdot 17^2=121$, and the percentage of steel is 1.04. We enter the diagram with these values of R and p , find the intersection of the horizontal and vertical lines through these values respectively, and from the steel and concrete curves adjacent to this intersection estimate f_s to be 13,750 and f_c 675 lbs./in².

(3) We first find the intersection of the curves $f_c=700$ and $f_s=12,000$; from that point tracing down we find $p=1.35\%$, and tracing horizontally we find $R=137$. Then $bd^2=M/R=135,000/137=986$, from which b and d may be decided upon, and then finally the amount of steel.

60. Flexure Formulas for Ultimate Loads, Based on Parabolic Variation of Compression and Neglecting Tension in Concrete.—It is assumed that the amount of reinforcement is sufficient to develop the full compressive strength of the concrete without straining the steel beyond its yield point; or otherwise expressed, failure occurs by crushing of the concrete, the stress in the steel being still within the yield point. Then the parabola representing the variation of compression is a full parabola (see Art. 26), the upper end (see Fig. 19) being the vertex.




FIG. 19.

If the amount of steel in a beam is such that the ultimate strength of the concrete and the elastic limit of the steel would be reached simultaneously if the beam were subjected to a gradually increasing load, then this will be called the ideal amount—no better term seems available—but this amount may not be the best in a given case.

In the present connection, the two following properties of a parabola like that of Fig. 19 are useful: (1) The average abscissa of the parabolic arc equals two-thirds the greatest, f_c ; (2) the distance from the centroid of the parabolic area to its top equals three-eighths the total height, kd .

61. Neutral Axis and Arm of Resisting Couple.—The “initial modulus of elasticity” of the concrete (Art. 24) is denoted by E_c in the present article. It is represented by the tangent of the angle between the vertical through N and the tangent to the stress-strain curve at N . And since NA represents e_o , it follows from a well-known property of the parabola that $f_c = \frac{1}{2}E_c e_o$. Also $f_s = E_s e_s$, and from the assumption of plane sections it follows that $e_s/e_o = (d - kd)/kd$. Eliminating e_s/e_o from the above equations, and introducing the abbreviation n , gives

$$\frac{f_s}{2nf_c} = \frac{1-k}{k} \quad \dots \dots \dots (a)$$

When the loads and reactions are vertical—beam horizontal—the total tension and the total compression on the section are equal, i.e.,

$$f_s A = \frac{2}{3} f_c b k d \quad \dots \dots \dots (b)$$

Eliminating f_s/f_c between equations (a) and (b) and introducing the abbreviation p , gives $3pn = k^2/(1-k)$; this if solved for k gives

$$k = \sqrt{3pn + (\frac{3}{2}pn)^2} - \frac{3}{2}pn \quad \dots \dots \dots (1)$$

This formula shows that the neutral axes of all beams of a given concrete and of a given percentage of reinforcement are at the same proportionate depth, k , for their respective ultimate loads. The lower group of curves (Fig. 20) gives k for different values of p and n ; thus for $p=2\%$ and $n=15$, $k=0.60$. The curves show that k increases as p or n increases.

The distance of the centroid of the compressive stress from the compressive face of the beam is $\frac{3}{8}kd$; therefore the arm of the resisting couple TC is given by

$$jd = d - \frac{3}{8}kd, \quad \text{or} \quad j = 1 - \frac{3}{8}k \quad \dots \dots \dots (2)$$




FIG. 20.

Plainly, as k increases j decreases, but not at the same rate. The upper group of curves in Fig. 20 gives j for different values of p and n ; thus for $p=2\%$ and $n=15$, $j=0.775$. It should be noticed that j does not vary much with p , and that for $n=15$ and p greater than 1% the average value of j is about 0.80.

62. Ultimate Resisting Moment for a Given Ultimate Strength f_c .—Remembering the assumption made at the outset in regard to the amount of steel (Art. 60), it will be understood that the ultimate resisting moment always depends on the concrete; the value is

$$M_c = C \cdot jd = \frac{2}{3} f_c bkd \cdot jd = \frac{2}{3} jk f_c b d^2. \quad . \quad . \quad . \quad (3)$$

It should be remembered that this equation gives the ultimate resisting moment only if when the unit stress in the concrete is at the ultimate that in the steel is not beyond the elastic limit.

If the beam has the "ideal amount" of reinforcement before referred to, then the ultimate resisting moment can be computed from the steel by means of

$$M = T \cdot jd = f_s A \cdot jd = f_s p j b d^2, \quad . \quad . \quad . \quad (4)$$

in which f_s denotes elastic limit of steel.

For approximate computations one may use the average values $j=0.80$ and $k=0.52$; with these, formulas (3) and (4) become respectively

$$M_c = 0.278 f_c b d^2, \quad . \quad . \quad . \quad . \quad (3)'$$

$$M_s = T 0.8 d = 0.8 f_s p b d^2. \quad . \quad . \quad . \quad (4)'$$

63. Determination of Amount of Steel and Cross-section of Beam for a Given Ultimate Bending Moment.—When a beam contains the "ideal amount" of steel, the values of M given by (3) and (4) are equal; hence, $f_s/f_c = 2k/3p$. If the value

of k as given by equation (a) be inserted in this equation, then the following formula for the "ideal steel ratio" results:

$$p = \frac{2/3}{\frac{f_s}{f_c} \left(\frac{f_s}{2nf_c} + 1 \right)} \quad \dots \quad (5)$$

This shows that p depends only on the ultimate strength of concrete and elastic limit of steel, and not at all on the size of beam. Fig. 21 gives graphically the "ideal ratio" p for




FIG. 21.

different values of the ratio f_s/f_c and four values of n ; thus for $f_s=34,000$, $f_c=1700$, and $n=15$, $p=1.93\%$.

If, in any given case, the steel ratio as given by (5), or a higher value, is adopted, then the concrete would crush without straining the steel beyond the elastic limit, and the ultimate resisting moment of the beam is given by (3), which value equated to the ultimate bending moment, M , to be provided for, gives $\frac{2}{3}f_c j k b d^2 = M$, or

$$b d^2 = \frac{M}{\frac{2}{3} f_c j k} \quad \dots \quad (6)$$

From this d may be computed for any assumed value of b . If a lower value than that given by equation (5) is adopted for p , then under a gradually increasing load the stress in the steel would reach the elastic limit before the concrete would crush, and the formulas of this article could not be used to compute the ultimate resisting moment of the beam. See Art. 67 for solution of this case.

Approximating as before, $j=0.80$ and $k=0.52$, and eq. (6) becomes

$$bd^2 = \frac{3.6M}{f_c} \quad \dots \dots \dots (6)'$$

64. Diagrams and Examples.—Two numerical examples will now be given to illustrate the foregoing principles, and then a diagram will be explained by means of which computations in such examples can be wholly or partially avoided.

(1) A concrete beam is 10×16 inches in cross-section and the tension reinforcement consists of four $\frac{3}{4}$ -in. steel rods, their centers being two inches above the lower face of the beam. The ultimate compressive strength of the concrete being 2000 and the elastic limit of the steel 40,000 lbs./in² compute the ultimate resisting moment of the beam.

Solutions. Here $p=0.0126$, and for $n=15$, eq. (1) gives $k=0.52$ and (2) gives $j=0.805$. Hence

$$M_c = \frac{2}{3} 0.805 \times 0.52 \times 2000 \times 10 \times 14^2 = 1,096,000 \text{ in-lbs.}$$

It remains to test whether the stress in the steel would be within the elastic limit, the beam being subjected to a bending moment of 1,096,000 in-lbs. This is done by dividing the bending moment by the arm of the resisting couple, which gives the whole tension in the steel, and then this tension by the area of the steel; thus

$$\frac{1,096,000}{0.805 \times 14} = 97,300 \text{ lbs.} = T$$

and

$$\frac{97,300}{1.768} = 55,000 \text{ lbs./in}^2 = f_s$$

This result being beyond the stated elastic limit, eq. (3) does not apply to the problem in hand. (The ultimate resisting moment can be computed by other methods. See ex. 2, page 76.)

(2) A beam is to be figured to safely withstand a bending moment of 135,000 in-lbs., the ultimate compressive strength of the concrete being taken at 2000 and the elastic limit of the steel at 40,000 lbs/in².

Solution. With $n=15$, eq. (5) gives as the "ideal steel ratio," since $f_s/f_c=20$,

$$p = \frac{2/3}{20(\frac{2}{3} + 1)} = 0.02.$$

For this value of p , eq. (1) gives $k=0.598$, and (2) gives $j=0.775$. With a factor of safety of 3, the ultimate bending moment is 405,000 in-lbs., and eq. (6) gives

$$bd^2 = \frac{405,000}{\frac{2}{3} \times 2000 \times 0.775 \times 0.598} = 656 \text{ in}^3.$$

Trying 6 inches for b , then $d^2=109.3$ or $d=10.5$ in.; also $A=0.02 \times 6 \times 10.5=1.26$ in².

The "coefficients of resistance" on the parabolic theory are $f_s p j$ and $\frac{2}{3} f_c j k$ (see equations 4 and 3), and using the symbols R_s and R_c , as in Art. 59,

$$R_s = f_s p j \quad \text{and} \quad R_c = \frac{2}{3} f_c j k.$$

The f_s curves of the diagram (Plate V, page 217) are graphs of the first equation for certain values of f_s as marked on the curves and $n=15$. (The curves for $n=12$ differ very little from these.) The f_c curves are graphs of the second equation for various values of f_c as marked; the full curves are for $n=15$ and the dotted for $n=12$.

In using the diagram to determine (1) the ultimate resisting moment of a given beam for a specified ultimate compressive strength of the concrete, or (2) a steel ratio and size of beam to withstand a given ultimate bending moment with specified compressive strength of concrete, these formulas respectively should be borne in mind:

$$M = R b d^2 \quad \text{and} \quad b d^2 = M / R.$$

The foregoing two examples will now be solved by means of the diagram.

(1) The percentage of steel being 1.26, we first find that value on the lower margin of the diagram, and then trace vertically to the line marked $f_c=2000$. We note that the point thus found is above the line

$f_s = 40,000$, the elastic limit of the steel of the beam, and hence conclude that the amount of steel in this beam is insufficient to develop the full compressive strength of the concrete without straining the steel beyond the elastic limit. If the elastic limit of the steel were as high as 55,000 lbs/in², we would trace horizontally from the point as found above to either side of the diagram and read $R = 552$. Then $M = Rbd^2 = 552 \times 10 \times 14^2 = 1,087,000$ in.-lbs., which is the ultimate resisting moment of this beam with the high elastic limit steel.

(2) We first find the intersection of the curves $f_c = 2000$ and $f_s = 40,000$; from that point tracing down we find $p = 2\frac{1}{2}\%$, and horizontally we find $R = 620$. Then $bd^2 = M/R = 405,000/620 = 654$, from which b and d can be decided upon, and finally the amount of steel.

65. Flexure Formulas for any Load up to Ultimate, Based on Parabolic Variation of Compression and Neglecting Tension in Concrete (After Talbot).—It is assumed that the stress in the steel is not above the yield point. The parabola representing the variation of compressive stress is not a "full one", that is, its top is not the vertex, see Fig. 22, unless




FIG. 22.

the maximum concrete stress is at the ultimate value. As heretofore f_c and e_c will denote the unit stress and strain respectively at the compressive face of the concrete, and as in Art. 61, E_c will denote the initial modulus of elasticity of the concrete. In this article f'_c and e'_c will denote these same quantities at the ultimate stage of the concrete, and q will be used as an abbreviation for e_c/e'_c . It can be shown from

the properties of a parabola that: (1) The average abscissa to the parabola NB is $(3-q)/3(2-q)$ times the greatest abscissa




FIG. 23a.




FIG. 23b.

f_c ; (2) the distance from the centroid of the parabolic area to the top AB is $(4-q)/4(3-q)$ times its height, kd ; and (3)

$$f_c = f_c'(2-q)q = \frac{1}{2}(2-q)E_c e_c. \quad \dots (a)$$

Fig. 23a shows graphically the relation between q and the ratio f_c/f'_c ; thus when $q = \frac{1}{4}$ (the concrete is strained to one-fourth its limit of compression) the unit stress in the concrete is about 0.45 of the ultimate strength.

The lines NB in Fig. 23b show the distributions of compressive stress at a section of a beam when q is $\frac{1}{4}$, $\frac{1}{2}$, $\frac{3}{4}$ and 1 respectively as marked. In each case N is the neutral axis and AB represents the unit stress on the remotest fiber. When q is $\frac{1}{4}$, the distribution is almost linear.

66. Neutral Axis and Arm of Resisting Couple.—As in Arts. 55 and 61, $e_s/e_c = (d - kd)/kd$, and $f_s = E_s e_s$. Eliminating e_s/e_c from these two equations and (a), and introducing the abbreviation n , gives

$$\frac{f_s}{nf_c} = \frac{2(1-k)}{k(2-q)}. \quad \dots \dots \dots (b)$$

When the loads and reactions are vertical—beam horizontal—the total tension and total compression on the section are equal, i.e.,

$$Af_s = bkd f_c (3-q)/3(2-q). \quad \dots \dots \dots (c)$$

Eliminating the ratio f_s/f_c between equations (b) and (c), and introducing the abbreviation p , gives $6pn(1-k) = k^2(3-q)$, which solved for k furnishes the following formula:

$$k = \sqrt{2 \frac{3pn}{3-q} + \left(\frac{3pn}{3-q}\right)^2} - \frac{3pn}{3-q}. \quad \dots \dots \dots (1)$$

It shows that the neutral axes of all beams of a given concrete and a given percentage of reinforcement are at the same proportionate depth, k , for any particular stage of loading as given by q . The lower group of curves in Fig. 24 shows how k depends on p and n for $q = \frac{1}{4}$, the value taken by Talbot as closely corresponding to the working stage. The lower




FIG. 24.

group of curves in Fig. 25 shows how k depends on q (that is, on the stage of loading) for several values of p , n being taken as 15. Thus when $p=0.01$ and $q=0$ nearly (load very small), $k=0.42$ and when $q=1$ nearly (ultimate load), $k=0.48$.

The distance of the centroid of the compressive stress from the top of the beam is $kd(4-q)/4(3-q)$; hence the arm of the resisting couple is given by $jd=d-kd(4-q)/4(3-q)$ or

$$j=1-\frac{k(4-q)}{4(3-q)} \dots \dots \dots (2)$$

The upper group of curves in Fig. 24 shows how j depends on p and n , for the stage $q=\frac{1}{4}$. The upper group of curves in Fig. 25 shows how j depends on q for several values of p , n being taken as 15. It should be noticed that j does not change much for considerable changes in q .

67. *Resisting Moment for Given Values of f_c and f_s .*—Whether the resisting moment is determined by the concrete or steel depends on the percentage of reinforcement; in a general way the higher percentages make the moment depend on the concrete and the lower on the steel. As depending on the concrete, the resisting moment is given by

$$M_c=Cjd=\frac{3-q}{3(2-q)}jkf_cbd^2 \dots \dots \dots (3)$$

The value of q to be used here must correspond with the f_c used, the relation between q and f_c being given by (a) of Art. 65. As depending on the steel, the resisting moment is

$$M_s=Tjd=f_sAjd=f_spbjd^2 \dots \dots \dots (4)$$

68. *Determination of Fibre Stresses f_s and f_c for a Given Bending Moment.*—Formulas for these can be obtained by solving (3) and (4) for f_c and f_s respectively; thus

$$\left. \begin{aligned} f_c &= \frac{3(2-q)}{(3-q)} \frac{M}{jkb d^2} \\ f_s &= \frac{M}{pjb d^2} \end{aligned} \right\} \dots \dots \dots (5)$$




FIG. 25.

Neither f_c nor f_s can be determined directly from these, for each formula contains q (j and k depend on q), which is an unknown in the problem in hand. An estimated value of q must be used for a trial solution of (5), and then with the value of f_c thus found a better value of q may be obtained from (a) or from Fig. 23, which value may be used in a second trial solution.

69. *Determination of Amount of Steel and Cross-section of Beam for a Given Bending Moment.*—In order that the maximum unit compression in the concrete, f_c , and the unit stress in the steel, f_s , may have certain definite values when the beam is subjected to a given bending moment, a certain definite percentage of steel must be used. This percentage is such as makes the values of the resisting moment as determined by steel and concrete equal. Thus equating values of M from equations (3) and (4) and simplifying,

$$p = (3 - q)kf_c/3(2 - q)f_s.$$

Inserting in this the value of k furnished by (b) gives

$$p = \frac{3 - q}{3(2 - q)} \frac{1}{\frac{f_s}{f_c} \left(\frac{2 - q}{2n} \frac{f_s}{f_c} + 1 \right)} \dots \dots \dots (6)$$

In this also the value of q used should correspond to the value of f_c adopted as working stress. The curves of Fig. 26 give values of p for different values of f_s/f_c up to 50, q being taken at $\frac{1}{2}$.

If in any given case a value for p less than that given by (6) is adopted, then the resisting moment is given by equation (4), which equated to the bending moment to be provided for gives $f_s p j b d^2 = M$, or

$$b d^2 = \frac{M}{f_s p j} \dots \dots \dots (7)$$

If a greater value of p is adopted, then the resisting moment

is given by (3), which if equated to the bending moment gives $jkf_c bd^2(3-q)/3(2-q)=M$, or

$$bd^2 = \frac{3(2-q)}{3-q} \frac{M}{jkf_c} \quad \dots \dots \dots (8)$$

From the proper one of these, d can be computed for any assumed value of b .




FIG. 26.

Examples.—(1) It is required to solve example 1, Art. 59, by the methods of this article, it being supposed that for the working stress $f_c=600$ lbs/in², $q=\frac{1}{4}$.

Solution. As shown in the solution of the example referred to, $A=1.768$ in², and $p=0.0126$; therefore from eq. (1) or Fig. 24, n being taken as 15, $k=0.466$, and from eq. (2) or Fig. 24, $j=0.842$. Then from eq. (3)

$$M_c = \frac{1}{11} \times 0.842 \times 0.466 \times 600 \times 10 \times 14^2 = 242,000 \text{ in-lbs.}$$

$$\text{and } M_s = 15,000 \times 1.768 \times 0.842 \times 14 = 313,000 \text{ in-lbs.}$$

(2) It is required to solve example 1 of Art. 64 by the methods of this article.

Solution. As disclosed by the solution in Art. 64, the stress in the steel will reach the elastic limit before that in the concrete would

reach the ultimate strength; hence the ultimate resisting moment depends on the steel. The stress existing in the concrete when the steel is stressed to the elastic limit is unknown; so is q . Supposing that this stress in concrete is $\frac{3}{4}$ the ultimate strength, $q=0.5$ (see Fig. 23); then, since $p=0.0126$, and n is taken as 15, $k=0.48$ and $j=0.83$ (see Fig. 25), and eq. (4) gives $M_s=820,000$ in-lbs. For a bending moment of this value, the stress in the concrete would be (with the above values of q , j , and k) 1260 lbs/in² (see eq. 5). Now for the ratio 1260/2000, q is about 0.4, k , 0.75, and j , 0.825. Since this value of j is practically like the one used in the trial computation, the ultimate resisting moment may be taken as 820,000 in-lbs.

(3) It is required to solve example 2 of Art. 59 by the methods of this article, supposing the ultimate compressive strength of concrete to be 2500 lbs/in².

Solution. This problem can only be solved by trial because it is necessary to know q at the outset, and q depends on a quantity sought, f_c . Supposing that the load is about a safe one, then q equals about $\frac{1}{4}$. With this value, n equal to 15, and p equal to 0.0104 (already found on page 60), $k=0.43$, and $j=0.85$ (see Fig. 24). Then eq. (5) gives $f_c=630$ lbs/in². Now q depends on the ratio of the working stress in the concrete to its ultimate strength; for the approximate value, 630, the ratio is 0.25, and eq. (a), or Fig. 23, gives $q=0.15$. With this value eq. (1) gives $k=0.432$, eq. (2), $j=0.854$ (see also Fig. 25), and eq. (5), $f_c=635$ lbs/in². This value is so near the first that $q=0.15$ must be practically correct, and $j=0.854$ may be used to determine the stress in the steel. For this, eq. (5) gives $f_s=13,700$ lbs/in².

(4) It is required to solve example 3 of Art. 59 by the methods of this article, the ultimate compressive strength of the concrete being taken at 2000 lbs/in².

Solution. For the ratio 700/2000, q is about 0.2 (see Fig. 23). With $n=15$ eq. (6) gives $p=0.018$. For this value of p , we may use either (7) or (8) to compute the dimensions of the section. Choosing (7) we need first a value of j , which may be obtained from (2) and (1), or closely enough from Figs. 24 or 25; the figures give $j=0.82$, and eq. (7) gives $bd^2=763$. With $b=7$ (as in Art. 59) d is 10.5 in.

70. Comparison of Flexure Formulas after Talbot with (1) those for working conditions as given in Art. 54-59, and (2) those for ultimate conditions as given in Art. 60-64:

(1) The heavy horizontal lines of Fig. 25 give values of j and k , according to the lineal law (Art. 54), and the curved lines

those after Talbot. For $q=0.25$ and $p=0.015$, the difference between the two values of j is represented by aa , and the difference between the two values of k by b . For all values of q up to 0.25 or 0.30 the first difference is small, and so the values given by the two formulas for f_s must be nearly the same. The second difference is larger, and the two formulas for f_c will not agree so closely. An exact comparison will now be made.

Art. 56 gives (see eqs. 3 and 4).

$$f'_s = \frac{M}{p j' b d^2} \quad \text{and} \quad f'_c = \frac{2M}{j' k' b d^2}.$$

(The primes are used to distinguish the symbols from the corresponding ones in the other formulas.) Comparing these with eqs. (3) and (4), Art. 62, one gets

$$\frac{f'_s}{f_s} = \bar{j}' \quad \text{and} \quad \frac{f'_c}{f_c} = \frac{2(3-q)}{3(2-q)} \frac{j k}{j' k'}.$$

As already explained, q rarely exceeds $\frac{1}{4}$ for working conditions; with this value and $n=15$, the following table gives the ratios f'_s/f_s and f'_c/f_c for five percentages of steel. For values of q less than $\frac{1}{4}$, the ratios are nearer unity; for $q=0$, they are all unity and the two sets of formulas are identical.

$p =$	$\frac{1}{4}\%$.	$\frac{1}{2}\%$.	1%.	1.5%.	2%.
f'_s/f_s	0.995	0.993	0.991	0.990	0.989
f'_c/f_c	1.092	1.091	1.090	1.088	1.086

The unit stresses in the steel as given by the two formulas are practically identical. Any error involved in the formulas for f'_c , based on the linear law, is on the side of safety.

(2) For loads which stress the concrete to the ultimate limit, the stress parabola of Fig. 22 is full like that of Fig. 19, and $q=1$. The formulas of Arts. 65-70 for this stage and those of Arts. 60-64 are identical.

71. Flexure Formulas for T-beams.—The following discussion is based on the linear law of compression, and it neglects

the tension in the concrete. The following additional notation is employed (see also Fig. 27):

- b denotes width of flange;
 d " effective depth of beam;
 b' " width of web;
 t " thickness of flange;
 c " depth of neutral axis below top of flange;
 x " " " resultant compression below top of flange.

It is necessary to distinguish two cases, namely, (1) the neutral axis is in the flange, (2) the neutral axis is in the web. Which of the two cases is at hand in any particular computa-




FIG. 27.

tion is generally not apparent at the outset. One may assume either case and determine the neutral axis on that basis, and finally note whether or not the neutral axis falls as assumed. If not, the computation is to be repeated by the formulas of the other case.

72. Case I. The Neutral Axis in the Flange.—All formulas of Arts. 54-58 (except approximate ones) apply to this case. It should be remembered that b of the formulas denotes flange—not web—width, and p (the steel ratio) is $A \div bd$, not $A \div b'd$ (see Fig. 27).

Approximate Formulas.—Evidently the arm of the resisting couple, CT , is always greater than $d - \frac{1}{3}t$; hence the following approximate formulas err on the side of safety:

$$M_s = j_s A (d - \frac{1}{3}t) \quad \text{and} \quad j_s = M/A (d - \frac{1}{3}t).$$

These give good results. There are no satisfactory corresponding formulas based on concrete, and indeed they are unnecessary, as the flange of a T-beam is generally more than strong enough for the steel.

73. Case II. The Neutral Axis is in the Web.—The amount of compression in the web is commonly small compared with that in the flange, and, for simplicity, it will be neglected, as no great error will result.

Neutral Axis and Arm of Resisting Couple.—Just as in Art. 55,

$$\frac{e_c}{e_s} = \frac{f_c/E_c}{f_s/E_s} = \frac{c}{d-c} \quad \dots \quad (a)$$

The average unit compressive stress on the flange is $\frac{f_c}{c}(c - \frac{1}{2}t)$ and the whole compression is $\frac{f_c}{c}(c - \frac{1}{2}t)bt$. And since the whole tension and whole compression on the section are equal,

$$f_s A = \frac{f_c}{c}(c - \frac{1}{2}t)bt \quad \dots \quad (b)$$

Eliminating f_s/f_c between equations (a) and (b) we get an equation which when solved for c gives

$$c = \frac{2ndA + bt^2}{2(nA + bt)} \quad \dots \quad (1)$$

n having been substituted for E_s/E_c . This equation shows that as d or A increases, c also increases.

The arm of the resisting couple is $d - x$ (see Fig. 27). The distance x is equal to the distance of the centroid of the shaded trapezoid from the top of the beam, that is

$$x = \frac{3c - 2t}{2c - t} \frac{t}{3} \quad \dots \quad (2)$$

Resisting Moment and Working Stresses.—If the beam is under-reinforced, its resisting moment depends on the steel;

if over-reinforced, on the concrete. These two values of the moment are respectively

$$\left. \begin{aligned} M_s &= A f_s (d - x) \\ M_c &= C (d - x) = \frac{f_c}{c} (c - \frac{1}{2}t) b t (d - x) \end{aligned} \right\} \dots \dots (3)$$

If one is in doubt which of these to use when about to compute the resisting moment of a given beam with specified working stresses, then both values should be computed and the smaller taken as the resisting moment.

The unit stresses, f_s and f_c , produced by a certain bending moment M in a given beam can be computed from

$$C = T = \frac{M}{d - x}, \quad f_s = \frac{T}{A}, \quad f_c = \frac{f_s}{n} \frac{c}{d - c} \dots \dots (4)$$

Approximate formulas corresponding to (3) and (4) can be established as follows: From the stress diagram in Fig. 27, it is plain that the arm of the resisting couple is never as small as $d - \frac{1}{2}t$, and that the average unit compressive stress is never as small as $\frac{1}{2}f_c$, except when the neutral axis is at the top of the web. Using these limiting values as approximations for the true ones, we have as substitutes for (3) and (4)

$$\left. \begin{aligned} M_s &= A f_s (d - \frac{1}{2}t) \\ M_c &= \frac{1}{2} f_c b t (d - \frac{1}{2}t) \end{aligned} \right\} \dots \dots (3')$$

$$C = T = \frac{M}{d - \frac{1}{2}t}, \quad f_s = \frac{T}{A}, \quad f_c = \frac{2C}{bt} \dots \dots (4')$$

The errors involved in these approximations are on the side of safety, for (3)' gives values smaller than (3), and (4)' larger ones than (4).

74. Either Case I or II. To Dimension a T-beam for Given Loads.—Generally the thickness of the flange has been pre-determined, and the requirements are depth of beam d , amount of reinforcement A , and breadth of web b' . Explicit formulas for these are unwieldy, and the practical procedure is to assume

a depth d , then calculate the amount of reinforcement A , by approximate formulas (6) or (7) as the "case" may be, and finally determine the actual compressive stress in the concrete for comparison with the working strength.

To determine whether the case in hand is (I) or (II), one may make use of equation (5), obtained from equation (a), which gives the value of d , for which the neutral axis is at the junction of flange and web for the adopted working stresses:

$$d = t \left(\frac{f_s}{nf_c} + 1 \right) \dots \dots \dots (5)$$

If a smaller value of d was adopted the case is (I) and if a larger the case is (II). The following are approximate formulas for the area of the steel for these cases respectively.

$$A = M / (d - \frac{1}{3}t) f_s \dots \dots \dots (6)$$

and

$$A = M / (d - \frac{1}{2}t) f_s \dots \dots \dots (7)$$

Each formula errs on the side of safety, but (6) gives correct values when the neutral axis is at the union of flange and web.

The web must be wide enough to take the steel and to provide certain strength as explained later (page 184).

Examples.—(1) A T-beam has the following dimensions: $b = 48$ in., $t = 6$ in., $d = 22$ in., and $b' = 10$ in.; the steel consists of six $\frac{3}{4}$ -in. rods. If the working strengths of steel and concrete are 15,000 and 600 lbs/in² respectively, and $n = 15$, what is the safe resisting moment of the beam?

Solution. The area of the steel is 2.65 in², and $p = 2.65 / (48 \times 22) = 0.0025$. Supposing this beam to fall under Case I, we find k from Fig. 17 (or eq. (1), Art. 55) to be about 0.24; hence $kd = 5.3$ in., and the neutral axis is in the flange, that is, the case was correctly guessed. Now $j = 1 - \frac{1}{3}k = 0.92$; hence (see eqs. (3) and (4), Art. 56)

$$M_s = (15,000 \times 2.65)(0.92 \times 22) = 806,000 \text{ in-lbs.},$$

and

$$M_c = 300(5.3 \times 48)(0.92 \times 22) = 1,545,000 \text{ in-lbs.}$$

The safe resisting moment hence depends on the steel, as it usually does in T-beams. The approximate formula gives $M_s = 795,600$ in-lbs.

(2) Change t of the preceding example to 4 in. and find the safe resisting moment.

Solution. Evidently this beam now falls under Case II. Equation (1) gives $c=5.44$ in. and (2) $x=1.61$ in. From (3)

$$M_s = 15,000 \times 2.65(22 - 1.61) = 950,000 \text{ in-lbs.},$$

and $M_c = (600/5.44)3.44(48 \times 4)(22 - 1.61) = 1,485,000.$

The approximate formulas (3)' give $M_s=716,000$ and $M_c=1,152,000$ in-lbs.

(3) Suppose that the diameter of the rods in example (1) is $\frac{7}{8}$ in., and that the beam is subjected to a bending moment of 1,250,000 in-lbs. Compute the working stresses in the steel and concrete.

Solution. The area of the rods is 3.61 in², and $p=3.61/(48 \times 22)=0.0034$. Supposing the case to be I, we find k from Fig. 17 to be about 0.27; hence $kd=5.94$ in., and the neutral axis does lie in the flange. Now $j=1-\frac{1}{3}k=0.91$; hence (see eqs. (5) and (6), Art. 57)

$$f_s = \frac{1,250,000}{0.91 \times 22 \times 3.61} = 17,200 \text{ lbs/in}^2,$$

and $f_c = \frac{2 \times 17,200 \times 0.0034}{0.27} = 431 \text{ lbs/in}^2.$

(4) Suppose that the diameter of the rods in example (1) is 1 in., and that the beam is subjected to a bending moment of 1,250,000 in-lbs. Compute the working stresses in the steel and concrete.

Solution. Equation (1) gives $c=6.74$ in., hence the beam falls under Case II. Equation 2 gives $x=2.22$ in., and (see eqs. 4)

$$f_s = \frac{1,250,000}{(22 - 2.22)4.71} = 13,400 \text{ lbs/in}^2,$$

and $f_c = \frac{13,400}{15} \frac{6.74}{22 - 6.74} = 395 \text{ lbs/in}^2.$

The approximate formulas (4)' give $f_s=13,960$ and $f_c=457 \text{ lbs/in}^2.$

(5) The flange of a T-beam is 24 in. wide and 4 in. thick. The beam is to sustain a bending moment of 480,000 in-lbs., the working strengths of steel and concrete being respectively 15,000 and 500 lbs/in². What depth of beam and amount of steel will answer?

Solution. We will try $d=18$ in. Equation (5) gives $d=12$ in., and hence for the trial value the neutral axis falls in the web and the beam falls under Case II. Equation (7) gives $A=2$ in². It remains to be seen whether the working stress in the concrete, with $d=18$ and $A=2$, is within the specified limit. From equation (1) we get $c=4.13$ in., and from equation (4), $f_c=300 \text{ lbs/in}^2$, which is within the limit; hence so

far as fibre stress in steel and concrete are concerned these values of d and A will suffice.

75. T-beams Double-reinforced.—T-beams are often continuous over their supports; at such places the bending moment is negative, and the flange is under tension and the lower part of the web under compression. Not only is tensile steel provided, but some steel is always left in the web (see Chap. VII); that is, the beam is reinforced in compression, and is said to be double-reinforced. For a discussion of double-reinforcement see the following articles—particularly Art. 79—in which there is explained a simple method for determining the effect of the compressive steel on the stress in the tensile steel and the compression in the concrete.

76. Beams Reinforced for Compression.—The compression in the concrete is assumed to follow the linear law and the tension in it is neglected; the formulas then apply to working conditions only. In addition to the notation already adopted (see page 54), let

A' denote the cross-sectional area of the compressive reinforcement;

p' denote the steel ratio for the compressive reinforcement, that is A'/bd ;

f_s' denote the unit stress in the compressive reinforcement;

C' denote the whole stress in the compressive reinforcement;

d' denote the distance from the compressive face of the beam to the plane of the compressive reinforcement;

x denote the distance from the compressive face to the resultant compression, $C + C'$, on the section of the beam.

77. Neutral Axis and Arm of Resisting Couple.—From the stress diagram (Fig. 28) it appears that $f_s/nf_c = (d - kd)/kd$, or

$$f_s = n \frac{1-k}{k} f_c \quad \dots \dots \dots (1)$$

Similarly, $f_s'/nf_c = (kd - d')/kd$, or

$$f_s' = n \frac{k-d'}{k} f_c \quad \dots \dots \dots (2)$$

For simple flexure, the whole tension T and whole compression $C + C'$ are equal, hence

$$f_s A = \frac{1}{2} f_c b k d + f_s' A'. \quad (a)$$

Inserting the values of f_s and f_s' from (1) and (2) in (a) gives an equation which may be written thus:

$$k^2 + 2n(p + p')k = 2n(p + p'd'/d), \quad (3)$$




FIG. 28.

and from this the neutral axis of a given section can be located. The lower group of curves in Fig. 29 gives values of k for several values of p and all values of p' up to 2%; n is taken at 15 and d'/d as 1/10. Thus for $p=2\%$ and $p'=1.5\%$, $k=0.434$.

The arm of the resisting couple is the distance between T (see Fig. 28) and the resultant of the compressions C and C' . It follows from the principle of moments and the law of distribution of stress respectively that

$$x = \frac{\frac{1}{2} k + d' C' / d C}{1 + C' / C} d, \quad \text{and} \quad \frac{C'}{C} = \frac{2 p' n (k + d' / d)}{k^2},$$

from which x can be computed for any given section. Finally the arm $j d = d - x$ or

$$j = (1 - x/d). \quad (4)$$

The upper group of curves in Fig. 29 gives values of j for several values of p and all values of p' up to 2%; n is taken at 15 and d'/d at 1/10. Thus for $p=2\%$ and $p'=1.5\%$, $j=0.875$.




FIG. 29.

78. Resisting Moment and Working Stresses.—If the tensile reinforcement is low, the resisting moment depends upon it, and is given by

$$M_s = f_s A j d = f_s p j b d^2. \quad (5)$$

If the compressive reinforcement is low, the resisting moment depends upon it and the concrete, and is given by

$$M_c = \frac{1}{2} f_c k (1 - \frac{1}{2} k) b d^2 + f_s' p' b d (d - d');$$

but f_s' bears a certain relation to f_c (see eq. 2), which inserted in the preceding equation gives finally

$$M_c = [k(\frac{1}{2} - \frac{1}{6} k) + n p' (k - d'/d)(1 - d'/d)/k] f_c b d^2. \quad (6)$$

The unit fibre stress in the tensile steel produced by any bending moment M can be computed from

$$f_s = \frac{M / j d}{A} = \frac{M}{p j b d^2}, \quad (7)$$

and those in the concrete and compressive steel from f_s and equations (1) and (2) respectively.

Fig. 29 shows that the neutral axis is nearer the compressive steel ($k < 0.55$) unless the percentage of tensile reinforcement is quite high and the compressive low; thus for $p = 3\%$, the neutral axis is nearer the compressive steel unless p' is less than $3/4\%$, and when $p = 2\%$, it is nearer for all values of p' . Now since the unit stresses in the tensile and compressive steels are as the distances of the steels from the neutral axis, it follows that the unit stress in the compressive steel is generally less than that in the tensile, that is $f_s' < f_s$.

For approximate computations one might use the average values $j = 0.85$ and $k = 0.45$ in equations (5), (6), and (7); then they would become respectively

$$M_s = 0.85 p f_s b d^2, \quad (5)'$$

$$M_c = (0.19 + 10.5 p') f_c b d^2, \quad (6)'$$

$$f_s = 1.18 M / p b d^2. \quad (7)'$$

79. Determination of Amount of Compressive Reinforcement.—This problem presents itself as follows: From the circumstances of the case, the beam needs so much tensile steel that the compressive concrete, if unreinforced, would be stressed too high, and it is necessary to employ compressive reinforcement to reduce the stress in the concrete; the percentage of reinforcement necessary to lower the stress a certain amount is desired.

An explicit formula for this percentage is too cumbersome for practical use, but a diagram (Plate VI, page 218) can be constructed from which the desired quantity can be easily determined. The construction of such a diagram will now be explained.

Let f_s and f_c denote the unit stress in the tensile steel and the concrete respectively, kd the depth of the neutral axis, and jd the arm of the resisting couple, CT , when there is no compressive reinforcement (see Fig. 16); also let f'_s , f'_c , $k'd$, and $j'd$ denote the same quantities when there is compressive reinforcement. Then

$$f_c = \frac{f_s kd}{n(d - kd)} = \frac{Mk}{jdAn(1 - k)},$$

and

$$f'_c = \frac{f'_s k'd}{n(d - k'd)} = \frac{Mk'}{j'dAn(1 - k')}.$$

From these the *relative* reduction in f_c due to the addition of compressive steel is found to be

$$\frac{f_c - f'_c}{f_c} = 1 - \frac{j}{j'} \frac{k'}{k} \frac{1 - k}{1 - k'}. \quad \dots \quad (8)$$

Since j and k depend on p , and j' and k' on p' , the equation furnishes the relation between relative reduction in concrete stress and the percentages of steel. The relative reduction $(f_c - f'_c)/f_c$ depends largely on the percentage of compressive steel and for a given value of this percentage the reduction is practically the same for all ordinary percentages of tensile steel (from $\frac{1}{2}$ to 3%). Plate VI, page 218, gives values of

this reduction for different values of compressive steel from 0 to 2%. As heretofore, values $n=15$ and $d'/d=1/10$ were used.

Addition of compressive steel reduces the stress in the tensile steel. The relative amount of this reduction is given by

$$\frac{f_s - f_s'}{f_s} = 1 - \frac{j}{j'} \quad \dots \dots \dots (9)$$

The group of curves (Plate VI) gives this reduction in per cent (right-hand margin) for different percentages of tensile and compressive steels as noted. (For illustration of the use of this diagram, see example (3) following.)

Examples.—(1) A beam of which $b=12$ in., $d=18$ in., and $d'/d=1/10$ has $2\frac{1}{2}\%$ of tensile steel and 1% of compressive. If the working strengths of steel and concrete are 15,000 and 600 lbs/in² respectively, what is the safe resisting moment of the beam?

Solution. From Fig. 29, $k=0.5$ and $j=0.85$; therefore

$$M_s = 15,000 \times 0.025 \times 0.85 \times 12 \times 18^2 = 1,238,000 \text{ in-lbs.,}$$

and

$$M_c = (0.5 \times 0.417 + 15 \times 0.01 \times 0.4 \times 0.9/0.5) 600 \times 12 \times 18^2 = 736,000 \text{ in-lbs.,}$$

which is the safe resisting moment.

(2) Suppose that the beam of the preceding example were subjected to a bending moment of 1,000,000 in-lbs. What are the working stresses f_c , f_s , and f_s' ?

Solution. As in example (1), $k=0.5$ and $j=0.85$; therefore (see eq. 7) $f_s = 1,000,000 / (0.025 \times 0.85 \times 12 \times 18^2) = 12,100$ lbs/in². From equation (1), $f_c = (12,100 \times 0.5) \div (15 \times 0.5) = 810$ lbs/in², and from equation (2), $f_s' = 15(0.4/0.5)810 = 9720$ lbs/in².

(3) In a certain design of a beam it is necessary to use 2.5% of tensile steel and this would result in a stress of 1200 lbs/in² in the concrete; it is necessary to reduce this to 900 by adding compressive steel. How much additional steel is required?

Solution. (See Plate VI.) The desired reduction of the compressive stress is 25%. We find this value at the left side of the diagram, then trace horizontally to the concrete curve, and then down to the lower margin, reading there 0.9%, the required quantity. From the last point we trace up to the 2.5% steel curve and then to the right margin, where we note about 4.5% reduction in tensile steel stress due to 0.9% compressive steel.

80. Flexure and Direct Stress.—When the resultant, R , of the external forces acting on one side of a section of a beam is not parallel to the section, then, in general, there exist both direct and flexural stresses at the section. The exception obtains when the resultant passes through the centroid of the section (transformed, as explained below, if the section is reinforced unsymmetrically); in this exceptional case the fibre stress is wholly direct.

In concrete work, the direct stress is always compressive. Combination of direct compressive and flexural stress gives resultant fibre stress which is either (1) all compression or (2) part compression and part tension; these cases are discussed separately below. Whether a given R will produce fibre stress falling under case (1) or (2) depends on the eccentricity * of R , the relative amounts of steel and concrete at the section and on n . If the reinforcement is symmetrical, steel imbedded a depth equal to 1/10 the whole depth of beam, and n is 15, then for eccentricities *lower* than those given in the table, case (1) obtains, and for higher case (2).

$p=$	0%	$\frac{1}{2}\%$	1%	$1\frac{1}{2}\%$	2%
$e/h=$	$\frac{1}{4}$	0.187	0.202	0.214	0.224

In addition to notations already adopted, the following will be used (see Fig. 30):

R denotes the resultant of all the external forces acting on a beam on either side of the section under consideration;

e denotes the eccentric distance of R ; that is, the distance from the point where R cuts the section to the middle of the section;

N denotes the component of R normal to the section;

* By the eccentricity of R is meant the ratio of the distance between the centre of the section and the point where R pierces the section to the whole height of the section.

M denotes bending moment at the section; it equals $N\epsilon$ or the sum of the moments of all the external forces about the horizontal line through the middle of the section, but when the transformed section is used, the moment axis must be taken through its centroid;

A' denotes the area of the steel nearer the face of the concrete most highly stressed;

d' denotes the distance from that face to the plane of this steel;

A denotes the area of the steel at the other face;

d denotes the distance from the former face to the plane of this steel;

h denotes the whole height of the section;

p' denotes the steel ratio A'/bh ;

p denotes the steel ratio A/bh ;

u denotes the distance from the face most highly stressed to the centroid of the transformed section;

A_t denotes the area of the transformed section;

I_t denotes the moment of inertia of the transformed section with respect to its horizontal centroidal axis;

I_c denotes the moment of inertia of the section bh with respect to that axis; and

I_s the moment of inertia of the sections of the steel with respect to the same axis.

81. Transformed Section.—By the transformed section of a reinforced concrete beam is meant the actual section with the areas of the reinforcement replaced by concrete n -fold and in the planes of the reinforcement. Thus if Fig. 30*a* represents an actual section, 30*b* represents the section transformed, the areas of the upper and lower wings of the latter section being respectively n times the areas of the upper and lower reinforcements.

(A prism of steel of a given area and one of concrete of n times the area are equally rigid as regards simple tension or compression; hence a reinforced-concrete beam and a plain concrete beam whose section is that of the first transformed are

equally stiff in so far as stiffness depends upon fibre stress, and in certain cases, as stated later, the fibre stress in the reinforced beam can be computed from those in the plain concrete beam. In those cases, the actual section and the transformed section are equivalent, ideally at least. Actually, the two beams are




FIG. 30.

not equally strong because of dangerous stresses in the wings of the transformed section.)

Referring to Fig. 30 it will readily be seen that

$$A_t = bh + n(A + A'), \quad I_t = I_c + nI_s, \quad (1)$$

$$u = \frac{h/2 + npd + np'd'}{1 + np + np'}, \quad (2)$$

$$I_c = \frac{1}{3}b[u^3 + (h-u)^3] \quad \text{and} \quad I_s = A(d-u)^2 + A'(u-d')^2. \quad (3)$$

If the reinforcement is symmetrical, then $u = h/2$ and

$$I_c = \frac{1}{12}bh^3 \quad \text{and} \quad I_s = 2A(\frac{1}{2}h - d')^2. \quad (3)'$$

82. Case I. The Fibre Stress is Wholly Compressive.—(a) The unit fibre stress in the concrete can be computed just as though the beam were homogeneous, but the transformed section must be used in the computations if the beam is reinforced. The unit stresses in the steel will be n times those in the concrete in the planes of the reinforcements respectively. Thus the unit direct stress in the concrete is N/A_t ; the unit flexural stress in the concrete highest stressed is Mu/I_t ; that in the concrete adjoining the reinforcement highest stressed

is $M(u-d')/I_t$; and that in the concrete adjoining the other reinforcement is $M(d-u)/I_t$. The combined unit stresses are:

$$f_c = \frac{N}{A_t} + \frac{Mu}{I_t}, \quad \dots \dots \dots (4)$$

$$f_s' = n \frac{N}{A_t} + \frac{nM(u-d')}{I_t}, \quad \dots \dots \dots (5)$$

$$f_s = n \frac{N}{A_t} - \frac{nM(d-u)}{I_t}. \quad \dots \dots \dots (6)$$

These equations—and the stress diagram, Fig. 31—show that f_s is always less than f_s' , and f_s' is always less than nf_c ; hence the unit stresses in both steel reinforcements will always be safe if f_c is a safe value.




FIG. 31.




FIG. 32.

(b) The method employed for simple flexure, suitably modified, leads to formulas not involving the transformed section, as will now be explained.

From the stress diagram (Fig. 32) it will be seen that

$$f_s' = nf_c(1-d'/kh), \quad \dots \dots \dots (7)$$

$$f_s = nf_c(1-d/kh), \quad \dots \dots \dots (8)$$

and

$$f_c' = f_c(1-1/k). \quad \dots \dots \dots (9)$$

From the condition that the resultant fibre stress equals N ,

$$\frac{1}{2}(f_c + f_c')bh + f_s'A' + f_sA = N;$$

and from the condition that the moment of the total fibre stress about the centroidal axis equals M ,

$$\frac{1}{2}(f_c + f_c')bh\frac{h}{6(2k-1)} + f_s'A'\left(\frac{h}{2} - d'\right) - f_sA\left(\frac{h}{2} - d'\right) = M.$$

From these equations it is possible to compute the unit fibre stresses f_c , f_s , and f_s' in a given case.

When the reinforcement is symmetrical the equations simplify greatly, and they lead to the following formula:

$$12k(1 + 2np)e/h = 1 + 24npa^2/h^2 + 6(1 + 2np)e/h; \quad (10)$$

they also give the following formula for f_c or M :

$$\frac{M}{bh^2f_c} = \frac{1}{12k}(1 + 24npa^2/h^2). \quad (11)$$

When $d'/h = 1/10$, and $n = 15$, Fig. 33 gives values of $1/k$ for different values of eccentricity and percentage of steel; thus for $e/h = 0.1$ and $p = 1.5\%$, $1/k = 0.635$, hence $k = 1.57$.

83. Case II. *There is Some Tension at the Section.*—(a) If the tension in the concrete is so small as to be permissible, and this tension is taken account of in the computations, then the unit fibre stresses in the concrete and steel, if reinforcement is present, may be computed by the method explained under Case I.*

The combined unit stress in the remote tensile fibre is given by

$$f_c' = \frac{MI_t}{h-u} - \frac{N}{A_t}, \quad (12)$$

* It is assumed that the linear law of variations of the unit flexural stresses holds for the tension as well as compression.




FIG. 33.

and f_s as given by (5) is compressive or tensile according as its value is positive or negative.

(b) If the tensile stresses are so high that it is advisable to neglect the tension in the concrete, then a method similar to that used heretofore in simple flexure is simplest. The transformed section is not used. O (Fig. 34) denotes a horizontal




FIG. 34.

axis at mid-depth of the beam, M the moment sum of all the external forces on one side of the section with respect to that axis, and N , as before, the algebraic sum of the components of those forces perpendicular to the section. From the stress diagram, it follows that

$$f_s = n f_c \left(\frac{d}{k h} - 1 \right) \quad \dots \quad (13)$$

and

$$f_s' = n f_c \left(1 - \frac{d'}{k h} \right) \quad \dots \quad (14)$$

Since the resultant fibre stress equals N ,

$$\frac{1}{2} f_c b k h + f_s' A' - f_s A = N,$$

and since the moment of the fibre stress about the horizontal axis through O equals M ,

$$\frac{1}{2} f_c b k h \left(\frac{h}{2} - \frac{k h}{3} \right) + f_s' A' \left(\frac{h}{2} - d' \right) + f_s A \left(d - \frac{h}{2} \right) = M.$$

From these four equations k , f_c , f_s , and f_s' can be determined for a given section, reinforcement, M , and N .

If the reinforcement is symmetrical, then the equations simplify. The value of k is given by

$$k^3 - 3\left(\frac{1}{2} - \frac{e}{h}\right)k^2 + 12np\frac{e}{h}k = 6np\left(\frac{e}{h} + 2\frac{a^2}{h^2}\right). \quad (15)$$

The greatest unit compressive fibre stress in the concrete is given by

$$\frac{M}{bh^2f_c} = \frac{1}{12}k(3-2k) + \frac{2pn}{k} \frac{a^2}{h^2}, \quad (16)$$

and the unit stresses in the steel are given by (7) and (8). From (7), or the stress diagram, it is plain that f_s' is less than nf_c even for unsymmetrical reinforcements.

When $d'/h = 1/10$ and $n = 15$, Fig. 35 gives values of k for different values of eccentricity and percentage of steel; thus for $e/h = 1$, and $p = 0.8\%$, $k = 0.42$.

84. Diagrams.—To facilitate the application of equation (11) (Case I) and equation (16) (Case II), Plates VII and VIII, pages 219 and 220, have been constructed.

In the first diagram, values of the eccentricity, e/h , are given at the upper and lower margins; the ordinates from the lower margin to any curve are values of $(1 + 24npa^2/h^2)/12k$ (see equation 11), and hence of M/bh^2f_c , for the value p marked on that curve. Thus when $e/h = 0.1$ and $p = 1\%$, $M/bh^2f_c = 0.087$.

The dotted portions of the curves correspond to eccentricities which involve small tensile stress in the concrete and belong strictly to Case II. The values of the unit tensile stress f_c' can be calculated from equation (12) or from

$$\frac{f_c'}{f_c} = \frac{h - kh}{kh} = \frac{1}{k} - 1, \quad (17)$$

$1/k$ being obtained from equation (10), or from an extension of the appropriate curve in Fig. 33.

In the second diagram, also, values of the eccentricity e/h are given at the upper and lower margins; the ordinates from the lower margin to any solid curve are values of




FIG. 35.

$\frac{1}{12}k(3-2k)+2pna^2/kh^2$ (see equation 16), and hence of M/bh^2f_c , for the value of p marked on that curve. Thus when $e/h=1$ and $p=1\%$, $M/bh^2f_c=0.187$.

The dotted curves in the second diagram enable one to estimate the ratio of the unit stress in the tensile steel to that in the concrete, f_s/f_c , for most eccentricities and percentages of steel. Thus when $e/h=1$ and $p=0.5\%$, we find $e/h=1$ at the top or bottom and then trace vertically to the 0.5% curve and note the point of intersection. This point falls between the curves $f_s/f_c=20$ and 25 , and the ratio is about 21 . For values of e/h and p , which bring the "point" to the left of the line $f_s/f_c=15$, f_s will be less than $15f_c$, and hence less than the working strength of steel for all ordinary allowable values of f_c . No similar curves for f_s/f_c appear on the first diagram because that ratio is always less than 15 , and hence the unit stresses in the steel (both upper and lower) are within safe values for Case I, if f_c is safe.

85. Examples.—It is supposed in these that the steel is imbedded a depth of one-tenth the total height of the beam, and that $n=15$, so that the diagrams on pages 219 and 220 apply.

(1) A beam is 12 in. wide, 30 in. high, and contains 1% of steel above and an equal percentage below. At a particular section, the resultant R is 80,000 lbs., its inclination to the axis of the beam is 5° , and its eccentric distance is 4.5 in. Compute the unit fibre stresses in the concrete and steel (f_c , f_s , and f_s').

Solution. The eccentricity is $e/h=0.15$, and $M=80,000 \cos 5^\circ \times 4.5=358,650$ in-lbs. The beam falls under Case I because this eccentricity gives a "point" on the 1% curve of page 219, but not on that of page 220. Tracing horizontally from the point we read $M/bh^2f_c=0.112$; hence

$$f_c = \frac{358,650}{24 \times 30^2 \times 0.112} = 297 \text{ lbs/in}^2.$$

The unit stresses in the steel are less than $15f_c=4500$ lbs/in². Their exact values can be computed from equations (7) and (8); the value of k for use in them can be easiest obtained from the diagram on page 95.

(2) Change the eccentricity of the preceding example to 15 in. and solve.

Solution. The eccentricity is $e/h=0.5$, and $M=80,000 \cos 5^\circ \times 15=1,195,500$ in-lbs. The beam falls under Case II (see page 220), and for

the eccentricity 0.5 and 1% of steel the diagram gives $M/bh^2f_c=0.171$; hence

$$f_c = \frac{1,195,500}{12 \times 30^2 \times 0.171} = 647 \text{ lbs/in}^2.$$

The intersection of the 1% curve and the 0.5 eccentricity line lies to the left of the curve $f_s/f_c=15$; hence the unit stress in the tensile steel is less than $15 \times 647 = 9470 \text{ lbs/in}^2$. The exact value can be computed from equation 13; the value of k for use in it can be obtained easiest from the diagram on page 98.

(3) The breadth of a beam is 12 in. and its height 24 in. At a certain section the bending moment is 450,000 in-lbs., and the eccentric distance is 4 in. The working strength of the concrete being 600 lbs/in², how much steel reinforcement, if any, is required?

Solution. The eccentricity is $e/h=\frac{1}{6}$, and hence the beam would be on the border between Case I and II even if no steel were used. With steel, the beam falls under Case I, and

$$\frac{M}{bh^2f_c} = \frac{450,000}{12 \times 24^2 \times 600} = 0.1085.$$

Entering the diagram, page 219, with this value and tracing horizontally to the 0.167 eccentricity vertical, we find their intersection and note that it falls between the 0.6 and 0.8% curves; about 0.7% of steel therefore is required.

(4) In example (3) change the eccentric distance to 12 in. and solve.

Solution. The eccentricity is $e/h=\frac{1}{2}$, and the beam falls under Case II (see page 220). M/bh^2f_c has the same value as in example (3); hence entering the diagram with that value and tracing horizontally to the 0.5 eccentricity vertical, we find their intersection and note that it falls between the 0.2 and 0.3% curves; hence 0.3% is the required amount.

(At first thought it may seem that more steel is necessary in example (4) than in (3) because of the greater eccentricity in the former example. But it should be noted that the thrust N is much less in (4) than in (3), its values being $M/e=37,500$ and 112,500 lbs. respectively.)

86. Shearing Stresses in Reinforced Beams.—In Art. 46 the variation in shearing stress in a homogeneous beam was discussed and the general formula given for the intensity of shear at any point (see eq. (1)). In a reinforced beam the variation in shear differs from that in a homogeneous beam owing to the concentration of tensile stress in the steel. The

general formula for shearing stress may, however, still be used if the transformed section be employed; that is, if the area of the steel be multiplied by n and considered equivalent to concrete at the same horizontal plane. The tension area of the concrete should be neglected. A simpler method for present purposes is the following: In Fig. 36 is represented a short portion of a beam where the total vertical shear is V . Let v =horizontal (or vertical) shearing stress per unit area at the neutral axis, and let b =width of beam. Other quantities are sufficiently indicated in the figure. $C=T'$ and $C'=T''$.




FIG. 36.




FIG. 37.

The total shearing stress on any horizontal plane between the steel and the neutral axis will be equal to $T' - T$ and the stress per unit area $= v = \frac{T' - T}{bdl}$. From equality of moments we have the relation $Vdl = (T' - T)jd$, whence is derived the expression

$$v = \frac{V}{bjd} \quad \dots \dots \dots (1)$$

The shearing stress given by eq. (1) is the same at all points between the neutral axis and the steel; above the neutral axis the shear follows the parabolic law as in a homogeneous beam. Fig. 37 represents the law of variation for the case under discussion.

Using $7/8$ for an approximate value of j (see Art. 55) we have approximately

$$v = \frac{8}{7} \frac{V}{bd}; \quad \dots \dots \dots (2)$$

that is, the shearing stress at the neutral axis (equal to the maximum) is one-seventh or about 14% more than the average value.

87. Beams Reinforced for Compression.—In beams reinforced for compression formula (1) will still apply, the value of j being the distance between the tensile steel and the resultant of the compressive stresses as shown in Art. 77. In this case j is somewhat greater than in the previous case and v is more nearly equal to the average shearing stress $\frac{V}{bd}$.

88. T-beams.—Here again formula (1) still holds true, j retaining its general significance. As shown in Art. 73, j may be taken as closely equal to the distance from the steel to the centre of the flanges of the T ; hence

$$v = \frac{V}{b'(d - \frac{1}{2}t)} \quad \dots \dots \dots (3)$$

It is to be noted that in the T-beam the shearing stresses are practically the same as in a rectangular beam of the same depth and having the same width as the stem of the T . The slab aids in reducing the shear only by its effect in increasing slightly the value of j .

89. Working Formula.—Since the value of j varies only within narrow limits it is quite as satisfactory for comparative purposes and for purposes of design to use the *average* value of the shearing stress,

$$v' = \frac{V}{bd'} \quad \dots \dots \dots (4)$$

in which b is the breadth and d is the net depth of the beam. In T-beams b is the breadth of the stem and d is the total depth from top of beam to steel. The true maximum shear will generally be from 10 to 15 per cent higher than the average value thus determined.

90. Effect of Shear on the Tensile Stresses in the Concrete.—In Art. 46 it was shown that in a homogeneous beam the direc-

tion of the maximum tensile stresses is horizontal at the lower face and becomes more and more inclined as the neutral axis is approached, reaching an inclination of 45° at that place. In the reinforced beam we have assumed, for purposes of design, that there is no tension in the concrete. While such possible tension will add very little to the resisting moment of the beam it is desirable to consider it here in relation to the shearing stresses and the resultant effect on lines of probable rupture. The shearing stresses determined in the preceding article have been calculated on the assumption of no tensile stress in the concrete, but the effect of such tension on the distribution of the shear is very small and need not be considered.

To determine the amount and direction of the maximum inclined tensile stresses at any point, eq. (1), Art. 46, is still applicable. In this case large shearing stresses exist immediately above the steel, hence the maximum tensile stresses become considerably inclined as soon as we leave the line of the steel, the exact direction depending upon the relation between the shear and the horizontal tension. Exact calculations are impossible, since the actual horizontal tension in the concrete is unknown. While the steel is assumed to carry all tension the concrete will in fact be stressed in accordance with its deformation up to the point of ultimate deformation and rupture. Where the steel has a stress of its full working value of 12,000 to 15,000 lbs/in², the deformation will much exceed the ultimate deformation of the concrete and rupture must occur, but at points where the steel stress is low, as for example near the end of the beam, the concrete may be intact.

Suppose, for example, the stress in the steel is 3000 lbs/in². If the modulus of elasticity of the concrete in tension is 1,500,000 the stress in it will be $3000/20 = 150$ lbs/in²; which is not far from its ultimate strength. Suppose further that the unit shearing stress in the lower part of the beam is 100 lbs/in². By eq. (1) of Art. 46 the resultant maximum tension will be $t = \frac{1}{2}(150) + \sqrt{\frac{1}{4} \cdot 150^2 + 100^2} = 200$ lbs/in², and

will have a direction inclined $26\frac{1}{2}^\circ$ from the horizontal. This stress may exceed the ultimate strength of the concrete and the result will be an inclined crack. At points nearer the neutral axis the horizontal tensile stresses become less and the inclined tension approaches the value of the shearing stress and its inclination approaches 45° . The result of these inclined stresses is likely to be a progressive tension failure in an inclined direction which the horizontal rods are not very effective in preventing.

Excessive stresses of this kind are prevented in various ways. Obviously they will be reduced by keeping the horizontal tension small through the use of considerable horizontal steel at points of heavy shear, by keeping the shearing stresses low, and by various means of directly carrying the inclined stresses by special reinforcement.

91. Ratio of Length to Depth for Equal Strength in Moment and Shear.—For any given values of per cent of steel and of working stresses in shear and direct stress there is a definite ratio of length to depth of beam which will give equal strength in moment and shear. The strength of beams of greater relative length will be determined by their moment of resistance, while that of shorter beams by their shearing resistance. The ratio of length to depth for equal strength depends on the method of loading.

For Single Concentrated Loads.—In this case the shear V , due to a given load W , is $\frac{1}{2}W$, and the moment M is $\frac{1}{4}Wl$. Hence

$$W = 2V = 4M/l. \quad \dots \dots (a)$$

From Art. 89 we have $V = v'bd$ and from Art. 56 $M_s = f_s j p b d^2$, in which v' = safe average shearing stress and f_s = working stress in steel. Substituting, we have

$$2v'bd = \frac{4f_s j p b d^2}{l},$$

from which

$$\frac{l}{d} = \frac{2f_s j p}{v'} \dots \dots (1)$$

For a Uniformly Distributed Load a similar process gives the ratio

$$\frac{l}{d} = \frac{4f_s j p}{v'} \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

For Beams Loaded with Equal Loads at the Third Points,

$$\frac{l}{d} = \frac{3f_s j p}{v'} \quad . \quad . \quad . \quad . \quad . \quad . \quad (3)$$

In the case of continuous girders these formulas will apply if l be taken as the length between points of inflection.

Taking, for example, $p=0.01$, $v'=50$ lbs/in², and $f_s=15,000$ lbs/in², and using an average value of $7/8$ for j , we have the following ratios for $\frac{l}{d}$:

For concentrated loads $\frac{l}{d}=5.25.$

For uniformly distributed loads $\frac{l}{d}=10.5.$

For double concentrated loads $\frac{l}{d}=7.87.$

92. Bond Stress.—The stress on the bond between steel and concrete (Fig. 36, Art. 86) will be equal to $T'-T$ on the length dl .

If U denote the bond stress per lineal inch, we then have

$$U = \frac{T' - T}{dl},$$

whence we derive

$$U = \frac{V}{jd} \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

The bond stress per unit area will be equal to U divided by the sum of the perimeters of the steel sections.

93. Strength of Columns.—Concrete columns need rarely be calculated as long columns. In ordinary construction the ratio of length to least width will seldom exceed 12 or 15, while the results of tests indicate little or no difference in

strength for ratios up to 20 or 25. It will be desirable then to determine first the strength of a reinforced column considered as a short column. If the conditions require it a general column formula may then be applied to provide for cases where the length is excessive.

94. Methods of Reinforcement.—Columns are reinforced in two ways: (1) by means of longitudinal rods extending the full length of the column, and (2) by means of bands or spirally wound metal. In the first case the steel aids by carrying a part of the load directly, the stresses in the two materials being proportional to their moduli of elasticity. In the other case the steel supports the concrete laterally, preventing lateral expansion to a greater or less degree, and thus strengthening the concrete. Usually both methods are more or less combined, the longitudinal rods being frequently bound together at intervals by circumferential bands of some sort, and on the other hand hoops or spiral wire being conveniently held in place by longitudinal rods. Experiments show that both types of reinforcement are effective in raising the ultimate strength of a column, but conclusive results have not been reached as to the true relative effect of different types and amounts of reinforcement.

95. Columns with Longitudinal Reinforcement.—As long as the steel and concrete adhere the relative intensities of stress in the two materials will be as their moduli of elasticity, using the modulus as explained in Art. 24.

Let A denote total cross-section of column;

A_c " cross-section of concrete;

A_s " cross-section of steel;

p " ratio of steel area to total area $= A_s/A$;

f_c " stress in concrete;

n " ratio of moduli of steel and concrete at the given stress $f_c, = E_s/E_c$;

P " total strength of a plain column for the stress f_c ;

P' " total strength of a reinforced column for the stress f_c .

$f_s = n f_c$. The following table shows the various working stresses in the steel corresponding to various values of working stress in the concrete and to various values of the modulus E_c ; there is given also the percentage increase in strength for each one per cent of steel.

TABLE NO. 6.
LONGITUDINAL REINFORCEMENT OF COLUMNS.

f_c , lbs./in. ²	E_c , lbs./in. ²	Ratio of Moduli, n	f_s , lbs./in. ²	Percentage Increase in Strength for each 1% Rein- forcement.
300	750,000	40	12,000	39
	1,000,000	30	9,000	29
	1,500,000	20	6,000	19
	2,000,000	15	4,500	14
400	1,000,000	30	12,000	29
	1,500,000	20	18,000	19
	2,000,000	15	6,000	14
	2,500,000	12	4,800	11
500	1,000,000	30	15,000	29
	1,500,000	20	10,000	19
	2,000,000	15	7,500	14
	2,500,000	12	6,000	11
600	1,500,000	20	15,000	19
	2,000,000	15	10,000	14
	2,500,000	12	7,200	11
	3,000,000	10	6,000	.9
800	2,000,000	15	12,000	14
	2,500,000	12	9,600	11
	3,000,000	10	8,000	9
	3,500,000	8.6	6,900	7.6

From this table the relation among the various quantities may be clearly appreciated. It is to be noted that the working stresses in the steel must be relatively low except in the unusual combination of high working stresses in the concrete with low modulus. High-grade concrete, permitting high working stresses, will have a high modulus. For further discussion of the relations of working stresses, see Chapter V.

Examples.—(1) What will be the safe strength of a column $15'' \times 15''$ in cross-section which is reinforced with 1.5% of steel, the working stress in the concrete being 400 lbs/in². Take $n=15$.

From eq. (1) we have

$$P' = 400 \times 15 \times 15 \times \left(1 + 14 \times \frac{1.5}{100} \right) = 90,000(1 + 0.21) = 108,900 \text{ lbs.}$$

The strength of the plain concrete column would be 90,000 lbs., and the relative increase in strength is 21%. The stress in the steel would be $15 \times 400 = 6000$ lbs/in².

(2) The area of a column is 120 sq. in., load to be carried is 60,000 lbs., and working stress on the concrete is 400 lbs/in². What percentage of steel will be required? Take $n=15$.

The safe strength of a plain concrete column would be $120 \times 400 = 48,000$ lbs. Hence, from eq. (2), $\frac{P'}{P} = \frac{60}{48} = 1 + (15 - 1)p$. Hence

$$p = \left(\frac{60}{48} - 1 \right) \div 14 = 1.8\%.$$

96. Columns with Hooped Reinforcement.—Whenever a material subjected to compression in one direction is restrained laterally, then lateral compressive stresses are developed which tend to neutralize the effect of the principal compressive stresses and thus to increase the resistance to rupture. Were the compressive stresses equal in all directions there would be no rupture (as there would be no shear). The strengthening effect of lateral banding depends then upon the rigidity of the bands, that is, upon the amount of steel used and its closeness of spacing. Its elastic limit may also affect the ultimate strength of the column.

On the basis of the relative lateral and horizontal deformation of the concrete (Poisson's ratio) it is possible to deduce a theoretical relation between the lateral and the longitudinal stresses, and thence the portion of the longitudinal stress remaining unbalanced. Let μ = Poisson's ratio, f_c = unbalanced or excess of longitudinal over lateral compressive unit stress, f'_c = total longitudinal unit stress, f_s = unit tensile stress

in steel, p =steel ratio (reinforcement to be closely spaced). We find approximately

$$f_c' = f_c \left(1 + \frac{\mu np}{2} \right) \quad . \quad . \quad . \quad . \quad . \quad . \quad (1)$$

and

$$f_s = \mu n f_c^* \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Recent experiments by Talbot indicate that Poisson's ratio for concrete is quite small, probably not greater than $\frac{1}{10}$ or $\frac{1}{8}$.

* *Demonstration.* (See Johnson's "Materials of Construction".)—Let μ =Poisson's ratio; p =steel ratio considered as a thin cylinder of equivalent area surrounding the concrete; A_s =cross-section of this steel cylinder; r =radius. Then

$$A_s = p\pi r^2 \quad \text{and} \quad \text{thickness of cylinder} = \frac{p\pi r^2}{2\pi r} = p\frac{r}{2}.$$

With no steel banding the stress f_c' would cause a proportionate lateral swelling of $\frac{f_c'}{E_c}\mu$. If the actual stress in the steel is f_s then the compression per sq. in. developed in the concrete by the steel reinforcement $= f_s p \frac{r}{2} \div r = \frac{f_s p}{2}$. This compression caused by the banding is equal in all horizontal directions, and has the same effect on distortion as two pairs of equal compressive forces acting on two sets of faces of a cube. The resultant lateral compression due to these horizontal forces is equal to $\frac{f_s p}{2E_c}(1-\mu)$. Combining this compression with the lateral swelling caused by f_c' we have the net lateral deformation equal to $\frac{f_c'}{E_c}\mu - \frac{f_s p}{2E_c}(1-\mu)$. This net deformation must equal the actual deformation in the steel under the stress f_s , which is $\frac{f_s}{E_s}$ or $\frac{f_s}{nE_c}$. Hence we have

$$\frac{f_c'}{E_c}\mu - \frac{f_s p}{2E_c}(1-\mu) = \frac{f_s}{nE_c}.$$

A part of f_c' may be considered to be balanced by the lateral compression of $\frac{f_s p}{2}$; it is the unbalanced portion only which is significant. Call this unbalanced portion f_c ; then $f_c' = f_c + \frac{f_s p}{2}$. Then eliminating f_s from these two equations we find for f_c' the value

$$f_c' = f_c \left(1 + \frac{np\mu}{np(1-2\mu) + 2} \right) \quad . \quad . \quad . \quad . \quad . \quad . \quad (a)$$

At the latter value eqs. 1) and (2) would become $f'_c = f_c$ $(1 + np/16)$, and $f_s = \frac{1}{8}nf_c$. Comparing these equations with those of Art. 95 it would appear that within the limit of elasticity the hooped reinforcement is much less effective than longitudinal reinforcement; in fact it would seem that very little stress can be developed in the steel under elastic conditions as here assumed. Such reinforcement may, however, be quite effective in increasing the ultimate strength of a column.

Results of tests appear to accord in a general way with these theoretical relations. Hooped columns have a relatively large deformation, reaching at an early stage a deformation equal to the maximum for plain concrete. Under further loading the concrete is prevented by the banding from actual failure, but continues to compress and to expand laterally, increasing the tension in the bands, the elasticity of the bands rendering the column in large degree still elastic. Final failure occurs upon the breakage of the bands or their excessive stretching. Banded columns thus exhibit a toughness or ductility much greater than other forms, but without a corresponding increase in stiffness under lower loads. Ultimate failure is likely to be long postponed after the first signs of rupture, and the column will sustain greatly increased loads even after the entire failure of the shell of concrete outside the bands.

Considère has made extensive theoretical and experimental investigations of hooped columns, from which he concludes that

We also have

$$f_s = \frac{2\mu n}{np(1-2\mu)+2}f_c \quad \dots \dots \dots (b)$$

For ordinary values of p eqs. (a) and (b) are reduced approximately to

$$f'_c = f_c \left(1 + \frac{\mu np}{2}\right) \quad \dots \dots \dots (1)$$

and

$$f_s = \mu nf_c \quad \dots \dots \dots (2)$$

the ultimate strength is given by the formula

$$P' = f_c A + 2.4 f_s p A, \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

in which f_c is the strength of concrete and f_s is the elastic-limit strength of the steel. This formula virtually counts the steel worth 2.4 times as much as in longitudinal reinforcement. (For further discussion see Chapter IV.)

CHAPTER IV.

TESTS OF BEAMS AND COLUMNS.

BEAMS.

97. Methods of Failure of a Reinforced-concrete Beam.—

A reinforced-concrete beam tested to destruction will usually fail in one of three ways:

- (a) By the yielding of the steel at or near the section of maximum bending moment.
- (b) By the crushing of the concrete at the same place.
- (c) By a diagonal tension failure of the concrete at a place where the shear is large.

Methods (a) and (b) may be called "moment" failures. Method (c) is sometimes called a shear failure, but this term is somewhat misleading, as the concrete in such cases does not fail by shearing.

(a) As a beam is progressively loaded and the steel has reached its yield point any further load will rapidly increase the deformation. The effect of this is to open up large cracks in the tension side and to raise the neutral axis. This causes a rapid increase in the compressive stress in the concrete and ultimate failure soon occurs by the concrete crushing. Such yielding may also result in final failure by diagonal tension if large shear exists near the place of maximum moment. In this case the primary cause of failure is the yielding of the steel and such failure may properly be called a tension failure. The additional load carried after the yield point is reached depends on the excess strength of the concrete, position of loads, and

other causes, but it is usually not large and cannot be safely considered. The yield point of the steel may therefore be considered its ultimate strength for reinforcing purposes.

(b) If the beam is relatively long and the amount of steel is sufficient so that the crushing strength of the concrete is reached before the yield point of the steel, a failure by crushing is likely to result. In this case tension cracks may appear, but will not become large. Fig. 38, (a) and (b), illustrates methods of failure (a) and (b) respectively.




FIG. 38.—Methods of Failure of Beams.

(c) Diagonal tension failures are likely to occur whenever large shearing stresses exist together with considerable horizontal or moment stresses, and when no special provision is made for such conditions. This is especially likely to occur in beams of relatively great depth, beams having a ratio of depth to length of more than about 1:10 being likely to fail in this way if no special provision is made for web reinforcement.

Fig. 38, (c), illustrates the typical diagonal tension failure where only horizontal bars are used. The initial crack forms at *a*. This gradually extends upwards in an inclined line and



FIG. 39




Fig. 40.

a little later the concrete begins to fail in a horizontal tension crack just above the rods, progressing from *a* towards the end of the beam. Tension along this line is brought about by the new conditions existing after the concrete has become cracked along the diagonal line and the normal diagonal tension has thus ceased to act. Usually this horizontal crack rapidly extends to the end of the beam and the failure is complete. In other cases the diagonal crack may extend to the top of the beam, allowing the part on the right to drop down and causing final failure. In such a case the concrete on the left may remain intact. Figs. 39 and 40 are photographs representing "diagonal-tension" failures.

A rupture of the concrete on a diagonal line also causes an increase in the stress on the rod at *a*, as shown more fully in Art. 108. This may result in a failure of bond, especially if the support is too near the end of the beam.

Final failure thus often results from stresses which are developed after initial failure has occurred, and while the cause of final failure is important from the standpoint of ultimate strength, yet of more importance in design is the initial failure and its cause. Other conditions besides those already mentioned may influence final failure so as often to mislead the observer as to the cause of the initial failure.

98. *Minor Causes of Failure.*—Slipping of the bars may cause failure, but under usual conditions it will not occur; and as it can readily be obviated by proper construction it need not be considered as limiting the strength of the beam. Failure by the shearing of the concrete near the support is possible where the load is very close thereto, but as the shearing strength of concrete is about one-half the crushing strength, such failures are exceedingly unlikely and need rarely be considered. The usual so-called "shear" failures are in reality diagonal-tension failures.

99. Tests of Beams Giving Steel-tension Failures.—The diagrams of Figs. 41 and 42 present in a roughly classified form results of the most important tests on reinforced-concrete beams

in which the failure appears to have been caused primarily by the yielding of the steel. In such a case the strength of the beam is directly proportional to the elastic-limit strength of the steel, and hence the tests have been classified as nearly as practicable with respect to this limit. The tests are thus divided into four groups according to values for the elastic limit as given in the diagrams. On each of the diagrams are drawn theoretical curves of strength using values for the steel stress corresponding to the elastic limit for the group. The full line is based upon the parabolic law of stress variation, the full parabola being used; the dotted line is based upon the straight-line law of stress variation. The value of n was taken at 15.*

Considering the nature of the material and of the tests the agreement between theory and experimental results is very satisfactory. It is to be expected that the theoretical values should represent minimum rather than average results, since the strength of a beam as determined by the elastic limit of the steel should be at least equaled, and generally slightly exceeded, in a test if failure does not occur in some other way. If the conditions are favorable the strength may considerably exceed that corresponding to the elastic limit of the steel, and in a few tests the steel has been pulled apart before complete collapse has taken place. Such excess of strength cannot be counted upon, however, as is well indicated in the diagrams.

* The sources of information are as follows:

1. Boston Transit Commission, Fourth Annual Report, 1904.
2. Bulletins Nos. 1 and 4, University of Illinois, Engineering Experiment Station
3. Jour. West. Soc. Eng., Vol. X, 1905, p. 705 (C., M. & St. P. R'y Co.'s tests).
4. Jour. West. Soc. Eng., Vol. IX, 1904, p. 239 (tests of M. A. Howe).
5. Bulletins Nos. 4 and 6, Engineering Series, University of Wisconsin, 1907.
6. Proc. Am. Soc. Test. Materials, Vol. IV, 1904, p. 508 (Univ. of Penn. tests).
7. Eng. Record, Vol. LI, 1905, p. 545 (Purdue Univ. tests).




FIG. 41.—Steel-tension Failures.




FIG. 42.—Steel-tension Failures.

In the tests of the Boston Transit Commission, which range uniformly high, the conditions were favorable, inasmuch as the beams were tested with center load. The concrete was also of very high grade, having a crushing strength of about 4000 lbs/in², thus enabling the steel to elongate very considerably before final failure occurred through the crushing of the concrete.

No distinction has been made in these diagrams between the different grades of concrete employed. Variations in concrete will affect the results only by slightly affecting the position of the neutral axis, and hence the resisting moment of the steel, and by postponing somewhat the final failure, as noted above.

100. Results from Individual Tests.—In many of the tests made at the University of Illinois and at the University of Wisconsin, and in the tests made by Professor Howe, extensometers were used to measure distortions so that the deformation of the steel and of the extreme fiber of the concrete could be calculated and the neutral axis determined. Typical results are shown in Figs. 43 and 44. In Fig. 43 the proportions were such that the failure occurred by diagonal tension; neither the steel nor the concrete was stressed to the limit of failure. During the first stage of the test, up to a load of about 2500 pounds, the deformations in both steel and concrete are proportional to the loads. Up to this point the tension deformation has not been great enough to begin to rupture the concrete, but with increasing loads and deformations the concrete begins to fail, as shown by the appearance of minute cracks (the "water-marks" discussed in Art. 42), indicated on the diagram by the letters *W.M.* The deformation at the first "water-mark" in this case was about .00018, corresponding to a stress of 270 lbs/in², assuming a modulus of elasticity of 1,500,000. The first visible crack appeared at the point marked *C*.

The failure of the concrete in tension takes place somewhat gradually and causes a gradual increase in the rate of deforma-




FIG. 43.




FIG. 44.

tion as indicated by the curved part of the diagram between loads of 2500 and 4000 pounds. After the concrete has ceased to offer any considerable resistance in tension the deformations again become nearly proportional to the loads, but at a different ratio from that obtaining previously, giving nearly straight lines for both steel and concrete—in this case to the end of the test.

In Fig. 44 the amount of steel was small and a tension failure occurred. This is indicated by the great deformations at the end of the test. The curves in the early stages of the test are very similar, in general form, to those in Fig. 43.

In the case of a compressive failure the curve for compression shows an increased rate of deformation towards the end, somewhat similar to the diagram for simple compression.

101. Position of Neutral Axis and Value of n .—In Figs. 45 and 46 are plotted the results of experiments in which the position of the neutral axis has been determined. The position is given for three stages of the tests, at one-fourth, one-half, and three-fourths of the ultimate load. On the diagrams are plotted the theoretical positions of the neutral axis for various values of n . The full lines are based on the straight-line stress variation assumption, and the dotted lines on the assumption of a parabolic law in accordance with Professor Talbot's method (see Art. 65). The dotted lines have been drawn only for a single value of 15 for n . For the three-quarter load the dotted line for $n=15$ would coincide very closely with the full line for $n=20$. The value of q has been taken at $\frac{1}{4}$, $\frac{1}{2}$, and $\frac{3}{4}$, respectively.

It will be noted that for the one-quarter loads and the small percentages of steel the neutral axis is more uncertain and generally lower than for the higher loads and larger percentages. This is due doubtless to the relatively large influence of the tensile strength of the concrete in such cases. From these results it would seem that a value of 15 for n is as low as would be warranted, even for the quarter load, which is not far from the usual safe load. This corresponds to a value of E_c of 2,000,000,




FIG. 45.—Position of Neutral Axis. (1:2:5 Concrete.)




FIG. 46.—Position of Neutral Axis. (1:3:6 Concrete.)

which is somewhat low as determined by compressive tests. A value of $n=10$, corresponding to $E=3,000,000$, does not accord with results from bending tests. If the comparison between measured and calculated positions of the neutral axis be made on the basis of the parabolic law of stress variation the results will differ considerably in the latter stages of the tests, but very slightly at the quarter load. It should be noted, however, that it is only with the high percentages of steel that the concrete stress reaches nearly to its ultimate value, and hence is the only condition where the full parabolic law can be expected to give consistent and rational results.

In some of the tests whose results are plotted here the concrete was cut away from the steel for the measured distance, leaving it exposed. The position of the neutral axis was very slightly affected.

102. Observed and Calculated Stresses in Steel.—Where the neutral axis is determined by extensometer measurements a check upon theoretical results can be obtained by calculating the stress in the steel in two ways: (1) from the observed deformations at the plane of the steel, and (2) from the known bending moment and known position of the neutral axis. In the first calculation the tensile strength of the concrete, which is neglected, causes some error, especially under light loads, and in the second calculation the exact position of the centroid of pressure in the concrete, especially in the later stages of the test, is to a small degree uncertain, but as the variation in steel stress is only about 2%, using the two extreme assumptions of stress variation, this source of error is not great. Table No. 7 presents several representative results derived from such calculations. The stresses calculated from moments are based on the assumption that the concrete takes no tension.

Tests have been made at the University of Illinois and at the University of Wisconsin in which the rods have been exposed for a considerable distance along the center of the beam, and thus have been much less affected by any possible tensile stress in the concrete. Measurements of extension made in such

cases show little variation from those made on the ordinary beam.

TABLE NO. 7.
STRESSES IN STEEL REINFORCEMENT.

Authority.	Per Cent Reinforcement.	Observed Position of Neutral Axis, k .	Calculated Stress in Steel, lbs./in ² .	
			From Moments.	From Extensions in Steel.
Talbot; <i>Bull. Univ. of Ill., 1906.</i>	.74	.410	33,100	36,000
	1.23	.470	35,000	36,000
	1.60	.501	29,500	35,400
	1.66	.505	30,600	30,000
	1.84	.606	25,600	27,200
	1.84	.552	28,300	30,000
Withey; <i>Bull. Univ. of Wis., 1907.</i>	2.9	.670	35,200	36,000
	2.9	.600	31,600	33,000

Considering the nature of such experiments the results obtained may be considered as according with theory very satisfactorily.

103. Compressive Stresses in Concrete in Beams and in Compression Specimens.—An important question relating to proper working stresses is whether the ultimate compressive strength of concrete in a beam is the same as determined by a direct compression test.

The results of certain tests indicate that the compressive strength and ultimate deformation in a beam may be somewhat greater than in a prismatic compressive piece; and it would seem that the differences in condition are sufficient to make such a difference possible. In a compressive specimen the material is free to shear in any direction, thus limiting the strength of the specimen to its weakest shearing plane. In a beam the (shear) failure is practically confined to planes perpendicular to the side of the beam. Furthermore, in a beam the material is not subjected to the secondary stresses due to possible poor bedding of the test specimen or non-

parallel motion of the testing machine, as is the case in compression tests.

In most of the tests reported both the beams and the accompanying compression specimens have been hardened in air. Under these conditions there is usually some drying-out effect resulting in a weaker concrete than if hardened in water, and owing to the smaller dimensions of the compressive specimens the effect will be greater with them than with the relatively large beams. Many tests have therefore shown a compressive strength of concrete in the beam considerably greater than results obtained on cubes. When both beam and cube are hardened in water the results do not differ greatly. The following are some results obtained on tests made relative to this point.* The beams were 8"×10" net section and 12 ft. span. They were reinforced with 2½% of steel and gave compressive failures. The cubes were 4 inches in dimension and the cylinders 6" in diameter by 18" high.

		Stress in Concrete at Rupture, lbs/in ² .		
		Beam.	Cube.	Cylinder.
Hardened in air	1.....	1770	1187	1380
	2.....	1460	1350	1295
Hardened in water	3.....	1810	1450	1265
	4.....	1850	1750	1680

The stresses in the beams were calculated on the basis of the parabolic variation of stress, the neutral axis being determined by extensometers.

It will be seen that in case of the specimens hardened in air there is a marked difference in strength, but where hardened in water the difference is much less. The difference is hardly sufficient to warrant much consideration in the determination of working stresses.

* Bulletin No. 6, Engineering Series, University of Wisconsin, 1907.

104. Conclusions Regarding Moment Calculations.—

The comparison of experimental results with theoretical analysis herein given shows that the simple beam theory as generally employed, neglecting the tension in the concrete, can be used with confidence. In particular, the results appear to show that calculated on the basis of such theory the yield point (commonly called the elastic limit) of the steel may safely be taken as its ultimate strength in reinforced beams; that the crushing strength of concrete as determined by tests on cubes hardened under exactly similar conditions as the beams will be fully realized in the beam; that for working loads the straight-line law of stress variation is sufficiently exact; that the value of n may be taken at about 15, but that great accuracy in this respect is unnecessary; that for ultimate values, especially where the concrete is near failure, the parabolic assumption of stress variation may well be used.

105. Tests in which Failure Occurred by Diagonal Tension. *Influences Affecting Failure by Diagonal Tension.*—The strength of a beam in diagonal tension is not a simple function of the shear, but as shown in Art. 90 it depends also upon the horizontal tension or bending-moment stresses in the concrete. These will in turn depend upon the actual bending moment at the section of failure and the amount of horizontal reinforcement, a large percentage of reinforcement reducing the horizontal deformation and therefore the tension in the concrete and tending to strengthen the beam as regards failure in diagonal tension. The strength of the beam therefore depends upon the relation between shear and bending moment and upon the amount of reinforcement. The chief factor is, however, the shearing stress.

From the preceding considerations it is evident that the nature of the loading will influence the strength of the beam. Most structures are calculated for uniform or approximately uniform loading, and in experimental work two concentrated loads applied at the third points are commonly used as representing roughly the conditions which exist in the uniformly

loaded beam. Fig. 47 represents the variation in moment and shear in a beam loaded at the third points, while Fig. 48 shows similar curves for a uniformly loaded beam. It is to be noted that in the first case maximum shear occurs where maximum moment exists, while in the latter case maximum shear occurs at the point of zero moment. In the former case




FIG. 47.




FIG. 48.

diagonal-tension failure will occur just outside the loads, while in the latter case it will occur nearer to the support where the moment is considerably less than the maximum. Conditions as to shear are therefore somewhat more favorable in the continuously loaded beam. A single concentrated load causes less shear for a given moment than the double load, and is therefore more favorable as regards shear.

As continuous beams are commonly used in building construction it will be useful to note here the variation in shear and moment in such a beam. This is shown in Fig. 49, and it will be seen that the conditions here are quite unfavorable, large shear occurring near the supports where the negative bending moment is large.

Whether a beam will fail from moment stresses or shearing stresses will depend largely upon its relative length and depth. For any given distribution of loads and given stresses there is a definite ratio of length to depth for equal strength as given

in Chap. III, Art. 91, but by reason of the variation in shearing strength due to the direct effect of moment and amount of steel, these formulas can be considered as only roughly approximate.

106. Methods of Web Reinforcement.—There are in use many methods of placing steel in the web so as to reinforce it against inclined tension failure. The various methods may, for convenience, be divided into three groups: (1) Reinforcing metal placed at an inclination; (2) Reinforcing metal placed vertically; (3) Miscellaneous methods.




FIG. 49.

(1) Theoretically the most effective way to reinforce against tension failure in any direction is to place reinforcement across the lines of rupture, or in the direction of the maximum tensile stresses. In the case of web tension the lines of maximum stress vary in direction, but it is not practicable or necessary to have the inclination of the reinforcing rods exactly the same as the lines of maximum tension, and various arrangements will serve to accomplish the purpose. The most common method is to use several rods for the horizontal reinforcement and then to bend a part of these upwards as they approach the end, where they are not needed to resist bending stresses. Such an arrangement is shown in Fig. 50, (a) and (b). Separate

inclined rods may also be used, attached or not to the horizontal bars. The "stirrups" commonly placed in a vertical position may thus be inclined. Special forms of bars may be used, as the Kahn bar, Fig. 7, p. 31, in which strips are sheared from the main bar and bent up.

(2) Vertical reinforcement has long been the established practice in European work where the experience has extended over many years. It has proven its effectiveness and in connection with bent rods has many practical advantages. Vertical reinforcement usually consists of some form of bent rod or band styled a "stirrup", placed as shown in Fig. 50, (c) and (d). The Hennebique system, widely and successfully used, employs both the inclined rods and the vertical stirrup (see Fig. 85, Art. 162). Combined with bent rods many arrangements of stirrups are possible, especially in continuous-girder constructions, the chief object being to secure good connection of stirrup to top and bottom steel.

(3) Some form of web of woven wire or expanded metal may be used for web reinforcement, and still other arrangements of wire or rods employed as illustrated in Fig. 50, (e), (f), and (g). In (g), representing the Visintini system, the beam is made into a truss in which the chords and the tension diagonals are reinforced.

107. Action of Web Reinforcement.—To aid in appreciating the action of steel placed in various ways, consider the typical diagonal tension failure, Fig. 51, as it occurs where only horizontal rods are used. The inclined crack at *a* usually appears first, due to rupture of the concrete in tension. To assist in preventing this rupture in its initial stage the most efficient reinforcement would be such as supplied by the inclined rod 1, fastened to or looped about the horizontal bar, or by the bent end of one of the horizontal bars. Reinforcement in this direction is in a position to take stress immediately. The vertical rod 2 can hardly be as effective as the inclined rod in preventing initial rupture, for so long as the concrete is intact the deformation on a vertical line is practically zero, owing to the combined




FIG. 50.—Some Methods of Web Reinforcement.

action of web tension and web compression at right angles to each other. Unless the unit stresses in the steel be made very low, however, it is likely that the concrete has received excessive tensile stress even under working conditions, and may be assumed to be ruptured more or less in the same manner as on the tension face of the beam at points of maximum moment. At least the distortion in tension will be greater than in compression, and there will be a vertical movement of the concrete on the left of the crack, *a*, *downwards* with respect to the part of the right, and the vertical rod 2 will be brought into direct action if looped around or attached to the horizontal bars. Such a rod may then be more effective (allow of less vertical movement) than the inclined rod. Practically, there is no great difference in the effectiveness of the two forms of reinforcement if closely spaced so as to be in position to prevent excessive deformation all along the lower portion of the beam. To secure thoroughly effective reinforcement in this respect requires very careful arrangement of the rods and faithful execution of the work.

Vertical stirrups spaced a distance apart equal to or greater than the depth of the beam will give little aid in the prevention of diagonal cracks between successive stirrups although they may prevent final failure by the extension of a crack horizontally along the reinforcing rods. Stirrups should be looped around the horizontal rods so as to be firmly anchored at their lower end (or upper end at points of negative moment), where the stress is a maximum, but attachment to the rod is not necessary, as the office of the stirrup is to prevent vertical, or nearly vertical, distortion. The value of a stirrup unless anchored or looped at the top is limited by its strength of bond, and as its length is not great this point may need consideration. In some tests at the University of Wisconsin final failure has resulted from slipping of the stirrups. Stirrups made of small sections or bent in loops are advantageous in this respect. Where separate inclined reinforcement is used there is danger of its slipping along the horizontal rods if the inclination is too great.

Bent rods alone are apt to be of limited value, owing to the difficulty of providing rods close enough together. Convenience of horizontal reinforcement calls for comparatively few rods of large size, which provides too few for effective diagonal reinforcement. Where large rods are bent up the length of the bent end should be made sufficient, by bending at a small angle, to develop the requisite bond strength. Some tests of beams show failure of bond in the case of short bent rods. In




FIG. 51.




FIG. 52.


the case of continuous girders it is convenient to extend the bent rod horizontally at the top over the support to furnish tension reinforcement. A very satisfactory arrangement of web reinforcement is a combination of bent rods and vertical stirrups, and especially is this the case in continuous-beam construction. Tests of various arrangements, so far as the authors have been able to find, show the best results from this method under the ordinary conditions and proportions. Web reinforcement of woven wire or expanded metal should give good results.

108. *Effect of Stirrups on Stress in the Horizontal rods.*—

A careful study of the distribution of stress which exists after a beam begins to rupture on a diagonal line will show the fact that a stirrup, whether vertical or inclined, will relieve the stress in the horizontal rods at the point of rupture. Thus in Fig. 52, if the concrete no longer has tensile strength, the value of the tension T in the horizontal rods at the line of rupture, if unaided by the stirrup stress S_1 or S_2 , is equal to Vx/a , the same as its value was at section N before rupture began. The moment of the stress in the stirrup about the point A , whether the stirrup be vertical or inclined, serves to

TABLE No. 8.
TESTS GIVING SHEAR OR "DIAGONAL TENSION" FAILURES.

Authority and Kind of Concrete.	Net Cross-section $b \times d$	Span.	Method of Loading.	Percentage of Reinforcement.	Arrangement of Reinforcement.	Kind of Bars.	Average Shearing Stress at Failure, $Lbs./in^2$	No. of Tests	Kind of Failure
(2) Talbot: 1:3:6	8" \times 10"	12'	$\frac{1}{3}$ points	1.66-2.21	Straight	Plain round	102	7	Shear
(6) Marburg: 1:2:4 crush. strength = 1700 lbs./in ²	7" \times 8"	5' 8"	Center	.96-1.36	Straight	Sq. corrugated and twisted	95	13	Shear
(3) Harding: 1:2:5 crush. strength = 1530 lbs./in ²	12" \times 20"	12'	$\frac{1}{3}$ points	.75	Straight	Plain round	108	3	Shear
	12" \times 21 $\frac{3}{4}$ "	12'	"	.72-.75	"	Corrugated	128	6	"
	12" \times 23 $\frac{1}{2}$ "	12'	"	.75	"	Twisted	99	3	"
	12" \times 18 $\frac{3}{4}$ "	12'	"	.75	1 bent, 2 straight (a)	Plain round	132	3	Tension
	12" \times 20"	12'	"	.75	"	Twisted	155	3	Shear
	12" \times 18 $\frac{3}{4}$ "	12'	"	.75	(b)	"	184	3	Shear & tens.
	12" \times 19 $\frac{3}{8}$ "	12'	"	.75	5 bent, 2 straight (c)	Corrugated	186	3	"
	12" \times 21 $\frac{1}{2}$ "	12'	"	.72	3 bent, 2 straight (d)	"	200	3	Shear
	12" \times 23 $\frac{1}{4}$ "	12'	"	.75	1 bent, 2 straight (b)	"			



(4) Carson: 1:2:3 about crush. strength= 4100 lbs/in ²	6"×7½" about	5'	Center	1.22-2.26	Straight	Corrugated	201	6	Shear	
	"	5'	"	1.51-2.26	"	Twisted	213	2	"	
	"	5'	"	1.21-1.71	"	Pl. round & sq.	182	2	Tension	
	"	5'	"	1.22-1.62	Curved (a) and (b)	Corrugated	227	8	Shear & tens.	
{ (5) Withey: 1:2:4 crush. strength= 1780 lbs/in ²	"	5'	"	1.22-1.62	Straight with Stirrups (c)	"	220	5	Tension & comp.	
	"	5'	"	2.44 total	"	"	259	2	"	
	"	5'	"	3.25 total	"	"	338	2	"	
	"	5'	"	2.04-3.01 (top) 1.22-1.63 (bot.) 1.28-2.00 (top) .65-1.00 (bot.) 2.00 at top 1.00 at bottom	Straight Str. and bent Straight with Stirrups Str. and bent with stirrups Expanded metal Straight with expanded met.	Plain round	161	4	Shear	
{ (6) Double reinforced beams, simple span	7½"×9" and 7½"×11"	Overhanging beams.		a	}	"	258	8	Shear & tens.	
	}	}	}	b		"	240	10	"	
						"	334	3	Tension	
						"	240	8	Shear & tens.	
	8"×10"	12'	}	}	}	"	239	8	Shear	
						"	155	2	Compression	
						"	189	2	Shear	
						"	184	2	"	
						"	194	2	"	

reduce the value of T . Without the stirrup there is therefore more danger of failure of *bond* near the ends of the beam.

109. Results of Tests.—In Table No. 8 are given in a classified form the most important tests of rectangular beams which lend information on web stresses and web reinforcement. The reference number in the first column refers to the list of authorities on p. 127. In this table are given the significant facts as far as practicable, although a detailed inspection of the reports referred to is necessary for a thorough study of the tests. The kind of failure denoted as a “shear failure” is so called for convenience; they are diagonal-tension failures brought about by large shearing stresses and hence may be measured by the shearing forces present. The average shearing stress on a vertical section at failure is given. While the maximum shearing stress is somewhat greater than this (Art. 89) the average stress is practically as good a standard of measure and is much more readily calculated. Where the failure was not a shear failure the figures for shearing stress are valuable as indicating what the maximum stresses were, although the beam may have withstood still larger stresses if failure had not occurred in some other way.

Straight Reinforcement Only.—The tests of Professor Talbot, Professor Marburg, and Mr. Harding give values of from 95 to 123 lbs/in² under quite a variety of conditions. Mr. Carson, with specially good concrete, secured values of about 200 in the case of high-elastic-limit deformed bars and 182 for plain bars, which, however, failed in tension. In the University of Wisconsin tests on overhanging beams, which represented beams of great depth, those with straight bars gave a value of 161 lbs/in² and double reinforced beams values from 155 to 194 lbs/in², depending upon the per cent of steel used.

As stated in Art. 102 the amount of horizontal steel has a direct bearing on shear failures for the reason that large areas of steel with low unit stresses permit less extension of the concrete than small areas with high working stresses. This effect is shown in a marked manner in a series of tests made at the

University of Wisconsin on small mortar beams of 1·3 mixture. The beams were $3'' \times 4\frac{1}{2}''$ in cross-section and 4 ft. span length. Loads were applied at two points a varying distance apart. Only straight reinforcement was used, amounting to 1.41%. The tensile strength of the material was high, being 490 lbs/in². The results were as follows:

Distance Apart of Loads. Centre Load.	Average Shearing Stress. Lbs/in ² .
....	177
12''	200
24''	220
32''	316
36''	512
40''	850
44''	1035

The increase in strength as the loads approached the supports must be due largely to the decrease in moment stress and consequent distortion, which is essentially what occurs when large areas of steel and low working stresses are used.

Beams with Web Reinforcement.—Mr. Harding's tests included only bent rods, and with these very considerably higher ultimate values were obtained than for straight rods, averaging for the three groups 190 lbs/in². Plain bars, bent, gave tension failures, these bars being of lower elastic limit than the deformed bars. These results are therefore of negative value. In some of Mr. Harding's tests the inclined bars pulled out, the bent ends being relatively short, as indicated in the sketches. An inspection of the deflection curves of these beams will show that those in which the rods were not bent were the stiffer beams, owing to the greater average amount of steel carrying the bending moment. Mr. Carson's results average 227 lbs/in² for curved bars and from 220 to 338 lbs/in² for straight bars with stirrups, the strength increasing with increasing per cent of metal. The stirrups were $1'' \times \frac{1}{8}''$ straps spaced about 7 in. apart. A reference to Table No. 12 will


show the effect of stirrups on the ultimate strength and method of failure of beams reinforced for compression. In the tests of Mr. Withey the bent rods alone gave 258 lbs/in² and stirrups alone averaged 240, while the combination gave 334, with a tension failure, showing still greater web stresses possible. Expanded metal, as used, proved too weak, as it pulled apart at a shearing value of 240 lbs/in². T-beam tests described in Art. 110 indicate that a value of 300 lbs/in² may readily be reached with stirrups and bent rods even with a relatively poor concrete.

The importance of tensile strength in the concrete should be noted in this connection, as the diagonal tension or shear failure is the one to be most feared and therefore most carefully guarded against.

110. Tests on T-Beams.—The reinforcing of T-beams requires special care in providing against shearing stresses. Where a floor slab forms the upper part of a beam there will usually be ample strength in compression for any depth likely to be selected. The design of the stem of the T, or the beam below the slab, is therefore largely a question of providing sufficient concrete and reinforcement to take care of the shearing stresses. In this case, therefore, it is important to provide a strong web for shearing stresses, as the strength in this respect will commonly determine its size. In Tables Nos. 9 and 10 are given the most important tests on T-beams known to the authors. The percentage of steel is calculated with reference to a rectangular beam having a cross-section equal to the circumscribing rectangle. The yield point of the plain steel in the tests of Table No. 9 was about 37,000 lbs/in², and its ultimate strength 51,000 lbs/in². A load of about 19,000 lbs. would stress the steel in the beams having .84% reinforcement to the yield point. This limit is exceeded only in the last three of the list. In these beams inclined stirrups were used, placed in a notch in the bar; in all other series the stirrups were placed vertically.

Reviewing these experiments we note, first, the results with straight bars and no stirrups. The beams having the .8-in.

TABLE NO. 9.
T-BEAM TESTS MADE BY F. VON EMPERGER.*



Concrete, 1:4; age, about 100 days.
Plain round steel used except where noted. Span = $78\frac{1}{4}$ ".
Beams loaded with two loads at $\frac{1}{4}$ points.

Number.	Percentage Reinforcement.	Number and Approximate Size of Rods.	Arrangement of Rods.	Number and Spacing of Stirrups Support.	Total Breaking Load, Pounds.	Average Shearing Stress on Beam $4'' \times 6''$, Lbs./in ² .
1	.84	Two; 8-inch	Straight	None	5700	119
2	.64	Two Thacher bars, 7-inch	"	"	5700	119
3	.84	Eight; 4-inch	"	"	9470	198
4	.84	Two; 8-inch	"	3 double, spaced 8"	9800	205
5	.84	"	"	5, spaced 4"	16000	334
6	.84	"	"	6, spaced 2" to 6"	16500	345
7	.64	Two Thacher bars, 7-inch	"	"	17200	360
8	.84	Eight; 4-inch	"	6 double, spaced 3 $\frac{1}{4}$ "	15600	325
9	.84	"	4 straight, 4 bent	None	12100	252
10	.84	"	"	4, spaced 5 $\frac{1}{4}$ "	16000	334
11	.84	Two; 8-inch	Straight	4 inclined, spaced 6"	13800	288
12	.84	"	"	4 double, inclined, spaced 6"	21800	455
13	.84	"	"	6 double, inclined, spaced 4"	23100	482
14	.75	Two; 32" X 14"	"	"	23700	495

* Forscherarbeiten auf dem Gebiete des Eisenbetons, Heft V, 1906.

rods and the Thacher bars developed a value of 119 lbs/in² average shearing stress, while the .4-in. rods developed 198, the difference being due doubtless to the difference in bond strength, although the previous experiments cited would indicate that not much greater value than the latter figure could be expected from straight bars only.

Noting the next five beams, all have straight rods and vertical stirrups, No. 4 having stirrups spaced 8" apart, while the others have a spacing of 4" or less near the support. For the former a value of 205 lbs/in² was reached, while the three others averaged 341, all being nearly the same despite the variety of bars used. No. 9 had bent bars and no stirrups, giving a strength of 252, while No. 10 had bent rods and stirrups rather widely spaced, developing 334. Nos. 11-14 had inclined stirrups attached to the bars and all but the first gave high values of over 450 for the shear.

In these tests it should be noted that a load of 16,000 lbs. would develop in the rods a theoretical stress of $(8000 \times 20)/4.2 = 38,000$ lbs/in². For the .8-inch rods this would require an average bond strength of about $38,000/(2 \times \frac{3}{4} \times \pi \times 25\frac{1}{2}) = 320$ lbs/in², about all that could be expected. The .4-inch rods would be stressed one-half as much in bond. The spacing of stirrups in No. 10 was too great to be entirely efficient. The inclined attached stirrups gave the best results in these tests, but whether similar results would be obtained where strength of bond was not in question cannot be stated. In case of weak bond an attached inclined stirrup virtually adds much to the bond strength of the bar.

In Table No. 10 are given further results of tests. In the first four tests the supports were placed too near the ends of the beam (4 inches) with the result that after the initial cracking the bars soon pulled out. After reducing the span length to 5 feet no further trouble in this respect was experienced. The results correspond closely with those given in the other tables.

TABLE No. 10.


T-BEAM TESTS AT THE UNIVERSITY OF WISCONSIN.*

Concrete, 1:2:4; age, 30 days.

Compression strength of cubes = 1120 lbs./in.²

All rods plain round. Length of beams, 6' 8".

Span length: Nos. 1-4 = 6 feet; all others = 5 feet.

Loaded at third points. Width of flange, 12" for Nos. 9-12; all others 9".
Rods bent up in all beams, two rods in those containing three rods and four rods (in pairs) in those containing six rods. All stirrups placed about $3\frac{1}{4}$ " apart.

Number.	Percentage Reinforcement.	Number and Size of Rods.	Web Reinforcement in Addition to Bent Rods.	Total Breaking Load, Pounds.	Average Shearing Stress on Section, $\frac{3}{8}'' \times d$.	Kind of Failure.
1	.94	Three; $\frac{1}{2}$ -inch	None	4000	107	Bond
2	.94	" "	" "	5100	136	"
3	.82	Three; $\frac{3}{8}$ -inch	$\frac{1}{4}''$ stirrups	4750	127	"
4	.52	" "	" "	4000	107	"
5	.52	" "	$\frac{3}{16}''$ stirrups	9380	238	Tension and shear
6	.82	" "	" "	9400	246	" "
7	1.05	Six; $\frac{3}{8}$ -inch	" "	12850	330	Compression
8	1.05	" "	" "	13550	349	Shear
9	.39	Three; $\frac{3}{8}$ -inch	$\frac{1}{4}''$ stirrups	8400	216	"
10	.39	" "	" "	8000	205	"
11	.78	Six; $\frac{3}{8}$ -inch	" "	11400	304	"
12	.78	" "	" "	12700	346	"
13	.52	Three; $\frac{3}{8}$ -inch	Expanded metal	7800	217	"
14	.52	" "	" "	7000	190	"
15	1.05	Six; $\frac{3}{8}$ -inch	" "	13800	384	Tension and shear
16	1.05	" "	" "	12600	350	Compression

* Bulletin No. 6, 1907.

TABLE NO. 11.

T-BEAM TESTS AT THE UNIVERSITY OF ILLINOIS.*

Concrete, 1:2:4; age about 60 days; comp. strength of cubes=1820 lbs/in².

Steel: yield point of plain round=17300 lbs/in²; of Johnson bars=36200 lbs/in².

Size of beams: thickness of flange=3 $\frac{1}{4}$ in.; thickness of web=8 in.; depth to center of steel=10 in.; total length=11 ft.; span length=10 ft.; width of flange varied.

Stirrups: made of $\frac{1}{2}$ -in. Johnson bars; five stirrups at each end spaced 6 in. apart.

Loads applied at third points. All failures were steel tension failures.

Num- ber.	Width of Flange. Inches.	Percent- age Reinforce- ment.	Number and Size of Rods.	Total Breaking Load. Pounds.	Average Shearing Stress on Section 8"×10" lbs/in ² .	Stress in Steel. lbs/in ² .
1	16	1.05	3 $\frac{3}{4}$ " Johnson	46700	293	64300
4		1.10	4 $\frac{3}{4}$ " Plain round	32410	203	41500
7		1.10	4 $\frac{3}{4}$ " " "	30100	188	38100
3		0.93	4 $\frac{3}{4}$ " Johnson	55700	347	57500
6	24	0.92	5 $\frac{3}{4}$ " Plain round (2 bars bent up)	39300	246	40700
8		0.92	5 $\frac{3}{4}$ " Plain round (2 bars bent up)	40100	250	41200
2		1.05	6 $\frac{3}{4}$ " Johnson	80500	503	55700
5		1.05	6 $\frac{3}{4}$ " Johnson (2 bars bent up)	83300	521	57400
9	32	0.97	7 $\frac{3}{4}$ " Plain round (3 bars bent up)	50900	318	37600

Table No. 11 contains results of recent tests by Professor Talbot. The maximum values of shearing stress are unusually high and indicate very effective web reinforcement. As no shear failures occurred the possible limit of strength of web was not determined. The very large excess of stress in the steel as compared to the yield points should be noted, due in large measure no doubt to the excessive compressive strength and the thorough web reinforcement.

III. Conclusions as to Shearing Strength.—From the available data it would appear that with ordinary concrete and no

* Bulletin No. 12, Eng. Exp. Station, Univ. of Ill., 1907.

web reinforcement the ultimate average shearing strength is about 100 lbs/in² and that this strength can readily be increased by the use of web reinforcement to 300 to 400 lbs/in². The latter figure may, from our present knowledge, be taken as about the maximum value with ordinary, closely spaced web reinforcement. It appears also that the shearing strength of a T-beam is about the same as that of a rectangular beam of the same depth and a width equal to the width of the stem of the T. It is to be understood that the shearing stress is here used merely as a convenient measure of the diagonal tensile stress, which is really the stress involved. This being the case it would be incorrect to take any account of the shearing strength of the steel in designing the reinforcement, as is sometimes done.

112. Beams Reinforced for Compression. — Generally speaking, it is more economical to carry compressive stresses by concrete than by steel, but limitations as to size sometimes makes it desirable to strengthen the compressive side of a beam. In cases, also, where both positive and negative moments exist in the same beam, either as alternating stresses or simultaneously at different points, steel reinforcement will be used on both sides and its value on the compressive side needs to be known. Obviously, steel reinforcement on the compression side will have little effect in beams that would otherwise fail in tension or shear, although there would be some gain owing to increased distance between centers of tensile and compressive forces. The effectiveness of steel in compression has sometimes been questioned, but the results of tests on beams and columns indicate that, in ordinary ratios at least, the steel does its share of work. Table No. 12 gives results of tests on double reinforced beams made at the University of Wisconsin.

The neutral axis was found by the use of extensometers, after which the stresses in steel and concrete at "load considered" were found, assuming the compression in the concrete to follow the parabolic law. Unfortunately, no web reinforcement was used, so that all the beams were too weak in shear to develop the full compressive strength, except in the case of the first

TABLE No. 12.

TESTS OF BEAMS REINFORCED FOR COMPRESSION.

UNIVERSITY OF WISCONSIN, 1906.*

Size of beams, 8" x 10" net section; 12' span. Concrete, 1:2:4; crushing strength = 1630 lbs./in.².
 Beams loaded at third points. Plain straight r. and rods used; elastic limit of $\frac{3}{4}$ " rods = 38,600 lbs./in.² and of $\frac{3}{8}$ " rods = 42,200 lbs./in.². All rods straight; no stirrups.

No.	Reinforcement, Tension Side.		Reinforcement, Compression Side.		Load at First Crack, Pounds.	Ultimate Load, Pounds.	$\frac{M}{bd^2}$	Average Shear Strain, Lbs./in. ² .	Load Considered.	Neutral Axis, \bar{k} .	Stress in Tension Steel, Lbs./in. ² .		Stress in Compression Steel by Deformations, Lbs./in. ² .	Maximum Compressive Stress in Concrete, Lbs./in. ² .	Ratio of Comp. Stress to Steel in Max. Stress in Concrete.	Kind of Failure.
	Bars.	Per Cent.	Bars.	Per Cent.							By Moments.	By Deformation.				
P_1	2.9	0.0	None	0.0	6000	24780	794	165	22160	.670	35.00	36000	2260	Comp.
P_2	"	0.0	None	0.0	4000	21380	683	141	20160	.675	31600	33000	2050	{ Comp. & shear
R_1	"	0.49	2 $\frac{3}{4}$ " R	0.49	8900	28740	922	190	26160	.590	39000	39000	4000	2370	16.7	Shear
R_2	"	0.49	"	0.49	6000	27840	895	184	26160	.600	33100	39000	45000	2210	19.5	"
T_1	"	0.98	4 $\frac{1}{2}$ " R	0.98	6000	24180	774	159	22160	.570	32500	33000	33000	1610	20.8	"
T_2	"	0.98	"	0.98	6000	31260	1003	206	24160	.565	35700	33800	36000	1760	19.9	"
V_1	"	1.47	6 $\frac{1}{4}$ " R	1.47	8000	27580	884	182	25160	.510	36100	36000	28500	1710	15.9	"
V_2	"	1.47	"	1.47	6000	31380	1008	206	29160	.555	42100	42000	39000	1670	23.4	"

* Bulletin No. 6, Engineering Series, University of Wisconsin, 1907.




FIG. 53.

two beams. The tensile stresses in the steel as calculated by the two methods agree very closely. The compression in the concrete is determined by subtracting from the total compression the compressive stress in the steel. As a check the ratio of stress in steel to stress in concrete has been computed. It is seen to be fairly constant and about equal to the value of n for the concrete at rupture, as it should be. These results indicate that the steel is taking its share of stress and that the compression side of the beam is strengthened in accordance with the usual theory. Obviously, in order to secure full benefit of the steel up to rupture, a fairly high elastic limit material should be used.

Fig. 53 gives a typical set of curves for the double reinforced beams. Comparing with those shown in Art. 100, it will be seen that these beams are much stiffer and apparently more perfectly elastic, as would be expected from the nature of the reinforcement.

TABLE No. 13.

TESTS OF BEAMS REINFORCED FOR COMPRESSION.

BOSTON TRANSIT COMMISSION.*

Beams and material as described in Table No. 8. All beams reinforced with $\frac{1}{2}$ " corrugated bars, with same number top and bottom. Stirrups $1'' \times \frac{1}{8}''$, spaced about 7". Centre loads.

Number.	Total Reinforcement.		Use of Stirrups.	Load at First Sign of Failure. Lbs./in ² .	Ultimate Load. Lbs./in ² .	$\frac{M}{bd_2}$	Average Shearing Stress, $\frac{V}{A}$, Lbs./in ² .	Kind of Failure.
	Number of Bars.	Percentage						
72	4	1.62	No	9920	10980	513	126	Tension
78	4			11424	14148	660	162	"
71	4			11000	16506	766	188	Shear & tens.
77	4			11224	15072	701	172	" " "
70	6	2.44	No	14992	16096	740	182	Shear
76	6			16716	17300	796	195	"
69	6			17724	23972	1106	272	Tension
75	6			14476	21284	990	244	"
68	8	3.25	No	19044	19044	880	215	Shear
74	8			17200	18584	854	210	"
67	8			21200	30168	1400	344	Tension
73	8			22132	29178	1347	332	"

* Tenth Annual Report, 1904.

Table No. 13 gives results of tests on double-reinforced beams by the Boston Transit Commission. The table is of value mainly in showing the benefit of stirrups. Crushing failures were obtained in but few cases in this series of tests, even where no compressive reinforcement was used, so that little advantage could be expected. It should be noted that where stirrups are not used the results shown in this table are very nearly the same as those of Table No. 12, although the quality of the concrete in the latter case was much inferior. Conditions were such that the full strength of the concrete was not developed in the tests of Table No. 13.

TABLE No. 14.

TESTS OF PLAIN CONCRETE COLUMNS.

WATERTOWN ARSENAL, 1903-1905.

All columns were 8 ft. high and ranged from 10 in. in diameter to 12 in. square. The age of the concrete ranged from 5 to 8 months.

Kind of Concrete.	Crushing Strength, Lbs./in ² .	
	Results of Individual Tests.*	Average Crushing Strength.
1:1 mortar.....	{ 5011 + 4320 }	4665
1:2 "	3652 2488	3070
1:3 "	2062 2692	2377
1:4 "	{ 1564 1471 1050 }	1362
1:5 "	1038 1082	1060
1:1:2 (pebbles).....	1525 1720	1622
1:1:2 (trap rock).....	3900	3900
1:2:4 (pebbles).....	1506 1710	1608
1:2:4 (trap-rock).....	{ 1750 1990 1413 }	1718
1:3:6 (pebbles).....	{ 462 700 1260 }	807
1:3:6 (trap-rock).....	{ 1350 750 1446 }	1182
1:2:4 (cinders).....	871	871
1:3:6 (cinders).....	{ 1060 698 }	879

* Where two lines of values are given, those in the first line are results obtained in the 1904 series, those in the second line are from the 1905 series.

COLUMNS.

113. **Tests of Plain Concrete Columns.**—The best series of tests which have been made on columns, to the authors' knowledge, are those made at the Watertown Arsenal, and reported in *Tests of Metals, 1904*, and subsequent volumes. The principal results on plain concrete are given in Table No. 14.

TABLE NO. 15.
TESTS OF REINFORCED COLUMNS.
MASSACHUSETTS INSTITUTE OF TECHNOLOGY.

Num-ber.	Cross-section.	Ratio: Length Diam.	Number of Rods and Size (Square).	Plain or Twisted.	Area of Steel, Sq. In.	Percentage of Reinforcement.	Crushing Strength, Lbs./in ² .
1	8"×8"	25.5	1 1"	P	1	1.56	1670
2	"	25.5	1 1"	T	1	1.56	1985
3	"	18.0	1 1"	P	1	1.56	1560
4	"	18.0	1 1"	T	1	1.56	1970
5	"	9.0	1 1"	P	1	1.56	2160
6	"	9.0	1 1"	T	1	1.56	2080
7	"	25.5	1 1½"	P	1.56	2.44	2125
8	"	25.5	1 1½"	T	1.56	2.44	2410
9	"	25.5	4 ¾"	P	2.25	3.51	2840
10	"	25.5	4 ¾"	T	2.25	3.51	2610
11	"	18.0	4 ¾"	T	2.25	3.51	2300
12	"	18.0	4 ¾"	P	2.25	3.51	2390
13	"	9.0	4 1"	T	4.0	6.25	2470
14	"	9.0	4 1"	P	4.0	6.25	3810
15	10"×10"	20.4	1 1"	P	1	1	2150
16	"	7.2	1 1"	P	1	1	2000
17	"	7.2	1 1"	T	1	1	2284
18	"	14.4	1 1½"	T	1.56	1.56	2620
19	"	14.4	1 1½"	P	1.56	1.56	2570
20	"	14.4	4 ¾"	T	2.25	2.25	3000
21	"	14.4	4 ¾"	P	2.25	2.25	2740

These tests indicate an average strength for 1:2:4 concrete of 1600 to 1700 lbs/in², with no excessive variation in individual tests. For the weaker mixture, 1:3:6, the individual tests are much more at variance, indicating greater unreliability. The great strength of very rich mortars is noteworthy, and this fact is borne out by experiments on columns slightly reinforced. Considering relative cost, a rich mortar may often be the more advantageous. Thus, for example, if cement,

sand, and stone cost respectively \$2.00, \$0.75 and \$1.00 per unit, and the cost of mixing and placing be \$1.50, the net cost of a cubic yard of 1:2:4 concrete will be about \$5.85, and the cost of a yard of 1:1 mortar will be about \$12.00, or slightly more than double, while the strength is about three times as great. Similarly, the cost of a 1:2 mortar is about \$8.85, while it has nearly double the strength of a 1:2.4 concrete.

114. Tests on Columns with Longitudinal Reinforcement.—The results of a valuable series of experiments made at the Massachusetts Institute of Technology are given in Table No.15.* The concrete was 1:3:6 broken stone concrete; the rods were partly plain square rods and partly twisted rods, the strength of the plain rods being 56,000-60,000 lbs/in², and of the twisted rods about 80,000 lbs/in². Where single rods were used they were placed in the centre, and where four rods were used they were placed in the form of a square one-half the dimensions of the column. The columns were approximately thirty days old.

Grouping these tests in accordance with the amount of reinforcement we have the following average values:

	Per Cent Reinforcement.	Average Strength, Lbs/in ² .	Calculated Strength, $f = 1470(1 + 19p)$, Lbs/in ² .
8"×8" columns. Average length=12.4 ft. {	1.56	1904	1904
	2.44	2267	2170
	3.51	2535	2450
	6.25	3140	3250
10"×10" columns. Average length=11.0 ft. {	1.0	2145	$f = 1800(1 + 19p)$, 2145
	1.56	2452	2320
	2.25	2870	2600

It is evident that the larger columns are, for like reinforcement, stronger than the smaller columns, showing an effect either of ratio of length to diameter or of diameter directly. Little difference is observed between plain and twisted bars. The effect of amount of reinforcement can be observed by con-

*Trans. Am. Soc. C. E., Vol. L, 1903, p. 487.

sidering each size separately. The results have been studied on the basis of the theoretical formula of Art. 95, Chapter III,

$$\frac{P'}{P} = 1 + (n-1)p, \quad . \quad . \quad . \quad . \quad . \quad (1)$$

in which P'/P represents the ratio of the strength of the reinforced to that of the plain concrete column.

No results are given for plain concrete columns, but assuming that the column with the lowest percentage of steel follows the theoretical law the strength of the ideal plain concrete column is calculated to be 1470 lbs/in² for the first group and 1800 lbs/in² for the second group, making $n=20$. Taking these values then as a basis the results are plotted in Fig. 54. Abscissas represent per cent of reinforcement and




FIG. 54.—Tests of Reinforced Columns. (Mass. Inst. of Technology.)

ordinates the relative strengths, that of the ideal plain concrete being 100. The theoretical relation is shown by the straight line drawn for $n=20$. This value of n corresponds to a value of E_c of 1,500,000, which would be a reasonable value at rupture on the basis of total deformation, as explained in Art. 24. While the results are not sufficiently numerous to be at all conclusive, they do indicate that the relative strength

of such columns is fairly represented by the theoretical law. Calculated values corresponding to the theoretical lines of the diagram are given by the formulas

$$f=1470(1+19p)$$

and

$$f=1800(1+19p).$$

These values are given in the table on p. 153. Eliminating the longest columns of the first group a fairly correct value for the ultimate strength of all would be given by $f=1600(1+19p)$ (n is assumed equal to 20).

The following table gives results of tests made at the Watertown Arsenal on concrete columns reinforced with longitudinal bars only. All columns were 8 ft. long and approximately 12"×12" square; age, 3½ to 8 months.

TABLE NO. 16.
TESTS OF REINFORCED COLUMNS.
WATERTOWN ARSENAL, 1904-1905.

Kind of Concrete.	Reinforcement.		Com- pressive Strength, Lbs./in ² .	Strength of Plain Concrete. (See Table No. 14.)	Ratio of Strength of Rein- forced Concrete to Plain Concrete.
	Description.	Per Cent.			
1:2 mortar.....	8 ¾" bars	2.85	4200	3070	1.37
1:3 ".....	" "	2.87	3841	2377	1.61
1:4 ".....	" "	2.86	3377	1518	2.22
1:5 ".....	" "	2.86	2813	1060	2.65
1:5 ".....	13 ¾" "	4.63	3905	1060	3.68
1:1:2 (pebbles)...	4 ¾" twisted	1.46	2890	1720	1.68
1:2:4 ".....	" "	1.43	1990	1710	1.17
" ".....	4 ¾" Thacher	1.03	1990		1.17
" ".....	4 ¾" corrugated	.97	2180		1.28
" ".....	4 ¾" twisted	1.45	1820		1.06
" ".....	8 ¾" "	2.86	3160		1.84
" ".....	8 ¾" Thacher	2.09	2760		1.62
" ".....	8 ¾" corrugated	1.94	2830		1.66
1:3:6 ".....	4 ¾" twisted	1.44	1370	462	2.96
1:3:6 (trap-rock)...	8 ¾" corrugated	1.94	2290	1350	1.82
" ".....	" "	1.93	2650		
1:2:4 (cinders)...	4 ¾" twisted	1.45	2095	871	2.40
1:3:6 ".....	4 ¾" bars	1.42	1932	1060	1.82
" ".....	8 ¾" "	2.83	3100		2.92

On Fig. 55 are plotted the results of the mortar tests and the 1:2:4 concrete in the same manner as the values in Fig. 54, using as a standard the results on plain concrete given in Table No. 14. Average values have been plotted for the columns with percentages of .97 and 1.03 and of 1.43 and 1.45. Lines




FIG. 55.—Tests of Reinforced Columns. (Watertown Arsenal.)

have also been drawn representing the theoretical relations for different values of n . In the mortar tests the results show that for the poorer mortars the relative effect of the steel is high, corresponding to what would be obtained theoretically by using a value of $n=40$ to 50. In the 1:2:4 concretes the results do not vary widely from the theoretical results for $n=30$, or a value of E_c at rupture of 1,000,000.

It is assumed in the theoretical discussion that the steel is not stressed beyond its elastic limit. It is to be noted that in these tests the stress on the steel bars must have been as high as 45,000 to 50,000 lbs/in², showing the usefulness of a fairly high elastic-limit steel in this case. (See further discussion in Chapter V.)

TABLE NO. 17.
TESTS OF REINFORCED COLUMNS.
UNIVERSITY OF ILLINOIS, 1906.*

No.	Length.	Cross-section.	Reinforcement.		Crushing Strength. Pounds per sq. in.	
			Kind.	Per cent.	Individual Test.	Average of Group.
1	12 ft.	12"×12"	4 $\frac{3}{8}$ -in. rods	1.20	1587	1809
3			4 $\frac{3}{8}$ -in. rods	1.21	1862	
7			12 $\frac{1}{4}$ -in. ties		1850	
11			4 $\frac{3}{8}$ -in. rods	1.21	1936	
2	12 ft.	9"×9"	12 $\frac{1}{4}$ -in. ties	1.21	1577	1710
6	"		4 $\frac{3}{8}$ -in. rods	1.52	1600	
10	"		4 $\frac{3}{8}$ -in. rods	1.52	1280	
12	9 ft.		12 $\frac{1}{4}$ -in. ties	1.50	2335	
14	12 ft.		4 $\frac{3}{8}$ -in. rods	1.48	1367	
16	9 ft.		9 $\frac{1}{4}$ -in. ties	1.50	1607	
17	6 ft.		4 $\frac{3}{8}$ -in. rods	1.49	2206	
5	12 ft.		9 $\frac{1}{4}$ -in. ties	1.47	1710	
8	"		4 $\frac{3}{8}$ -in. rods	0	2004	
9	"		12 $\frac{1}{4}$ -in. ties		1610	1550
13	"		4 $\frac{3}{8}$ -in. rods		1709	
15	6 ft.		9 $\frac{1}{4}$ -in. ties		1189	
18	"	9"×9"	Plain	0	1079	

Table No. 17 contains the results of tests made by Professor A. N. Talbot at the University of Illinois. The columns were made of 1:2:3-3/4 concrete and plain steel of 39,800 pounds per square inch elastic limit. The age was from 59 to 71 days. Comparing the reinforced with the plain concrete,

* Bulletin No. 10, Engineering Exp. Sta., 1907.

the average strength of the 12"×12" columns with 1.2 per cent reinforcement is about 1.17 times as great, and the 9"×9" columns with 1.5 per cent reinforcement is about 1.10 times as great. These tests indicate a less effect of reinforcement than some of the other tests quoted. The smaller cross-section of the columns containing the larger amount of reinforcement may have been the cause of the lower strength of this group. It is important to note the wide variation in the individual results of these and other tests; they indicate what may be expected in practice, and show clearly the necessity of adopting conservative values of working stress. Careful measurement of distortions showed that the ratio of stress in steel to stress in concrete varied from about 14 at the beginning to about 27 at rupture, taking average values. The low value for ultimate strength of the reinforced columns appeared to be due to a lower actual crushing strength of the concrete in these columns than in the plain columns.

115. Effect of Length of Column on Compressive Strength.—Comparing the results on plain concrete columns, p. 151, with the tests on cubes, pp. 11–14, it is evident that the strength of the column is materially less. While there is thus a very considerable reduction of strength as compared to the cube, there appears to be little difference in the strength of columns of various lengths up to 15 to 20 diameters. A series of tests made at the Watertown Arsenal* for the Aberthaw Construction Co. on 12"×12" columns gave practically the same results for all lengths from 2 ft. to 14 ft., the average of all being 957 lbs/in² for hand-mixed and 1099 lbs/in² for machine-mixed concrete. The temperatures were, however, low, and the results are not a fair criterion as to absolute strength.

In the tests of Table No. 15 the difference in average results upon the 8"×8" columns and those on the 10"×10" size is marked. But comparing results for each size among them-

* *Tests of Metals*, 1897.

selves there is little or no effect noticeable up to 25 diameters. Numbers 2 and 3 are reported as having failed by buckling, but these average practically the same as Nos. 1 and 4. From these tests it would appear therefore that no account need be taken of length of column below about 25 diameters, although caution should be used in accepting these results as conclusive. Twenty diameters would seem to be a safe length below which a uniform working stress may be used. The working strength should, however, be taken materially below that for beams. Greater lengths than 20 diameters are rarely needed for important members. Where necessary they may be designed by the usual column formulas, the reinforcement being in this case of great importance.

116. Hooped Concrete Columns.—If a compression member be reinforced by banding or winding, such a reinforcement will raise the ultimate strength by preventing lateral expansions under the compressive forces. It was shown in Art. 96 that under this system of reinforcement the steel cannot be stressed as high under low loads as in the case of longitudinal reinforcement, and that while distortion may be great the ultimate strength may be high. The strengthening effect of banding will then depend upon the amount of metal used and its resistance to expansion as measured by the relative rigidity of steel and concrete. As in the case of longitudinal reinforcement the greatest relative effect occurs with poor concrete of low modulus. Tests on columns show that in general such columns deform or compress more than those with longitudinal reinforcement.

In 1902 and 1903 Considère * published certain tests made on columns reinforced by spirally wound wire and by longitudinal rods or wire. His most important results were those obtained upon a number of octagonal columns 5.9 in. short diameter. As a result of these and other tests, as well as from a theoretical basis, he came to the conclusion that steel in the

* Génie Civil, 1902.

form of spiral reinforcement was 2.4 times as efficient as in the form of longitudinal reinforcement, presuming the spacing of the wire to be not great ($\frac{1}{4}$ to $\frac{1}{10}$ of the diameter of the spiral) and that ordinary mild steel be used. It was found also desirable to use a small amount of steel in the form of longitudinal reinforcement. Tests on the elastic properties showed considerable deformation and set, but after the first application of a load the column is relatively rigid, with greatly increased value of E .

Table No. 18 gives results of an important series of experiments on hooped columns conducted by Bach.* The columns




FIG. 56.—Tests of Hooped Columns. (Bach)

were of octagonal form with short diameter equal to 275 mm. and height of 1 m. The concrete was 1:4 gravel concrete 5-6 months old. Each result is the average of three tests, except in the case of the unreinforced concrete, where four tests were made. The steel was mild steel. The results in the last column do not indicate as great increase in strength as might be expected and the relative effect of longitudinal and spiral reinforcement does not appear to be greatly different.

* Quoted from Mörsch, Eisenbetonbau, p. 70.

TABLE No. 18.
TESTS ON HOOPED COLUMNS.
(BACH.)

Group.	No.	Spiral Reinforcement.		Longitudinal Reinforcement.		Per Cent Spiral Reinforcement.	Per Cent Longitudinal Reinforcement.	Per Cent Total Reinforcement.	Crushing Strength in Lbs./Sq. In.	Ratio of Strength to Plain Concrete.
		Pitch, Inches.	Diameter, Inches.	Number of Rods.	Diameter, Inches.					
	I		No reinf			1890	1.00
I	1	1.496				0.64	0.25	0.89	2260	1.20
	2	1.457		4	.276	1.29	0.25	0.54	2530	1.34
	3	1.654		4	.276	2.30	0.25	2.55	3410	1.80
II	4					0.64	1.22	1.86	3220	1.70
	5	1.496		8	.433	1.29	1.22	2.51	3270	1.73
	6	1.457		8	.433	2.25	1.22	3.47	4000	2.12
III	7	1.694		8	.433					
	8	1.222		4	.276	1.53	0.25	1.78	2850	1.51
	9	1.576		4	.276	2.42	0.25	2.67	3000	1.59
IV	10	1.615		4	.276	3.41	0.25	3.66	3640	1.93
	11	1.457		4	.276	5.12	0.25	5.37	3500	1.85
	12'	1.575		8	.197	1.19	0.25	1.44	2320	1.23
V	12 ²	1.575		8	.276	2.42	0.49	2.91	3270	1.73
	12 ³	1.575		8	.394	4.75	1.01	5.76	4300	2.28
	13'	3.150		8	.276	0.60	0.49	1.08	2310	1.22
VI	13 ²	3.150		8	.394	1.22	1.01	2.23	2580	1.36
	13 ³	3.150		8	.473	2.38	1.45	3.83	2330	1.50
	14'	4.725		8	.394	0.40	1.01	1.41	2205	1.17
VI	14 ²	4.725		8	.473	0.82	1.45	2.27	2600	1.38
	14 ³	4.725		8	.551	1.60	1.96	3.56	2950	1.46

To exhibit these results in a graphical manner they have been plotted in Fig. 56 in the same manner as those in Figs. 54 and 55. The strength of 1890 lbs./in² for the plain concrete column has been taken as unity. The *total* percentages of reinforcement have been taken as abscissæ. All the results of each group have been connected by a dotted line to aid in studying them. Theoretical lines for longitudinal reinforcement have been drawn for $n=20$ and 25. A careful study of these tests in comparison with those of Figs. 54 and 55 fails to show any considerable difference in relative strength for a given *total* amount of reinforcement. The results appear to be about the same. They do not, therefore, show any considerable superiority of spiral over longitudinal reinforcement. Group III, for example, has relatively more spiral reinforcement than group II, but its curve is lower. Groups V and VI are both relatively weak, probably owing to the wide spacing of the spirals.

Tests made at the Watertown Arsenal in 1905 and reported by Mr. James E. Howard * showed a large effect from hoops consisting of riveted bands 1.5" \times 12". Results on 1:2:4 columns 10½ in. diameter \times 8 ft. long, 5-6 months old, were as follows:

	Strength, lbs/in ² .
Plain concrete columns.	1413
13 hoops.	2232
13 hoops, 4 angle-bars.	3029
25 hoops.	3428
25 hoops, 4 angle-bars.	4189
47 hoops.	5289

The size of the angles was not stated. The amount of steel in the hoops is approximately 1% for 13 hoops, 1.8% for 25 hoops, and 3.4% for 47 hoops. Compared to the plain concrete column the strengthening effect of the hoops is relatively greater than the longitudinal reinforcement previously discussed.

* Proc. Am. Soc. Test Materials, Dec., 1906.

Important tests by Professor A. N. Talbot on hooped columns* showed greatly increased ultimate strength but little or no effect of the reinforcement for loads up to the usual ultimate strength of plain concrete. The general results were in accordance with the discussion of Art. 96. The total deformation at failure was very great, amounting to eight or ten times that for plain concrete; the lateral deflection was also large. Cracking or scaling of the thin exterior shell of concrete began at a load about equal to that causing failure in the plain concrete.

As regards ultimate strength, the effect of the reinforcement was from two to four times as great as would be caused by the same amount of longitudinal reinforcement. The following formulas were found to express approximately the ultimate strength in terms of percentage of steel used:

$$\text{for mild steel, } P' = 1600 + 65,000 p;$$

$$\text{for high steel, } P' = 1600 + 100,000 p;$$

where P' = strength per square inch, and p = percentage of steel with reference to the concrete core within the hoops. The strength of plain concrete is assumed to be 1600 pounds per square inch.

The tests given herein, excepting possibly those of Bach, show that the effect of hooping is to render the column "tough" and to increase greatly its ultimate resistance. The accompanying deformations are, however, large, and there appears to be little or no aid rendered until a load is reached about equal to the ultimate strength of plain concrete. This makes it difficult to combine effectively longitudinal and hoop reinforcements. This question, together with the subject of working stresses, is further discussed in Chapter V.

* Proc. Am. Soc. Test. Materials. 1907: Eng. Record, Aug. 10, 1907, p. 145.

117. Fatigue Tests of Reinforced Concrete.—Important experiments conducted by Professor J. L. Van Ornum* on reinforced beams indicate an effect under repeated application of loads similar to that which he found for mortar and concrete in compression as mentioned on p. 25. In the case of beams the failure under repeated loads appeared to be largely a gradual fracture in diagonal tension, ending with a compression failure. The number of repetitions required to produce failure varied




FIG. 57.

with the load applied, rupture being ultimately produced after several thousand repetitions for loads as low as 55 and 60% of the usual ultimate strength. The most important of his results are indicated in Fig. 57, taken from his paper, showing the number of repetitions required to produce failure at various values of maximum load in percentage of the usual ultimate load.

The change in the modulus of elasticity was also investigated, and it was found that under repeated loads not ultimately

* Trans. Am. Soc. C. E., 1907, LVIII, p. 294.

causing rupture the concrete soon became perfectly elastic, with a value of the modulus of about two-thirds of its initial value. At loads ultimately causing rupture the modulus became for a time nearly constant, but rapidly decreased as rupture was approached.

These tests indicate that concrete when repeatedly loaded beyond about 50% of its ordinary ultimate strength will not remain indefinitely elastic and will fail. This limit may be called the permanent elastic or fatigue limit of concrete. It is of much importance in relation to working stresses.

CHAPTER V.

WORKING STRESSES AND GENERAL CONSTRUCTIVE DETAILS.

118. Working Stresses and Factors of Safety.—In the design of steel structures it has come to be the practice to make use of definite working stresses rather than factors of safety. These working stresses are based, for the most part, on the permanent elastic-limit strength of the material, although the margin of safety between the elastic-limit and the ultimate strength (indicated by strength and ductility) receives consideration. The working stresses are made sufficiently below the elastic limit to provide for:

- (a) Variations and imperfections in material and workmanship.
- (b) Uncalculated stresses, such as secondary stresses, stresses due to unequal settlement, and, usually, those due to temperature changes.
- (c) Dynamic effect of live load if not provided for by an allowance for impact.
- (d) Possible increase in live load over that assumed, or rare applications of excessive loads.
- (e) Deterioration of the structure.

The more accurately the various elements are determined in any case the closer may the working stress approach the elastic limit. Where the dynamic effect of the live load does not enter, or is otherwise fully provided for, and where items (d) and (e) are of small moment, working stresses for steel structures will vary from about one-half to two-thirds the elastic-limit strength of the material. Were it absolutely certain that

the elastic limit of the material would never be exceeded in any emergency, then the margin of strength between the elastic limit and the ultimate strength would be of no importance. This is, however, not the case, and under actual conditions of service there is a very considerable element of safety in the fact that the ultimate strength is in most materials much higher than the elastic limit. Stated in another way, a designer would never use a working stress of one-half or two-thirds the elastic limit in a material where the ultimate strength did not considerably exceed this limit. While therefore the working stresses are selected chiefly with reference to the elastic limit, the ultimate strength also receives consideration.

In recent years most designers base their calculations on certain working stresses selected as above indicated. Formerly, and to some extent now, calculations are based on specified "factors of safety" referred to ultimate strengths. In either case both the elastic limit and the ultimate strength must be considered in the design, and experienced designers will arrive at about the same results by either method. In reinforced-concrete design the problem is complicated by the use of two unlike materials whose elastic limits and ultimate strengths are not similarly related. Furthermore, as the materials are stressed beyond their elastic limits the stresses do not necessarily increase in proportion to the load, so that if working stresses of one-fourth the ultimate are selected, for example, the corresponding load may be considerably greater or less than one-fourth the ultimate load. This condition makes it especially desirable to consider ultimate strength, and is an argument for the use of the "factor-of-safety" method.

119. Relative Effect of Dead and Live Loads.—The tendency of practice in the treatment of live-load stresses is to reduce them to equivalent dead-load stresses by the application of some sort of impact formula or by other means of estimation. The resulting stresses are then considered on the same basis as the usual dead-load stresses and a single set of working stresses applied. This method is simple, logical, and tends to facilitate

a proper adjustment of the design to the conditions. Separate working stresses will give equally satisfactory results when properly selected, but the system is not as flexible or convenient as the method of the single working stress with impact coefficients.

The question of impact coefficients, or the relation between live- and dead-load working stresses, requires little special attention in connection with reinforced concrete structures. It is essentially the same as it is in the case of steel structures, excepting as the amount of impact may be modified by the structure itself. In steel railroad structures of short span, for example, the impact, or dynamic effect of live load, is usually assumed to be about 100% of the live load stresses. Experiments show that this is probably not too high and that the actual stresses from live load may be 100% greater than the static stresses, due largely to the effect of unbalanced locomotive wheels. Where a large amount of ballast intervenes between the load and the structure the impact is doubtless much less. In the case of concrete structures the great mass of the concrete undoubtedly tends to reduce the effect of impact and vibration, or to localize such effect more than in a steel structure. The conditions involved in concrete designing, therefore, are likely to be favorable as regards impact and may permit the use of lower coefficients than are used for steel structures. The proper coefficient to use, or the relation between live- and dead-load working stresses, varies much under different conditions and must be left to the judgment of the designer, or to formulas or rules prepared especially for the purpose. Further discussion of this question will not be undertaken here.

In buildings it is the practice in steel construction to use a single working stress, no account being taken directly of any special effect of the live load. Allowance is made in the design of large girders and columns which receive their load from large areas for the fact that such large areas, especially if on two or more floors, are seldom or never loaded to the extent assumed for smaller areas. This allowance varies with different conditions,

but relates solely to the selection of the amount of live load rather than to its effect. In a building, when heavily loaded with its live load, the portion of the load which is in motion and capable of producing a dynamic effect is generally but a very small percentage of the total live load. In most cases, therefore, in building construction it is not necessary to treat the live-load stresses differently from the dead-load stresses, and the design is based on a single set of working stresses. Special cases will arise, however, where the dynamic effect of the live load requires consideration, as, for example, in the case of floors supporting moving machinery.

Whatever the effect of live load may be it can more readily be taken account of by adding to the resulting live-load stresses a percentage which, in the judgment of the engineer, will reduce them to their dead-load equivalent, and then apply a single set of working stresses, or factor of safety, to the sum of the stresses. The discussion of working stresses in the following articles will relate to the proper basal working stress for dead load, or for live load suitably increased for impact.

BEAMS.

120. Working Formulas.—From the analysis and results of experiments discussed in preceding chapters there would appear to be no good reason why the rational formulas as developed in Chapter III should not be used in designing. No empirical formula is needed. Furthermore, in the judgment of the authors, the simple formulas based on the straight-line stress variation should be used for purposes of design, safe working stresses being employed. These formulas are practically correct for such working stresses, and there seems to be no more reason to use formulas designed only to express ultimate strength than there is in the case of wooden or cast-iron beams where the conditions are similar. It is, however, desirable that the working stresses be selected with some reference to ultimate strength, although with principal reference to elastic strength.

121. Working Stresses in Concrete and Steel.—The strength of a beam is limited usually by:

- (a) The compressive strength of the concrete,
- (b) The elastic-limit strength of the steel, or
- (c) The strength of the beam in diagonal tension.

In this article the first two elements only will be considered.

From tests relative to elastic limit, such as those of Bach and Van Ornum (see Chapters II and IV), it would appear that the permanent elastic limit of concrete is from 50% to 60% of its ultimate strength as determined in the usual manner. If a factor of safety of two be applied to the elastic-limit strength to provide for items (a), (b), and (c) of Art. 118, we will have a dead-load basal working stress of 25% to 30% of the ultimate strength. Assuming an ultimate strength of concrete in cube form of 2000 to 2200 lbs/in², the working stress will then be from 500 to 600 lbs/in².

With respect to the steel the ultimate strength hardly comes into consideration; its elastic-limit strength is nearly its ultimate strength for reinforcing purposes. So far as safe stress in the steel is concerned a working stress of one-half the elastic limit is entirely safe as a dead-load stress. Let it be assumed then, for illustration, that a steel is used having an elastic-limit strength of 32,000 lbs/in², and that the working stress is taken at 16,000 lbs/in². Let us now consider the conditions which exist in a beam designed with the above working stresses when subjected to an increasing load.

For a load which produces stresses in the steel or concrete within the respective elastic limits, the two materials are indefinitely elastic and the beam is entirely secure; and were it certain that the stresses would under no conditions exceed these values the design would be entirely satisfactory. Suppose, however, that under emergency conditions, or by accident, the stresses pass the respective elastic limits, it will be noted that as regards the concrete there is still a very large margin of strength (about 50%), while as regards the steel the margin is little or nothing. Hence the beam fails through excessive

stresses in the steel; that is, the ultimate strength of the beam is limited by the steel to a value much below its strength as determined by the concrete. It follows that in order to utilize, for emergency purposes, the strength of the concrete beyond its elastic limit, the working stress in the steel must be selected so as to give the desired margin of strength without much exceeding *its elastic limit*. To secure these conditions in the above case, the working stress in the steel would have to be taken at about 8000 lbs/in² or a material of higher elastic limit selected in order to support an ultimate load equal to four times the working load. The concrete would be able to support even more than four times the working load, since at high stresses the fibre stress no longer follows the straight-line law of stress variation, and such a load will produce a fibre stress considerably less than 2000 lbs/in².

Considering the fact that in well-designed beams the steel stress at failure will considerably exceed its elastic limit, and considering also the greater reliability and uniformity of steel as compared to concrete, it would seem that a working stress in the steel of about one-third its elastic limit would correspond fairly well with the working stress in the concrete here suggested. With such values for working stresses the beam will have a factor of safety as regards elastic limit of about two (determined by the concrete), and as regards ultimate strength its factor of safety will be at least five relative to the concrete and from three to four relative to the steel. Its elastic limit is thus determined by the concrete and its ultimate strength by the steel, which may be considered as satisfactory conditions.

The working stresses in the steel should also be considered with reference to its distortion. High working stresses involve large distortions, and hence a greater degree of incipient rupture in the concrete. This condition is probably of little moment in most cases so far as it concerns undesirable appearance or exposure of steel to corrosion, but is of importance with reference to its effect on diagonal tensile stresses as explained in Art. 109. Low unit stresses in the steel are greatly to be preferred on this

account. It will also be shown in Art. 133 that very little is to be gained in economy by using stresses higher than about 12,000 lbs/in². Considering this fact and the objections to high stresses above mentioned, it would seem that a stress of 15,000 lbs/in² should be considered the maximum desirable value irrespective of the quality of the steel used. A lower value is strongly to be recommended. Finally, as the result of this analysis we may conclude that the basal working stress in the steel should not exceed about one-third its elastic limit nor exceed 15,000 lbs/in².

122. Quality of Steel.—As stated in Art. 34, there exists considerable difference of opinion as to the quality of steel to be desired, especially with reference to the use of soft or hard material, or steel with low or high elastic limits. Certainly a material as hard as that formerly denominated "hard bridge steel" is entirely suitable for reinforced construction. Such material has an elastic limit of about 40,000 lbs./in². Much material has been used of an elastic limit of 45,000 to 50,000 lbs/in² and even higher, but a value beyond this is not to be desired. An elastic limit of 45,000 lbs/in² is three times the working stress of 15,000 lbs/in². The use of a steel with an elastic limit higher than this is unnecessary and is of doubtful wisdom, as the ductility of a higher steel of the usual quality is not high. The authors would suggest a material of the quality employed for buildings with an elastic limit of 35-40,000 lbs/in² and working stresses of 12,000 to 14,000 lbs/in².

123. Bond Stress.—The factor of safety with reference to the slipping of the rods should be at least 5, since the strength of a beam should not be limited by the strength of bond. From the data of Chapter IV, we may take the ultimate bond strength of plain steel at from 250 to 400 lbs/in². A working stress of from 50 to 75 lbs/in² would therefore be suitable. With a working bond stress of 60, say, and a tensile unit stress of 15,000 a round bar will need to be embedded a length of $15,000/4 \times 60 = 62.5$ diameters to develop its full strength. In the case of large bars of 1" to 1½" in diameter this length is very considerable

and for short beams may be difficult to secure. The deformed bar, or the anchored bar, is of especial value under these conditions.

For deformed bars the safe working stress may be taken at about 100 lbs/in², thus requiring a length of embedment of about $15,000/4 \times 100 = 37.5$ diameters.

124. Shearing Stresses.—From the results discussed in Chapter IV the ultimate shearing strength of a beam having no web reinforcement may be taken at about 100 lbs/in², calculated as average shearing stress on the cross-section. Inasmuch as a failure due to high shearing stresses is apt to be sudden, the factor of safety should be fully as great as that with reference to the compressive strength of the concrete. This gives a working stress of 25 to 30 lbs/in². For beams in which the web is well reinforced the working stresses may be made 3 or 4 times as great, or from 75 to 100 lbs/in².

125. Calculation of Web Reinforcement.—Sufficient experimental work has not been done to enable the proportioning of web reinforcement to be done with any degree of exactness. However, a rough estimate of the requirements can be determined on rational grounds. The tests already quoted in Chapter IV indicate that beams with horizontal bars only cannot be stressed safely beyond about 30 lbs/in² average shearing stress, the strength depending on the quality of concrete and the unit stresses adopted for the horizontal steel. In practice it will rarely happen that a beam need carry more than 100 lbs/in² average shearing stress, and tests of the best work indicate that this should be about the maximum limit. In such a case if the concrete be assumed to carry 30 lbs/in² the steel must carry the remainder at a working stress of say 15,000 lbs/in². If the area of cross-section of beam be bd , then the shear to be carried is $70bd$; and as the tendency to rupture is on a line inclined at 45°, this shear may be considered as the load to be carried by the web reinforcement in a length equal to the depth d . The necessary steel area is therefore $A = 70bd/15,000 = .0047bd$, or .47%. The area of the horizontal reinforcement

should not be taken into account, as is sometimes done. Where the shear is large, as in the case assumed, the stirrups or other reinforcing members should be placed not farther apart than $\frac{1}{2}d$, and the sectional area of each may therefore be taken $= .23\%$ of the cross-section. For example, a beam $8'' \times 12''$ would require stirrups 6 in. apart and each of a cross-section of $.23\% \times 96 = .22 \text{ in.}^2$. This would be equivalent to a $\frac{3}{8}$ -in. stirrup in a single loop or a $\frac{1}{4}$ -in. stirrup in a double loop. Close spacing is of more importance even than size, but high working stresses are undesirable, as they permit too great distortions, with resulting minute cracks in the concrete. The value of a stirrup or the bent end of a bar is also limited by its safe bond strength. Inclined rods are almost necessarily of too large size and too far apart to be effective without some stirrups, but the two combined, using fewer stirrups, is an effective combination. Where the shear in the beam is less than the allowed value, web reinforcement may be omitted.

126. Spacing of Bars.—In rectangular or T-beams the spacing of bars is important; in T-beams this consideration will largely control the width of the beam. The requirement in general as to spacing is that the amount of concrete left between the bars must be sufficient to transmit to the upper part of the beam the stress which the bars give over to the concrete below them. If the bars are circular it may be assumed that one-half of the stress in them is given over to the concrete below, hence the strength of the concrete on a longitudinal section through the center plane of the bars must equal one-half of the stress in the bars. If the shearing stress be taken as equal only to the bond stress then the clear space between bars must be one-half the circumference of a bar, or 1.57 diameters. In the sense here employed the shearing strength is at least twice the bond strength for smooth rods, so a clear spacing of less than one diameter is sufficient from this standpoint. In the case of square bars, on the same basis, the clear spacing would need to be $1\frac{1}{2}$ diameters if the bars are placed with sides vertical, or one diameter is placed with sides diagonal.

But in addition to the shearing stresses there is likely to be developed more or less tension in the concrete surrounding the rods, so that there should be left ample areas of concrete between them, especially towards the end where the bond stresses are large. A minimum clear spacing of at least $1\frac{1}{2}$ diameters should be provided, with an equal distance between the outside rod and the surface of the beam. Where some of the rods are bent up the spacing can readily be made more liberal towards the end of the beam.

Liberal spacing, or large net section of concrete, favors large rods and few in number; good bond strength without waste of material favors small rods. If bent rods are to be used for web reinforcement, then numerous small rods are also advantageous. If the bond strength is not in question, or can easily be taken care of, then large rods are desirable, but more stirrups or other secondary reinforcement may be needed than where small rods are used.

127. Economical Proportions and Working Stresses.—For given unit prices, the cost of concrete beams per unit of resisting moment will vary with the proportions adopted for breadth and depth, and with the working stresses employed. Because of the mutual relations between the concrete and steel it may happen that the maximum economy of construction may be obtained by using less than the allowable working stresses in one or the other of the two materials. It will therefore be useful to investigate the effect on cost of variations in proportions and in the working stresses.

Consider a portion of a rectangular beam one unit in length.

Let c = cost of concrete per unit volume;

r = ratio of cost of steel to cost of concrete per unit volume;

p = ratio of steel area to concrete area;

C = cost of beam per unit length.

Then $C = c(bd + rpbd) = cbd(1 + rp)$ (1)

From Art. 59 we have $bd^2 = M/R$, in which M = bending

moment and R = coefficient of strength of the beam, depending in value only upon f_s , f_c , and n . From this we may write $bd = M/Rd$, $bd = \sqrt{Mb/R}$, and $bd = \sqrt[3]{(b/d)(M^2/R^2)}$, whence we derive the three expressions for cost:

$$C = c(1 + rp) \frac{M}{Rd}, \quad . \quad . \quad . \quad . \quad . \quad (2)$$

$$C = c(1 + rp) \sqrt{\frac{Mb}{R}}, \quad . \quad . \quad . \quad . \quad . \quad (3)$$

and
$$C = c(1 + rp) \sqrt[3]{\frac{b}{d} \cdot \frac{M^2}{R^2}}, \quad . \quad . \quad . \quad . \quad . \quad (4)$$

128. General Effect of Varying Proportions.—Since the values of R and p depend only on f_s , f_c and n we note from (2) that the cost of a rectangular beam to support a given moment, M , varies inversely with the depth; and from (3) that the cost varies directly with $\sqrt{\text{breadth}}$; and finally, from (4) that it varies with the cube root of the ratio of breadth to depth. In all cases it is assumed that the two dimensions are made to correspond with each other as calculated from the selected values of f_s and f_c . It follows from (2) that with given values of f_s and f_c the deeper the beam the less the cost, so long as b can be reduced accordingly. The depth will, however, be limited in various ways. It may be limited by the requirement of shearing stress fixing the value of bd , or it may be limited by the head room required, or it may practically be limited by the fact that a certain breadth is necessary to give a convenient and proper covering of the steel reinforcement or to give a beam of satisfactory proportions. In the construction of continuous surfaces, such as floor slabs, the case is one of fixed width, since the width of beam to carry the load coming upon a strip one foot wide is also one foot. We may then consider four cases according to the particular feature of the design which is the controlling element. These cases are:

- (a) When the area of cross-section is determined by the shear;
- (b) When the depth of the beam is fixed;




FIG. 58.—Relative Cost for Fixed Depth.

that for values of f_c of 500 or 600 lbs/in² no economy is secured by using values of f_s greater than 12–14,000 lbs/in². For larger values of r or of f_c , higher values can economically be used for f_s , but a value of 80 for r is not likely to be greatly exceeded. If the cost of concrete be as low as 20 c. per cu. ft. the corresponding cost of steel would be \$16.00 per cu. ft., or 3.2 c. per pound. This is a low cost of concrete and a high cost of steel. The diagram shows that the cost is decreased by increased values of f_c .

131. (c) *The Width of the Beam is Fixed.*—From eq. (3) the cost for given values of M and b varies with $(1+rp)/\sqrt{R}$. Fig. 59 represents this quantity plotted for various values of f_s and f_c . Comparing this with Fig. 58 it is seen that somewhat higher values of f_s are warranted, but it is evident that the gain in economy is very small for values above 16,000 lbs/in², except where the steel is very expensive and the concrete cheap.

132. (d) *The Ratio of Width to Depth is Fixed.*—It is often desired to secure approximately a certain given ratio of breadth to depth. In this case we find from eq. (4) that the cost will vary with $(1+rp)/R^{\frac{3}{2}}$. Fig. 60 represents this quantity for various values of f_s and f_c . It is seen that the most economical values will lie between those of cases (b) and (c).

133. *Floor Slabs with Weight of Concrete Eliminated.*—In all the foregoing discussion the moment to be resisted has included that due to the weight of the beam itself. For large beams and girders this is unimportant in this connection, but with floor slabs, where the external load is small, the weight of the material itself modifies the results to a large extent. General results cannot be presented for all cases, but the analysis will be given for a single case representing ordinary conditions. A span length of 10 ft. has been taken and a net floor load of 150 lbs/ft². Then from Table No. 21, Chap. VI, the required cross-section and amount of steel has been determined for various values of f_s and f_c . The relative cost per unit floor area has been calculated for values of r of 40, 60, 80, and 100 and the results plotted in Fig. 61. Comparing these results with those of Fig. 59, where the weight of the beam has not been deducted,




FIG. 59.—Relative Cost for Fixed Width.




FIG. 60.—Relative Cost for Fixed Ratio, Breadth to Depth




FIG. 61a.—Relative Cost for Fixed Breadth, Weight of Beam Deducted.




FIG. 61b.—Relative Cost for Fixed Breadth, Weight of Beam Deducted.

it is seen that the economical values of f_s are considerably less. For values of r not exceeding 60 and for f_c not exceeding 500 there is no reason for using a value for f_s higher than 14,000 lbs/in². For other spans and floor loads the results will be somewhat different, but the variation will not be great. Larger floor loads and shorter spans will give results more nearly approaching those of Fig. 59; smaller loads and longer spans will tend in the opposite direction.

Percentages of steel corresponding to any particular values of f_c and f_s are given by reference to Plate III, p. 215.

134. Effect of Overlapping Bars.—In most cases the reinforcing bars of slabs are made to overlap more or less; where negative moment over the beams is taken care of this overlapping may be 25 to 30 per cent. To take account of this in using the equations or diagrams of the preceding articles, the most convenient method is to increase the unit cost of steel, or the ratio r , by the same percentage that measures the overlap of the steel.

135. T-Beams.—In the case of T-beams, the slab forms practically all the compressive area, but does not enter into the cost of the beam. Using the approximate formula, eq. (7), of Art. 74 the area of the steel is equal to $M/f_s(d' + \frac{1}{2}t)$, in which d' is the depth of beam *below* the slab. The cost is then

$$C = c \left[b'd' + \frac{rM}{f_s(d' + \frac{1}{2}t)} \right] \dots \dots \dots (1)$$

From this expression it is evident that the cost will decrease with increased values of f_s under all conditions, and that with a fixed value of $b'd'$ the cost decreases with increase in depth. If d' is fixed then the cost will be a minimum when b' is made as small as possible, and its value will then be determined by the shearing stress or by the space required for the bars. If the value of b' is assumed as fixed, then there is a definite value of d' which will give minimum cost. Considering d' as variable and b' as constant we find by differentiation that for

minimum cost the value of d' is given by the equation

$$d' + t/2 = \sqrt{rM/f_s b'}. \quad (2)$$

From this expression the best depth for various assumed widths can readily be determined and the desirable proportions finally selected.

T-beams should not be made too deep in proportion to width, as such forms are relatively weak at the junction of stem and flange. All re-entrant angles in rigid material such as concrete are points of weakness and such angles should therefore be modified by curved lines or made obtuse by sloping the sides of the beam. A width of beam sufficient to carry the shear and to give plenty of space for the bars is usually ample. The maximum desirable ratio of depth to width may be taken at about two for small beams up to three or four for very large and massive work. Depths are often determined by available head room. Beams of excessive depths are objectionable as being more difficult and troublesome to reinforce properly; the cost of web reinforcement also becomes relatively greater.

COLUMNS.

136. Working Stresses.—The working stresses for columns should represent at least as great a factor of safety as for beams. The experiments noted in Chapter IV indicate that concrete in the form of a column is not as strong as in the cube or beam form. A value of about 1600 lbs/in² for 1:2:4 plain concrete would seem to be a fair value for ultimate strength, and applying a factor of safety of four gives a working stress of 400 lbs/in².

The working stress in the steel is a function of the working stress in the concrete and the ratio, n , of the moduli of elasticity of the two materials. If this ratio is taken at 12, then the working stress in the steel must be, in the above case, $12 \times 400 = 4800$ lbs/in². Under working loads the steel is therefore stressed only to a very low value.

Let us consider the variation in the stresses in a column subjected to increasing loads. Fig. 62 represents a stress-strain diagram of 1:2:4 concrete in compression. The modulus up to 500–600 lbs/in² is, say, 2,500,000; the modulus at rupture (ratio of stress to total deformation) is perhaps only 1,000,000. In Fig. 63 let abscissæ represent unit stress in concrete in the given column up to 1600 lbs/in². Let the ordinates above the axis represent the total stress in the steel corresponding to various unit stresses in the concrete. For low values of f_c the value of n is 12 and $f_s = 12f_c$. For higher values of f_c the value of n increases until at the maximum of 1600 lbs/in², $n = 30$ and $f_s = 30f_c$, or 48,000 lbs/in². The curve OAB rep-




FIG. 62.




FIG. 63.

resents the variation in the total stress $f_s A_s$. The total stress on the concrete, $f_c A_c$, may likewise be conveniently represented by ordinates from OX to a straight line OC , the scale below OX representing concrete stress. Then for any load causing a particular unit stress in the concrete, the total ordinate between the lines OB and OC will represent this load. From this it is plain that with increasing loads the steel receives a greater proportionate stress, the variation in the amount carried by the steel depending on the variation in the value of n . It is also evident from this diagram that the ultimate load on the column is much greater than four times the load which produces the

stress of 400 lbs/in² in the concrete. Hence if the working stress in the concrete is based on a factor of safety of four relative to plain concrete, then the factor of safety of the reinforced column will be greater than four. The case is somewhat similar to that of the beam. Obviously the total load increases more rapidly than the value of the stress f_c , the exact rate depending on the relative amount of steel and the variation in n .

For purpose of calculation the formula of Art. 95, Chap. III, is convenient. From this the total load for a reinforced column is

$$P' = Af_c[1 + (n-1)p], \quad . \quad . \quad . \quad . \quad (1)$$

in which p = steel ratio and A = total area.

To give a numerical illustration, let $p=1\%$, $f_c=400$, and $n=12$; then $P'=400A \times 1.11$. For $f_c=1600$ and $n=30$, $P'=1600A \times 1.29$. The second value is 4.65 times the former value, thus giving to the column a factor of safety relative to rupture of 4.65.

One result of the increased stress taken by the steel under increasing loads is that columns containing different amounts of steel will have different factors of safety relative to ultimate strength, even though calculated for the same working stresses. For example, consider a series of columns in which $p=1, 2, 3, 4$, and 5 per cent, and all having the same area A . Their relative strengths at a value of $f_c=400$ and $n=12$ will be as represented by the quantities 1.11, 1.22, 1.33, 1.44, 1.55. At ultimate load, determined by the value of 1600 for f_c and with $n=30$, the relative strengths will be as 4×1.29 , 4×1.58 , 4×1.89 , 4×2.16 , and 4×2.45 . Dividing this series by the former series we have the factors of safety as follows: 4.65, 5.18, 5.68, 6.00, and 6.32. The column having 5% of steel has therefore a factor of safety 1.36 times as great as the column with 1% of steel.

In order to secure a more uniform factor of safety, and to take some account of the fact that under increasing loads the steel receives an increasing proportion, it would seem desirable to use a value of n in the calculations somewhat larger than

that which is obtained by taking a value of E_c corresponding to very low stresses. A value of 15 or even 20 might well be taken for 1:2:4 concrete. On this basis the calculations will give a little more stress in the steel than actually exists under the usual working loads, but will give too small stress under ultimate loads. In the case of hooped columns it is not yet clear just what weight should be given to this form of reinforcement. Until further tests are available it would hardly seem wise to assign any greatly increased value to this form over longitudinal metal, although such a column undoubtedly is capable of greater deformation, or possesses greater "toughness".

137. Economy in the Use of Reinforced Columns.—From eq. (1) we see that with a value of $n=15$, the use of each 1% of steel adds 14% to the strength of a column. If the ratio of cost of steel to cost of concrete per unit volume be 50, then the increased cost of a column with 1% of steel will be $50 \times 1\% = 50\%$. The gain in strength being only 14%, the relative economy of the reinforced column is only $\frac{14}{114} = 76\%$ that of the plain concrete. Again, take a very strong mixture, such as 1:1 mortar, whose working stress may possibly be taken as high as 800 lbs/in². Such a mortar will cost perhaps \$12.00 per cu. yd. (not including forms, etc.) or 45 c. per cu. ft. Placing steel at the low value of 2 c. per lb., the cost ratio becomes 22.5. Such concrete will have a value of E_c of at least 3,000,000, giving $n=10$. Hence 1% reinforcement will add 9% to the strength and 22.5% to the cost. If a cheap concrete be taken with a low modulus the steel will add a larger percentage of strength, but at the same time a much greater percentage of cost. Another way of considering this question is from the standpoint of working stresses in the steel, which can scarcely be greater than 8000 lbs/in² under working conditions. The cost to carry a given load on the steel is then $(P/8000) \times \text{cost of steel}$. With 500 lbs/in² working stress in concrete the cost to carry the load on the concrete is $(P/500) \times \text{cost of concrete}$. The relative cost of the two materials is then

$(500/8000) \times$ cost ratio of steel to concrete. If this ratio = 50 then the relative cost = $25,000/8000 = 3\frac{1}{2}$; that is, the steel is $3\frac{1}{2}$ times as costly as an equivalent amount of concrete.

The above analysis shows that from the standpoint of theoretical economy the use of steel in columns is undesirable, and were this the only consideration it would not be used, at least in the form discussed. While no economy can be figured for the use of steel in columns it is by no means valueless. In practice, columns are subjected to bending moments uncertain in amount, but for which something more than plain concrete is desired, especially where the column is of considerable length. It is in such columns that tensile stresses are most apt to occur and where steel is most needed. Furthermore, steel is a more reliable material than concrete, and in small sections where the danger of weak or imperfect spots in the concrete is greatest, steel reinforcement is of great value in producing a more reliable structure. Then, again, great strength may be desired from small sections in order to save space, in which case steel may be used. In very large (relatively short) columns little is to be feared from bending stresses, as in such a case no resultant tensile stress is likely to occur. In general the above discussion shows that where the concrete may be assumed to carry its share of the load the amount of longitudinal steel should be made small, the amount preferably increasing with increasing ratio of length to diameter.

138. Use of Steel of High Elastic Limit.—In order that the elastic limit of the steel may not limit the strength of the column it must be somewhat high. If the ultimate strength of the concrete be 1600 lbs/in^2 and for this stress $n=30$, then at rupture the stress in the steel will be $48,000 \text{ lbs/in}^2$. For weaker and stronger concretes the product of f_c and n will not be greatly different, as the value of E_c varies with the strength of the concrete. For columns, therefore, a steel with an elastic limit of $45,000$ to $50,000 \text{ lbs/in}^2$ is desirable, otherwise the elastic limit of the steel will need to be taken into account in determining the ultimate strength, and in estimating the real factor

of safety and hence the working stresses. The behavior of mild-steel in columns when stressed beyond its elastic limit is not well determined. Tests where mild and hard steels have been used side by side show less difference in ultimate strength than would be expected. Supported by the surrounding concrete, buckling cannot take place until the concrete fails, hence the resistance of the rods in compression is probably greater than in an ordinary compression test.

139. Use of Steel at Ordinary Working Stresses.—From the preceding discussion it is seen that so long as the stresses in the concrete are kept within ordinary working values of 400 to 500 lbs/in² the stress in the steel will be much below usual working limits. Thus with a value of 400 for f_c and $n=15$, f_s is only 6000 lbs/in², or less than one-half its safe value. Under these conditions it is a question whether it may not be more advantageous to use a higher working stress in the steel and place little or no dependence on the concrete for carrying direct stress. The relation of the necessary quantities of steel and of working stresses for such a case as compared to the usual reinforced column will be determined.

If A = total area of reinforced concrete column;

pA = area of steel in the reinforced column;

A_s' = area of steel in a steel column using customary working stresses;

f_c = the working stress in the concrete;

f_s = the usual working stress in the steel for an all-steel column;

then for equal strength

$$f_c A [1 + (n-1)p] = f_s A_s' \quad (1)$$

Assuming the areas of the steel equal in the two cases ($pA = A_s'$) and solving for p we get

$$p = \frac{f_c}{f_s - f_c(n-1)} \quad (2)$$

This is the percentage of steel which, if used in the reinforced column, will give the same total section of steel as will be required in an all-steel column under the working stress f_s . If, for example, $f_c=400$, $n=15$, and $f_s=16,000$, we have $p=400 \div (16,000 - 400 \times 14) = 3.8\%$. This calculation indicates that columns reinforced with large amounts of steel are not likely to compare favorably in cost with the all-steel column, although the elements of pound cost of steel and of fireproofing must, of course, be considered.

The question now arises as to when a combination steel-concrete column should be calculated as a reinforced column and therefore with reference to safe stress on the concrete and when it may be calculated as an all-steel column merely surrounded by concrete. Evidently where the steel is used only in small sections and depends mainly upon the concrete for rigidity the column must be calculated with reference to the safe concrete stress, but where the steel is in a form to be able to act as a column independently of the concrete, then it would be proper to calculate the strength in either way. As to how much should be allowed for the concrete when the steel in such a column is stressed up to 16,000–18,000 lbs/in² is uncertain. Ordinarily nothing is allowed, but undoubtedly the ultimate strength of such columns is very considerably increased by the surrounding body of concrete. It would seem that a moderate amount of hooping would in this case be very advantageous. It would render the concrete "tough" and reliable under the relatively large deformations corresponding to the working stress in the steel. This would enable it to be depended upon for a certain amount of resistance. Tests on this form of column are much needed.

DURABILITY OF REINFORCED CONCRETE.

140. The Protection of Steel from Corrosion.—A continuous coating of Portland cement has been found by experience to be a practically perfect protection of steel against corrosion. The rusting of iron requires the presence of moisture and carbon

dioxide. Portland cement not only forms a coating which excludes the moisture and CO_2 , but in hardening it absorbs CO_2 , tending to remove any of this gas which may be present. In practice the protective nature of Portland-cement concrete has long been known, and its use as a paint was adopted by the Boston Subway Engineers after careful investigation.

While an unbroken coating of cement offers what appears to be a perfect protection, the value of a concrete as actually deposited may be very much less. A series of experiments made by Professor Charles L. Norton gives valuable information on this subject. In one series, small specimens of steel 6" long were embedded in blocks 3" \times 3" \times 8" in size of various mixtures of cement, sand, and stone or cinders. The blocks were then exposed for three weeks to various corrosive atmospheres consisting of steam, air, and CO_2 . The results were as follows: The neat cement furnished perfect protection. The specimens embedded in mortars and concretes showed spots of rust at voids or adjacent to a badly rusted cinder. He concludes that concrete to be an effective protection should be mixed quite wet so as to furnish a thin coating on the metal, and must be free from voids and cracks. He finds that dense cinder concrete mixed wet is as effective as stone concrete.

In a second series of experiments on steel already rusted, from a slight stain, to a deep scale, the following results were obtained: The concrete was 1:2½:5 (stone) and 1:3:6 (cinders). After one to three months in corrodors and one to nine months in damp air no specimen showed any change except where the concrete was poorly applied. Some of the concrete was purposely made very dry and the rods were not well covered. These specimens were seriously corroded. Unprotected steel specimens subjected to the same treatment were almost entirely corroded. While the experiments of Professor Norton provided for a covering of 1½ inches, there is no reason to suppose that a much thinner covering, if intact, will not furnish as good protection.

Many cases have been cited of steel removed from concrete

after the lapse of 20 years or more and found to be in perfect condition. A test by Mr. H. C. Turner,* in which steel bars embedded to a depth of 3 inches in blocks of 1:2:4 and 1:3:5 concrete and exposed to sea-water and air for nine months showed perfect preservation.

141. Fireproofing Effect of Concrete.—Severe fire tests show that when concrete is subjected to red-hot temperatures (about 1700°) for three or four hours and then is quenched by hose streams, it is likely to show pitting but that it will still offer a sufficient protection to the steel.†

A reinforced-concrete building at Bayonne, N. J., was subjected to a very hot fire in the burning up of its contents but with no injury to the building.‡

In the Baltimore fire of 1904 the value of concrete as a fireproofing material, and of reinforced-concrete construction, was fully demonstrated. Professor C. L. Norton of the Insurance Engineering Experiment Station, after a careful study of the damage done by the fire, states as follows:§

“Where concrete floor arches and concrete-steel construction received the full force of the fire it appears to have stood well, distinctly better than the terra-cotta.” The reason for this he considers to be the fact that terra-cotta expands about twice as much as steel, but that concrete expands about the same. Little difference was observed between stone and cinder concrete. High temperatures long continued dehydrate and soften concrete, but this process in itself gives off water and absorbs the heat, thus protecting the interior. The layer of changed material is then a better non-conductor than before, so the process goes on very slowly. Captain J. S. Sewell, reporting to the Chief of Engineers|| on the Baltimore fire, states that, with reference to concrete construction subjected to very

* *Eng. News*, Aug., 1904, p. 153.

† See tests by Professor Ira W. Winslow in *Eng. Record*, Nov. 26, 1904, p. 634, and by Professor F. P. McKibben in *Eng. News*, Nov. 21, 1901, p. 378.

‡ *Eng. Record*, April 12, 1902, p. 341.

§ *Eng. News*, June 2, 1904, p. 524.

|| *Eng. News*, March 24, 1904.

high heats: "Exposed corners of columns and girders were cracked and spalled, showing a tendency to round off to a curve of about 3 in. radius. Where the heat was most intense the concrete was calcined to a depth of $\frac{1}{4}$ "- $\frac{3}{4}$ ", but showed no tendency to spall, except at exposed corners. On wide, flat surfaces the calcined material was not more than $\frac{1}{4}$ -in. thick and showed no disposition to come off. The terra-cotta fireproofing showed up much poorer." In his general conclusions he considers it at least as desirable as steel work protected by the best commercial hollow tiles, and preferable to tile for floor slabs and fire-proof covering. While satisfactory protection of the steel can thus doubtless be secured the effect of fire upon the concrete itself, and its usefulness after more or less calcination, is a question of the utmost importance and one on which much more information is needed.

The necessary thickness of concrete to furnish adequate fire protection depends somewhat upon the character and importance of the member. Such members as main girders, where a failure would involve a considerable portion of the building and where the steel is concentrated in a few rods, should be more thoroughly protected than floor slabs of small span, where a few local failures would be of no importance, and where additional covering would add largely to the expense. Results of fire tests and experience in conflagrations indicate that 2"-2 $\frac{1}{2}$ " will offer practically complete protection, and that a minimum of $\frac{1}{2}$ "- $\frac{3}{4}$ " for floor slabs will usually be sufficient. Large flat surfaces, such as floor slabs, are less exposed than the corners of projecting forms like beams and columns. In a report of a committee of members of the American Society of Civil Engineers on the effects of fire in the San Francisco conflagration, similar conclusions were reached as to the value of concrete as a fire-proofing material. It was also found far preferable to tile for floors. With respect to the injury to the concrete itself the committee was of the opinion that it was sufficient in many cases to require reconstruction.*

* Proc. Am. Soc. C. E., March, 1907.

142. Reinforcing Against Shrinkage and Temperature Stresses.—Where a reinforced structure is unrestrained by outside forces the only stresses arising from shrinkage and temperature changes are those due to the mutual action of steel and concrete. As the two materials have nearly equal rates of expansion temperature changes will cause very little stress. Shrinkage in hardening will cause more important stresses, as shown in Art. 43, but still not unduly large unless the steel ratio is very high.

When the structure is restrained by outside forces so that it is not free to contract or expand, as in the case of a long wall, then the resulting stresses are likely to be high. When not reinforced, concrete will, under such circumstances, crack at intervals, its maximum deformation under stress not being equal to its maximum temperature deformations. If it be assumed that concrete when reinforced will not stretch more than plain concrete, as seems probable (Art. 42), then no amount of reinforcement can entirely prevent contraction cracks. The reinforcement can, however, force such cracks to take place as they do in a beam—at such frequent intervals that the requisite deformation takes place without any one crack becoming large. Laboratory tests on beams would indicate that if steel is used in sufficient quantities the cracks may easily remain quite invisible and be of no consequence from any practical standpoint. Thus if the coefficient of expansion be .000006 a change of temperature of 50° causes a change of length (if free) of .0003 part. A deformation of this amount in a beam (corresponding to a steel stress of 9000 lbs/in²) would not cause cracks easily detected. The prevention of large cracks by means of reinforcement is then a matter of using sufficient steel to force the concrete to crack at small intervals. No one crack will open up far until the steel is stressed beyond its elastic limit, hence we may say approximately that the amount of steel used must be such that the concrete will crack elsewhere before the steel is stressed beyond its elastic limit. A larger amount of steel will serve to keep the cracks smaller.

In calculating the requisite amount of steel the temperature stress in the steel itself must be considered. This will add to its shrinkage stress, so that its total stress will equal its temperature stress plus the stress necessary to crack the concrete. If, for example, the assumed drop in temperature be 50° the temperature stress in the steel $= 50 \times .0000065 \times 30,000,000 = 9750$ lbs/in². If the tensile strength of the concrete be 200 lbs/in² and the assumed allowed stress (elastic limit) in the steel be 40,000 lbs/in², then the stress available $= 40,000 - 9750 = 30,250$ lbs/in², and the required percentage of steel $= p = \frac{200}{30,250} = .0066$. If the elastic limit be 60,000 lbs/in² the steel ratio $= p = \frac{200}{60,000 - 9750} = .004$. For the purposes here considered obviously a high elastic-limit steel is desirable, and in order to distribute the deformation as much as possible a mechanical bond is advantageous.

CHAPTER VI.

FORMULAS, DIAGRAMS, AND TABLES.

103. Rectangular Beams; Linear Variation of Stress.




FIG. 64.

Notation.

- f_s = unit stress in steel;
- f_c = " " " concrete;
- E_s = modulus of elasticity of steel;
- E_c = " " " " concrete;
- $n = E_s/E_c$;
- T = total tension;
- C = " compression;
- M_s = moment of resistance relative to the steel;
- M_c = " " " " " " " concrete;
- M = bending moment or moment of resistance in general;
- A = steel area;
- b = breadth of beam;
- d = net depth of beam;
- k = ratio of depth of neutral axis to depth d ;
- j = ratio of lever-arm of resisting couple to depth d ;

p = steel ratio = A/bd ;
 $R_s = f_s p j$ = "coefficient of strength" relative to steel;
 $R_c = \frac{1}{2} f_c k j$ = " " " " " " concrete.

Formulas.

Position of neutral axis,

$$k = \sqrt{2pn + (pn)^2} - pn. \quad . \quad . \quad . \quad . \quad . \quad (1)$$

Arm of resisting couple,

$$j = 1 - \frac{1}{3}k. \quad . \quad . \quad . \quad . \quad . \quad . \quad (2)$$

Moment of resistance,

$$M_s = f_s p j \cdot bd^2 = R_s \cdot bd^2, \quad . \quad . \quad . \quad . \quad . \quad (3)$$

$$M_c = \frac{1}{2} f_c k j \cdot bd^2 = R_c \cdot bd^2. \quad . \quad . \quad . \quad . \quad . \quad (4)$$

Approximately,

$$M_s = f_s A \cdot \frac{7}{8}d, \quad . \quad . \quad . \quad . \quad . \quad . \quad (3')$$

$$M_c = f_c \cdot \frac{1}{6}bd^2. \quad . \quad . \quad . \quad . \quad . \quad . \quad (4')$$

Fibre stresses,

$$f_s = \frac{T}{A} = \frac{M \div jd}{A}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

$$f_c = \frac{2C'}{bkd} = \frac{2M \div jd}{bkd}. \quad . \quad . \quad . \quad . \quad . \quad (6)$$

Steel ratio,

$$p = \frac{1}{2} \cdot \frac{1}{\frac{f_s}{f_c} \left(\frac{f_s}{nf_c} + 1 \right)}. \quad . \quad . \quad . \quad . \quad . \quad (7)$$

Cross-section of beam for given bending moment M ,

$$bd^2 = \frac{M}{f_s p j} = \frac{M}{R_s}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (8)$$

$$bd^2 = \frac{M}{\frac{1}{2} f_c k j} = \frac{M}{R_c}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (9)$$

Diagrams.—Plates I–IV, pp. 213–216, are diagrams of values of k and j for various values of p ; and values of R_s and R_c (called simply R) for various values of p and of f_s and f_c . The value of n is taken at 10, 12, 15, and 18 respectively.

The use of the diagrams in finding moments of resistance (Eqs. (3) and (4)) and in determining cross-sections (Eqs. (8) and (9)) is obvious. The proper steel ratio, p , to use for given values of f_s and f_c (Eq. (7)) is determined from the intersection of the curves for the given values of f_s and f_c . Finally, the actual fibre stress, f_s or f_c , resulting from a given M , p , and bd^2 will be found by first calculating M/bd^2 from the given values. Call this R . Then with this value of R and the given value of p enter the diagram and find the corresponding values of f_s and f_c .

ILLUSTRATIVE EXAMPLES.—1. *Moment of Resistance.*—Given the following: $b=12''$, $d=20''$, $f_s=14,000$, $f_c=600$, and $p=0.8\%$; find M_s and M_c . Assume $n=15$. *Solution.* From Plate III, p. 215, we find for $p=0.8\%$ and $f_s=14,000$, $R_s=96$; and for $f_c=600$, $R_c=100$. Hence $M_s=96bd^2=460,800$ in-lbs., and $M_c=100bd^2=480,000$ in-lbs.

2. *Fibre Stresses.*—Given $b=12''$, $d=20''$, $p=0.8\%$, and $M=450,000$ in-lbs., to find f_s and f_c . *Solution.* Use Eqs. (5) and (6) directly; or, find M/bd^2 and use the diagrams. Thus $M/bd^2=450,000/4800=93.75$. Then from Plate III, with $R=93.75$ and $p=0.8\%$ we find f_s =about 13,500 and f_c =about 560 lbs/in².

3. *Cross-section of Beam and Steel Ratio.*—Given $M=500,000$ in-lbs., $f_s=12,000$, $f_c=500$, to find bd^2 . *Solution.* From Plate III we find at the intersection of the curves for $f_s=12,000$ and $f_c=500$, a value of R of 84. Hence $bd^2=500,000/84=5950$. The required amount of steel is also found from the diagram to be 0.8% .

144. Rectangular Beams; Parabolic Variation of Stress; for Ultimate Loads.

Notation.—

As in Art. 143, but here $R_c = \frac{2}{3}fkj$.

Formulas.

Position of neutral axis,

$$k = \sqrt{3pn + (\frac{3}{2}pn)^2} - \frac{3}{2}pn. \quad . \quad . \quad . \quad . \quad (10)$$

Arm of resisting couple,

$$j = 1 - \frac{2}{3}k. \quad . \quad . \quad . \quad . \quad . \quad . \quad (11)$$

Moment of resistance,

$$M_s = f_s p j \cdot b d^2 = R_s \cdot b d^2, \quad . \quad . \quad . \quad . \quad . \quad (12)$$

$$M_c = \frac{2}{3} f_c k j \cdot b d^2 = R_c \cdot b d^2. \quad . \quad . \quad . \quad . \quad (13)$$

Approximately,

$$M_s = f_s A \cdot 0.8d, \quad . \quad . \quad . \quad . \quad . \quad (12')$$

$$M_c = f_c \cdot 0.28 b d^2. \quad . \quad . \quad . \quad . \quad . \quad (13')$$




FIG. 65.

Fibre stresses,

$$f_s = \frac{T}{A} = \frac{M \div jd}{A}, \quad . \quad . \quad . \quad . \quad . \quad (14)$$

$$f_c = \frac{\frac{2}{3}C}{bkd} = \frac{\frac{2}{3}M \div jd}{bkd}. \quad . \quad . \quad . \quad . \quad . \quad (15)$$

Steel ratio,

$$p = \frac{2}{3} \cdot \frac{1}{\frac{f_s}{f_c} \left(\frac{f_s}{2n f_c} + 1 \right)}. \quad . \quad . \quad . \quad . \quad . \quad (16)$$

Cross-section of beam for given bending moment M ,

$$b d^2 = \frac{M}{f_s p j} = \frac{M}{R_s}, \quad . \quad . \quad . \quad . \quad . \quad (17)$$

$$b d^2 = \frac{M}{\frac{2}{3} f_c k j} = \frac{M}{R_c}. \quad . \quad . \quad . \quad . \quad . \quad (18)$$

Diagrams.—Plate V, p. 217, is a diagram of values of k and j for various values of p ; and values of R_s and R_c for various values of p , f_s , and f_c . The full lines are drawn for $n=15$; the dotted lines for $n=12$. The fibre stresses are here assumed as representing ultimate strengths, and the diagram is supposed to give results pertaining to ultimate strength. To use it for purposes of designing, the given loads or moments should be multiplied by the selected factor of safety, or the value of R obtained from the diagram divided by such factor of safety.

145. T-Beams; Linear Variation of Stress.




FIG. 66.

Notation. (In addition to that of Art. 143.)

b = width of flange;

b' = width of web;

t = thickness of flange;

c = depth of neutral axis;

x = depth of resultant of compressive stress;

$d - x$ = arm of resisting couple.

Formulas.

Case I. Neutral axis in the flange.

Use formulas (1)–(9) as for rectangular beams; formula (1) for k will determine whether the case is I or II.

Approximately,

$$M_s = f_s A (d - \frac{1}{3}t), \quad \dots \dots \dots (19)$$

$$A = \frac{M}{f_s (d - \frac{1}{3}t)}, \quad \dots \dots \dots (20)$$

Case II. Neutral axis in the web; compression in web neglected.

Position of neutral axis,

$$c = \frac{2ndA + bt^2}{2(nA + bt)} \quad \dots \dots \dots (21)$$

Position of resultant of compressive stress,

$$x = \frac{3c - 2t}{2c - t} \cdot \frac{t}{3} \quad \dots \dots \dots (22)$$

Moment of resistance,

$$M_s = f_s A (d - x), \quad \dots \dots \dots (23)$$

$$M_c = f_c \frac{(c - \frac{1}{2}t)bt}{c} (d - x). \quad \dots \dots \dots (24)$$

Approximately,

$$M_s = f_s A (d - \frac{1}{2}t), \quad \dots \dots \dots (23')$$

$$M_c = \frac{1}{2} f_c bt (d - \frac{1}{2}t). \quad \dots \dots \dots (24')$$

Steel area,

$$A = \frac{M}{f_s (d - x)}. \quad \dots \dots \dots (25)$$

Approximately,

$$A = \frac{M}{f_s (d - \frac{1}{2}t)}. \quad \dots \dots \dots (25')$$

146. Beams Reinforced for Compression.

Notation. (In addition to that of Art. 143.)

A' = area of compressive steel;

p' = steel ratio of compressive steel;

f_s' = unit stress in " "

C' = total stress in the compressive steel;

d' = distance from compressive face to the plane of the compressive steel;

x = depth to resultant compression, $C + C'$.

Diagrams.—Values of k and j are given in Fig. 29, p. 86, for various values of p and of p' . It is assumed that $d'/d = 1/10$ and $n = 15$. Plate VI, p. 218, gives the amount of compressive steel (values of p') necessary to use in order to reduce the compressive fibre stress, f_c , any given percentage below the value it would have with no compressive reinforcement. The effect of this compressive steel upon the value of the tensile stress in the steel is also given in the diagram for various values of p and p' .

147. Flexure and Direct Stress.—There are two cases:

- I. Where there is compression on the entire cross-section (Figs. 68 and 69);
- II. Where there is some tension on the cross-section (Fig. 70).




FIG. 68.




FIG. 69.




FIG. 70.

Notation.—The lower side of the beam in the figures on the preceding page is called the “tension face”.

R = resultant force acting on the section;

N = component of R normal to section;

e = eccentric distance of R , e/h = eccentricity;

M = bending moment = Ne ;

A' = area of steel near compressive face;

$p' = A'/bh$;

A = area of steel near tension face;

$p = A/bh$;

d' = distance of compressive steel from face;

u = distance from compressive face to centroid of transformed section;

a = distance from steel to center of section for symmetrical reinforcement;

A_t = area of transformed section;

I_c = moment of inertia of concrete about central axis of transformed section;

I_s = moment of inertia of steel about central axis of transformed section;

I_t = moment of inertia of transformed section;

f_c = maximum compressive fibre stress in concrete;

f'_c = maximum tensile fibre stress in concrete;

f'_s = stress in steel near compressive face;

f_s = stress in steel near tension face;

Formulas.

General.

$$A_t = bh + n(A + A'), \quad . \quad . \quad . \quad . \quad . \quad . \quad (34)$$

$$I_t = I_c + nI_s, \quad . \quad . \quad . \quad . \quad . \quad . \quad (35)$$

$$u = \frac{\frac{1}{2}bh + npd + np'd'}{1 + np + np'} \quad . \quad . \quad . \quad . \quad . \quad . \quad (36)$$

Case I. Compression on the entire cross-section.

Fibre stresses:

$$f_c = \frac{N}{A_t} + \frac{Mu}{I_t}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (37)$$

$$f'_c = \frac{N}{A_t} - \frac{M(h-u)}{I_t}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (38)$$

$$f'_s = n \left(\frac{N}{A_t} + \frac{M(u-d')}{I_t} \right), \quad . \quad . \quad . \quad . \quad . \quad . \quad (39)$$

$$f_s = n \left(\frac{N}{A_t} - \frac{M(d-u)}{I_t} \right). \quad . \quad . \quad . \quad . \quad . \quad . \quad (40)$$

If f'_c is negative, then the case is Case II.

For symmetrical reinforcement and for $d'/d=1/10$,

$$\frac{M}{bh^2f_c} = \frac{1}{12k} \left(1 + 24np \frac{a^2}{h^2} \right), \quad . \quad . \quad . \quad . \quad . \quad . \quad (41)$$

$$f'_s = nf_c \left(1 - \frac{d'}{kh} \right). \quad . \quad . \quad . \quad . \quad . \quad . \quad (42)$$

Case II. Tension on part of the cross-section.

If the tension in the concrete is considered, use the formulas of Case I.

For symmetrical reinforcement and for $d'/d=1/10$,

$$f'_c = f_c \frac{1-k}{k}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (43)$$

$$f_s = nf'_c \left(1 - \frac{d'}{(1-k)h} \right). \quad . \quad . \quad . \quad . \quad . \quad . \quad (44)$$

If the tension in the concrete is neglected.

For symmetrical reinforcement and for $d'/d=1/10$,

$$\frac{M}{bh^2f_s} = \frac{1}{12k} (3-2k) + \frac{2pn}{k} \cdot \frac{a^2}{h^2}, \quad . \quad . \quad . \quad . \quad . \quad . \quad (45)$$

$$f'_s = nf_c \left(1 - \frac{d'}{kh} \right), \quad . \quad . \quad . \quad . \quad . \quad . \quad (46)$$

$$f_s = f'_s \frac{(1-k)h-d'}{kh-d'} = nf_c \frac{(1-k)h-d'}{kh}. \quad . \quad . \quad . \quad . \quad . \quad (47)$$

Diagrams.—Values of $1/k$ for Case I, Eqs. (41) and (42), and Case II, Eqs. (43) and (44), are given in Fig. 33, p. 95; and values of k for Case II, Eqs. (45) and (46), are given in Fig. 35, p. 98. Plate VII, p. 219, is a diagram for values of M/bh^2f_c for Case I, Eq. (41); and Plate VIII for the same quantity for Case II, Eq. (45), given in terms of the eccentricity e/h and the steel ratio p . The diagrams are constructed for $n=15$.

ILLUSTRATIVE EXAMPLES.—I. An arch ring is 24 in. deep and is symmetrically reinforced. For each side $p=0.9\%$. On a width of 12 in. $N=75,000$ lbs.; $e=3$ in.; what is the maximum stress f_c ? *Solution.* The eccentricity $=3/24=.125$. The diagram of Plate VII will be used, and the case is Case I. This diagram gives at once $M/bh^2f_c=.097$. We also have $M=75,000 \times 3=225,000$ in.-lbs. Hence $f_c=225,000/(12 \times 24^2 \times .097)=336$ lbs/in².

2. If, in Ex. 1, the eccentricity be 6 in., find the maximum compressive stress f_c and the maximum tensile stress f'_c , the concrete being considered as carrying tension if necessary. *Solution.* Use Plate VII. The eccentricity is $6/24=.25$. From the diagram we find $M/bh^2f_c=.141$, whence $f_c=572$ lbs/in². From Eq. (10), p. 94, the value of $k=.9$. This being less than unity there will be tension on the section. From Eq. (43) the tensile concrete stress $=f'_c=64$ lbs/in².

3. If in Ex. 2 the tension in the concrete be neglected, find f_c , f'_s , and f_s . *Solution.* Use Plate VIII. $e/h=.25$. The value of $M/bh^2f_c=.14$, whence $f_c=576$ lbs/in². The compressive stress in the steel, f'_s , is always less than nf_c ; in this case it is, from Eq. (46), equal to $nf_c \times \left(1 - \frac{1}{11k}\right) = nf_c \times .88$, k being found from Fig. 35. The tensile steel stress, f_s , is less than the compressive. From Eq. (47) it is found to be 276 lbs/in².

148. Shearing and Bond Stress.

Notation.

V = total vertical shear at any section;

v = maximum horizontal or vertical shearing stress per unit area;

v' = average shearing stress per unit area;

U = bond stress per unit length of beam;

b and d = dimensions of a rectangular beam;

b' = width of web of T-beam;

$$d = \text{net depth of T-beam;}$$
 t = flange thickness of T-beam;

jd = arm of resisting couple for any beam.

Formulas.

Rectangular beams:

$$v' = \frac{V}{bd}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (48)$$

$$v = \frac{V}{bid}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (49)$$

$$U = \frac{V}{id} (50)$$

Approximately,

$$v = \frac{V}{b \cdot \frac{7}{8}d} = \frac{8}{7}v'. \quad . \quad . \quad . \quad . \quad . \quad (49')$$

$$U = \frac{8}{7} \frac{V}{d} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (50')$$

T-beams:

$$v' = \frac{V}{b'd'}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (51)$$

$$v = \frac{V}{b_{jd}}, \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (52)$$

$$U = \frac{V}{id}, \dots \dots \dots (53)$$

Approximately,

$$v = \frac{V}{b'(d - \frac{1}{2}t)}, \quad \cdot \quad \cdot \quad \cdot \quad \cdot \quad \cdot \quad (52')$$

$$U = \frac{V}{d - \frac{1}{2}t}. \quad . \quad . \quad . \quad . \quad . \quad . \quad (53')$$

149. Columns.

Notation.

A = total cross-section:

A_c = cross-section of concrete;

$A_s =$ " " longitudinal steel;

150. Stresses in Circular Plates.—The exact determination of stresses in floor systems, such as the “mushroom” system described in Art. 168, and in the ordinary foundation-plate supporting a single column, involves very complex analytical processes. As an aid in estimating the stresses in such cases, Plates X and XI have been prepared. They give the bending moments in circular plates supported rigidly over any given area at the center. Plate X gives the moments for the case of a uniformly distributed load on the entire area, and Plate XI the moments for a load uniformly distributed along the periphery. In each case the full lines give the coefficients for the radial bending moments, and the dotted lines those for the circumferential bending moments. The curves are drawn for five different ratios of r_1 to r_0 , or radius of plate to radius of fixed support. For other ratios interpolations may be made.

The calculations for the diagrams are based upon the analysis presented by Prof. H. T. Eddy* for homogeneous plates. The value of Poisson's ratio assumed in the numerical substitutions has been 0.1, as approximately determined in recent experiments by Prof. A. N. Talbot.

Example.—A circular plate 10 ft. in diameter is rigidly supported by a column 24 in. in diameter. It supports a load of 150 lbs/ft² over the area and a load of 500 lbs/ft along its outer circumference. Required, the radial and circumferential bending moments.

Solution. The ratio of $r_1:r_0=120:24=5$. (The upper diagram of Plate XI may be used in finding this ratio.) In Plate X we then obtain the coefficients Q_1 and Q_2 for any desired point in the plate, using the curves corresponding to $r_1:r_0=5$. The value of Q_1 (ordinate to dotted curve) is seen to be a maximum at a distance from the center equal to about $1.7r$; its value is about 4.7. Hence the maximum circumferential moment due to the load of 150 lbs/ft is $4.7 \times 150 \times 1^2 = 705$ ft-lbs per foot width of section. The value of Q_2 (ordinate to full curve) is a maximum at the edge of the support and has a value of 16. The radial bending moment is therefore equal to $16 \times 150 \times 1^2 = 2400$ ft-lbs per foot

* Year Book, Engrs. Soc., Univ. of Minn., 1899.

width of section. The radial moment rapidly falls off with increased distance from the support.

The moments due to the peripheral load of 500 lbs/ft are found from Plate XI to be respectively $M_1 = 3.1 \times 500 \times 1 = 1550$ ft.-lbs., and $M_2 = 9.6 \times 500 \times 1 = 4800$ ft.-lbs.

151. Coefficients and Working Stresses.—The following is a résumé of the coefficients and working stresses suggested in the discussion of Chapter V. They may be considered as applicable to ordinary conditions on the basis of equivalent dead-load stresses and with concrete of 1:2:4 to 1:2½:5 composition.

Beams.

	Working Stress.	
Concrete in compression.....	500-600	lbs/in ²
Concrete in shear, average stress:		
<i>a.</i> Without shear reinforcement.	30-40	“
<i>b.</i> With shear reinforcement...	50-80	“
Bond stress:		
<i>a.</i> Smooth rods.....	60-75	“
<i>b.</i> Deformed rods.....	100-175	“
Steel in tension.....	12,000-15,000	“
Value of $n = E_s/E_c$	12-15	

Columns.

Concrete in compression.....	300-400
Value of $n = E_s/E_c$	15-20

152. Tables.—*Areas of Steel Rods.*—Table No. 19 gives sectional areas and weights per foot of round and square rods of various sizes, and the total area per foot of width of slab when the rods are spaced various distances apart.


Materials Required for One Cubic Yard of Concrete.—Table No. 20 gives the quantities of material required for one cubic yard of concrete of various proportions. The table is based

on *Thatcher's Tables*.* As conditions vary greatly, these tables should be used only for approximate values.


Safe Loads for Floors.—Table No. 21 gives span lengths for floor-slabs for various live loads per square foot, and for various values of working stresses f_s and f_c . The tables have been calculated for beams supported at the ends, the bending moment being $\frac{1}{8}wl^2$. The value of n has been taken at 15. For continuous slabs $\frac{1}{10}wl^2$ is commonly taken as the bending moment. The permissible span length on this basis will be 12% greater than the tabular values. Where the span length is given, to find necessary thickness of slab based on $\frac{1}{16}wl^2$, take 90% of the given span length and look up this value in the table. The table also gives the amount of steel required per foot of slab, so that by reference to Table No. 18 a suitable size and spacing can readily be determined. The moment of resistance of a beam one foot wide is also given for general use.

*Johnson's *Materials of Construction*, p. 610a.


$n=10$



$$n = 12$$



$n = 15$





$n = 18$ 

PLATE IV.

Full lines for $n=15$; dotted lines for $n=12$.






PLATE VI.—Compressive Reinforcement of Beams.




PLATE VII.—Flexure and Direct Stress.




PLATE VIII.—Flexure and Direct Stress.




PLATE IX.—Working Stresses in Columns.




PLATE X.—Stresses in Circular Slabs.




PLATE XI.—Stresses in Circular Slabs.

TABLE No. 19.
AREAS, WEIGHTS, AND SPACING OF RODS.
ROUND RODS.

Sectional Area of Steel per Foot of Slab when Spaced as follows:																	
Diam-eter, Inches.	Area, Square Inches.	Circum-ference, Inches.	Weight per Foot, Pounds.	2"	2½"	3"	3½"	4"	4½"	5"	5½"	6"	7"	8"	9"	10"	12"
				.29	.23	.20	.17	.15	.13	.12	.11	.10	.08	.07	.07	.06	.05
$\frac{1}{8}$.0491	.7854	.167	.46	.36	.31	.26	.23	.20	.18	.17	.15	.13	.11	.10	.09	.08
$\frac{5}{16}$.0767	.9818	.261	.66	.53	.44	.38	.33	.29	.26	.24	.22	.19	.17	.15	.13	.11
$\frac{3}{8}$.1104	1.1781	.376	.90	.72	.60	.51	.45	.40	.36	.33	.30	.26	.23	.20	.18	.15
$\frac{1}{2}$.1503	1.3745	.511	1.18	.94	.78	.67	.59	.52	.47	.43	.39	.34	.29	.26	.24	.20
$\frac{5}{8}$.1963	1.5708	.668	1.49	1.19	.99	.85	.75	.66	.60	.54	.50	.43	.37	.33	.30	.25
$\frac{3}{4}$.2485	1.7672	.845	1.84	1.47	1.23	1.05	.92	.82	.74	.67	.61	.53	.46	.41	.37	.31
$\frac{7}{8}$.3068	1.9635	1.043	2.23	1.78	1.48	1.27	1.11	.99	.89	.81	.74	.64	.56	.49	.45	.37
1	.3712	2.1599	1.262	2.65	2.12	1.77	1.51	1.32	1.18	1.06	.96	.88	.76	.66	.59	.53	.44
$1\frac{1}{8}$.4418	2.3562	1.502	3.11	2.48	2.07	1.78	1.56	1.38	1.24	1.13	1.04	.89	.78	.69	.62	.52
$1\frac{1}{4}$.5185	2.5526	1.763	3.61	2.88	2.40	2.06	1.80	1.60	1.44	1.31	1.20	1.03	.90	.80	.72	.60
$1\frac{3}{8}$.6013	2.7489	2.044	4.14	3.31	2.76	2.37	2.07	1.84	1.66	1.51	1.38	1.18	1.03	.92	.83	.69
$1\frac{1}{2}$.6903	2.9453	2.347	4.71	3.77	3.14	2.69	2.36	2.09	1.88	1.71	1.57	1.35	1.18	1.05	.94	.78
$1\frac{5}{8}$.7854	3.1416	2.670	5.36	4.77	3.98	3.41	2.98	2.65	2.39	2.17	1.99	1.70	1.49	1.33	1.19	.99
1	.8940	3.3343	3.380	5.96	5.12	4.41	3.81	3.31	2.95	2.68	2.45	2.23	2.01	1.84	1.64	1.47	1.23
$1\frac{1}{4}$	1.2272	3.9270	4.172	7.36	5.89	4.91	4.21	3.68	3.27	2.95	2.68	2.45	2.10	1.84	1.64	1.47	1.23
$1\frac{3}{8}$	1.4849	4.3197	5.049	8.91	7.12	5.94	5.09	4.45	3.96	3.56	3.24	2.97	2.55	2.23	1.98	1.78	1.48
$1\frac{1}{2}$	1.7671	4.7124	6.008	10.60	8.48	7.07	6.06	5.30	4.71	4.24	3.86	3.53	3.03	2.65	2.36	2.12	1.77

TABLE No. 20.

MATERIALS REQUIRED FOR ONE CUBIC YARD OF CONCRETE.

Proportion of Mixture.				Required for One Cubic Yard.		
Cement.	Sand.	Stone.	Ratio: Mortar Stone	Cement, Barrels.	Sand, Cubic Yards.	Stone, Cubic Yards.
1	1	2.0	.70	2.57	0.39	0.78
1	1	2.5	.56	2.29	0.35	0.87
1	1	3.0	.47	2.06	0.31	0.94
1	1.5	2.5	.71	2.05	0.47	0.78
1	1.5	3.0	.60	1.85	0.42	0.84
1	1.5	3.5	.51	1.72	0.39	0.91
1	1.5	4.0	.44	1.57	0.36	0.96
1	2.0	3.0	.72	1.70	0.52	0.77
1	2.0	3.5	.62	1.57	0.48	0.83
1	2.0	4.0	.54	1.46	0.44	0.89
1	2.0	4.5	.48	1.36	0.42	0.93
1	2.5	4.0	.64	1.35	0.52	0.82
1	2.5	4.5	.57	1.27	0.48	0.87
1	2.5	5.0	.51	1.19	0.46	0.91
1	2.5	5.5	.46	1.13	0.43	0.94
1	3	4.5	.66	1.18	0.54	0.81
1	3	5.0	.60	1.11	0.51	0.85
1	3	5.5	.54	1.06	0.48	0.89
1	3	6.0	.50	1.00	0.46	0.92
1	3	6.5	.46	.96	0.44	0.95

TABLE NO. 21.

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{16}wl^2$ multiply given span lengths by 1.12.

1. $f_c = 400$ $R = 59$
 $f_s = 12,000$ $p = .0056$

Total Thickness of Slab, Inches.	Thickness of Con- crete below Steel, Inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resist- ance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.								
					50	75	100	150	200	250	300	400	500
2		.0833	1100	24.2	3.2	2.7	2.4	2.1	1.8	1.6	1.5		
2½		.1167	2200	30.3	4.2	3.7	3.3	2.8	2.5	2.3	2.1	1.8	
3		.150	3600	36.4	5.3	4.6	4.2	3.6	3.2	2.9	2.6	2.3	
3½		.183	5400	42.5	6.2	5.5	5.0	4.3	3.8	3.5	3.2	2.8	
4	1	.200	6400	48.5	6.6	5.9	5.4	4.6	4.1	3.8	3.5	3.1	2.8
4½	1	.233	8700	54.6	7.5	6.7	6.1	5.3	4.8	4.3	4.0	3.5	3.2
5	1	.267	11400	60.6	8.3	7.5	6.8	6.0	5.3	4.9	4.5	4.0	3.6
5½	1	.300	14400	66.7	9.1	8.2	7.6	6.6	6.0	5.5	5.1	4.5	4.1
6	1½	.317	16000	72.7	9.3	8.5	7.8	6.9	6.2	5.7	5.3	4.7	4.3
7	1¾	.383	23500	84.8	10.8	9.9	9.2	8.2	7.4	6.8	6.4	5.7	5.1
8	1¾	.450	32400	97.0	12.1	11.2	10.5	9.3	8.5	7.9	7.4	6.6	6.0
9	1½	.500	40000	109.1	12.9	12.0	11.3	10.1	9.3	8.6	8.0	7.2	6.6
10	1½	.567	51400	121.3	14.1	13.2	12.4	11.2	10.3	9.6	9.0	8.1	7.4
12	1½	.700	78400	145.7	16.4	15.4	14.6	13.3	12.3	11.4	10.8	9.8	9.0

2. $f_c = 400$ $R = 54$
 $f_s = 14,000$ $p = .0043$

2		.064	1000	24.2	3.0	2.6	2.3	2.0	1.7	1.6			
2½		.090	2000	30.3	4.1	3.5	3.2	2.7	2.4	2.2			
3		.116	3300	36.4	5.0	4.4	4.0	3.4	3.0	2.8	2.0	1.7	2.0
3½		.141	4900	42.5	5.9	5.3	4.8	4.1	3.7	3.3	3.1	2.7	2.4
4	1	.154	5800	48.5	6.3	5.6	5.1	4.4	4.0	3.6	3.3	2.9	2.6
4½	1	.180	7900	54.6	7.1	6.4	5.8	5.1	4.5	4.2	3.8	3.4	3.1
5	1	.206	10400	60.6	7.9	7.1	6.5	5.7	5.1	4.7	4.4	3.9	3.5
5½	1	.231	13100	66.6	8.6	7.9	7.2	6.4	5.7	5.2	4.9	4.3	3.9
6	1½	.244	14600	72.6	8.9	8.1	7.5	6.6	6.0	5.5	5.1	4.5	4.1
7	1¾	.296	21400	84.7	10.3	9.5	8.8	7.8	7.1	6.5	6.1	5.4	4.9
8	1¾	.347	29500	96.9	11.6	10.7	10.0	8.9	8.1	7.5	7.0	6.3	5.7
9	1½	.386	36400	109.0	12.4	11.5	10.8	9.7	8.9	8.2	7.7	6.9	6.3
10	1½	.437	46800	121.1	13.5	12.6	11.9	10.7	9.8	9.2	8.6	7.7	7.1
12	1½	.540	71400	145.4	15.6	14.7	13.9	12.7	11.7	11.0	10.3	9.3	8.6

TABLE NO. 21—*Continued.*

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{16}wl^2$ multiply given span lengths by 1.12.

3. $f_c = 400$ $R = 52$
 $f_s = 15,000$ $p = .0038$

Total Thickness of Slab, Inches.	Thickness of Concrete below Steel, Inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resistance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.								
					50	75	100	150	200	250	300	400	500
2		.057	1000	24.1	2.9	2.6	2.3	1.9	1.7	1.5			
2½		.080	1900	30.3	4.0	3.5	3.1	2.6	2.3	2.1	1.9	1.7	1.5
3		.103	3100	36.4	4.9	4.3	3.9	3.3	3.0	2.7	2.5	2.2	2.0
3½		.126	4700	42.5	5.8	5.2	4.7	4.0	3.6	3.3	3.0	2.7	2.4
4	1	.137	5600	48.5	6.1	5.5	5.0	4.3	3.9	3.5	3.3	2.9	2.6
4½	1	.160	7600	54.6	6.9	6.3	5.7	5.0	4.5	4.1	3.8	3.3	3.0
5	1	.183	9900	60.5	7.7	7.0	6.4	5.6	5.0	4.6	4.3	3.8	3.4
5½	1	.206	12600	66.5	8.5	7.7	7.1	6.2	5.6	5.1	4.8	4.2	3.8
6	1½	.217	14000	72.5	8.7	8.0	7.4	6.5	5.8	5.4	5.0	4.4	4.0
7	1½	.263	20500	83.6	10.1	9.3	8.6	7.7	6.9	6.4	6.0	5.3	4.8
8	1½	.309	28300	96.8	11.4	10.5	9.8	8.7	8.0	7.4	6.9	6.2	5.6
9	1½	.343	34900	108.9	12.1	11.3	10.6	9.5	8.7	8.1	7.6	6.8	6.2
10	1½	.389	44800	120.9	13.2	12.4	11.6	10.5	9.7	9.0	8.4	7.6	6.9
12	1½	.480	68400	145.2	15.3	14.4	13.7	12.5	11.5	10.8	10.1	9.2	8.4

4. $f_c = 400$ $R = 50$
 $f_s = 16,000$ $p = .0034$

2	2	.051	900	24.1	2.9	2.5	2.2	1.9	1.6	1.5			
2½	2	.072	1800	30.3	3.9	3.4	3.1	2.6	2.3	2.1	1.9	1.7	1.5
3	2	.092	3000	36.4	4.8	4.2	3.8	3.3	2.9	2.6	2.4	2.1	1.9
3½	2	.112	4500	42.5	5.7	5.0	4.6	3.9	3.5	3.2	2.9	2.6	2.3
4	1	.123	5400	48.5	6.0	5.3	4.9	4.2	3.8	3.4	3.2	2.8	2.5
4½	1	.143	7300	54.6	6.8	6.1	5.6	4.8	4.3	4.0	3.7	3.2	2.9
5	1	.164	9500	60.5	7.5	6.8	6.2	5.4	4.9	4.5	4.2	3.7	3.3
5½	1	.184	12100	66.5	8.2	7.5	6.9	6.0	5.4	5.0	4.6	4.1	3.7
6	1½	.194	13400	72.5	8.5	7.7	7.2	6.3	5.7	5.2	4.9	4.3	3.9
7	1½	.235	19700	83.5	9.8	9.0	8.4	7.4	6.8	6.2	5.8	5.2	4.7
8	1½	.276	27100	96.7	11.0	10.2	9.5	8.5	7.7	7.2	6.7	6.0	5.4
9	1½	.307	33500	108.7	11.8	11.0	10.3	9.2	8.4	7.8	7.3	6.6	6.0
10	1½	.348	43000	120.7	12.9	12.0	11.3	10.2	9.4	8.7	8.2	7.4	6.7
12	1½	.430	65600	145.0	14.9	14.0	13.3	12.1	11.2	10.4	9.8	8.9	8.2

TABLE NO. 21—*Continued.*

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{16}wl^2$ multiply given span lengths by 1.12.

5. $f_c = 400$ $R = 46$
 $f_s = 18,000$ $p = .0028$

Total Thickness of Slab, Inches.	Thickness of Concrete below Steel, Inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resistance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.								
					50	75	100	150	200	250	300	400	500
2		.042	900	24.1	2.8	2.4	2.1	1.8	1.6	1.4	1.3		
2½		.058	1700	30.3	3.7	3.3	2.9	2.5	2.2	2.0	1.8	1.6	1.4
3		.075	2800	36.4	4.6	4.1	3.7	3.2	2.8	2.5	2.3	2.1	1.8
3½		.092	4200	42.5	5.5	4.9	4.4	3.8	3.4	3.1	2.8	2.5	2.3
4	1	.100	5000	48.5	5.8	5.2	4.7	4.1	3.6	3.3	3.1	2.7	2.4
4½	1	.117	6700	54.6	6.6	5.9	5.4	4.7	4.2	3.8	3.6	3.1	2.8
5	1	.133	8800	60.4	7.3	6.6	6.1	5.3	4.7	4.3	4.0	3.6	3.2
5½	1	.150	11100	66.4	8.0	7.3	6.7	5.9	5.3	4.8	4.5	4.0	3.6
6	1½	.158	12400	72.4	8.2	7.5	6.9	6.1	5.5	5.1	4.7	4.2	3.8
7	1½	.192	18200	83.4	9.5	8.8	8.1	7.2	6.5	6.0	5.6	5.0	4.5
8	1½	.225	25100	96.6	10.7	9.9	9.3	8.3	7.5	6.9	6.5	5.8	5.3
9	1½	.250	31000	108.6	11.4	10.6	10.0	8.9	8.2	7.6	7.1	6.4	5.8
10	1½	.283	39800	120.6	12.5	11.6	11.0	9.9	9.1	8.5	7.9	7.1	6.5
12	1½	.350	60700	144.9	14.4	13.6	12.9	11.7	10.8	10.1	9.5	8.6	7.9

6. $f_c = 500$ $R = 84$
 $f_s = 12,000$ $p = .0080$

2		.120	1600	24.3	3.8	3.2	2.9	2.4	2.2	1.9	1.8	1.6	1.4
2½		.168	3100	30.4	5.1	4.4	4.0	3.4	3.0	2.7	2.5	2.2	2.0
3		.216	5100	36.5	6.3	5.5	5.0	4.3	3.8	3.4	3.2	2.8	2.5
3½		.264	7600	42.7	7.4	6.6	6.0	5.1	4.6	4.2	3.8	3.4	3.1
4	1	.312	9100	48.7	7.8	7.0	6.4	5.5	4.9	4.5	4.2	3.7	3.3
4½	1	.337	12300	54.8	8.9	8.0	7.3	6.3	5.7	5.2	4.8	4.3	3.8
5	1	.385	16100	60.9	9.8	8.9	8.2	7.1	6.4	5.9	5.5	4.8	4.4
5½	1	.433	20400	67.0	10.8	9.8	9.0	7.9	7.1	6.5	6.1	5.4	4.9
6	1½	.457	22700	73.1	11.1	10.1	9.4	8.2	7.4	6.8	6.4	5.6	5.1
7	1½	.553	33300	85.3	12.8	11.8	10.9	9.7	8.8	8.1	7.6	6.7	6.1
8	1½	.649	45800	97.6	14.4	13.3	12.4	11.1	10.1	9.4	8.8	7.8	7.1
9	1½	.721	56600	109.7	15.4	14.3	13.4	12.1	11.0	10.2	9.6	8.6	7.9
10	1½	.817	72700	122.0	16.8	15.7	14.8	13.3	12.3	11.4	10.7	9.6	8.8
12	1½	1.010	110900	146.5	19.4	18.3	17.3	15.8	14.6	13.6	12.9	11.6	10.7

TABLE NO. 21—Continued.

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{10}wl^2$ multiply given span lengths by 1.12.

7. $f_c = 500$ $R = 77$
 $f_s = 14,000$ $p = .0062$

Total Thickness of Slab, Inches.	Thickness of Con- crete below Steel, Inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resist- ance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.									
					50	75	100	150	200	250	300	400	500	
2		.094	1400	24.2	3.6	3.1	2.8	2.4	2.1	1.9	1.7	1.5	1.4	
2½		.131	2800	30.3	4.8	4.2	3.8	3.2	2.9	2.6	2.4	2.1	1.9	
3		.168	4700	36.4	6.0	5.3	4.8	4.1	3.6	3.3	3.0	2.7	2.4	
3½		.206	7000	42.5	7.1	6.3	5.7	4.9	4.4	4.0	3.7	3.3	2.9	
4	1	.224	8300	48.5	7.5	6.7	6.1	5.3	4.7	4.3	4.0	3.5	3.2	
4½	1	.262	11300	54.6	8.5	7.6	7.0	6.1	5.5	5.0	4.6	4.1	3.7	
5	1	.299	14800	60.7	9.5	8.5	7.9	6.8	6.2	5.7	5.2	4.6	4.2	
5½	1	.336	18700	66.8	10.4	9.4	8.7	7.6	6.9	6.3	5.9	5.2	4.7	
6	1½	.355	20900	72.9	10.5	9.5	8.8	7.8	7.0	6.5	6.0	5.4	4.8	
7	1½	.430	30600	85.1	12.2	11.1	10.3	9.3	8.3	7.7	7.2	6.5	5.8	
8	1½	.505	42100	97.4	13.7	12.6	11.8	10.6	9.6	9.0	8.3	7.5	6.8	
9	1½	.561	52000	109.5	14.8	13.7	12.9	11.5	10.6	9.8	9.2	8.3	7.6	
10	1½	.636	66800	121.7	16.1	15.0	14.2	12.8	11.8	11.0	10.3	9.3	8.5	
12	1½	.785	102000	145.9	18.9	17.5	16.6	15.1	14.1	13.1	12.4	11.2	10.3	

8. $f_c = 500$ $R = 74$
 $f_s = 15,000$ $p = .0056$

2		.083	1400	24.2	3.5	3.1	2.7	2.3	2.0	1.8	1.7	1.5	1.3
2½		.117	2700	30.3	4.7	4.1	3.7	3.2	2.8	2.5	2.3	2.0	1.8
3		.150	4500	36.4	5.9	5.2	4.7	4.0	3.6	3.2	3.0	2.6	2.4
3½		.183	6700	42.5	7.0	6.2	5.6	4.8	4.3	3.9	3.6	3.2	2.9
4	1	.200	8000	48.5	7.4	6.6	6.0	5.2	4.6	4.2	3.9	3.4	3.1
4½	1	.233	10900	54.6	8.3	7.5	6.9	6.0	5.3	4.9	4.5	4.0	3.6
5	1	.267	14200	60.6	9.2	8.3	7.7	6.7	6.0	5.5	5.1	4.5	4.1
5½	1	.300	18000	66.7	10.1	9.2	8.5	7.4	6.7	6.2	5.7	5.1	4.6
6	1½	.317	20100	72.8	10.4	9.5	8.8	7.7	7.0	6.4	6.0	5.3	4.8
7	1½	.383	29400	84.9	12.0	11.1	10.3	9.1	8.3	7.6	7.1	6.4	5.8
8	1½	.450	40500	97.2	13.5	12.5	11.7	10.5	9.5	8.8	8.2	7.4	6.7
9	1½	.500	50000	109.3	14.5	13.5	12.6	11.3	10.4	9.6	9.0	8.1	7.4
10	1½	.567	64200	121.5	15.8	14.7	13.9	12.6	11.5	10.7	10.1	9.1	8.3
12	1½	.700	98000	145.7	18.2	17.2	16.3	14.8	13.7	12.8	12.1	10.9	10.0

TABLE NO. 21—Continued.

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{16}wl^2$; for $M = \frac{1}{10}wl^2$ multiply given span lengths by 1.12.

9. $f_c = 500$ $R = 71$
 $f_s = 16,000$ $p = .0050$

Total Thickness of Slab, inches.	Thickness of Concrete below Steel, inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resistance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.								
					50	75	100	150	200	250	300	400	500
2	$\frac{3}{4}$.075	1300	24.2	3.5	3.0	2.7	2.3	2.0	1.8	1.7	1.4	1.3
2 $\frac{1}{2}$	$\frac{3}{4}$.105	2600	30.3	4.7	4.1	3.7	3.1	2.8	2.5	2.3	2.0	1.8
3	$\frac{3}{4}$.135	4300	36.4	5.8	5.1	4.6	4.0	3.5	3.2	2.9	2.6	2.3
3 $\frac{1}{2}$	$\frac{3}{4}$.165	6500	42.5	6.8	6.1	5.5	4.8	4.2	3.8	3.6	3.1	2.8
4	1	.180	7700	48.5	7.2	6.4	5.9	5.1	4.5	4.1	3.8	3.4	3.1
4 $\frac{1}{2}$	1	.209	10500	54.7	8.2	7.3	6.7	5.8	5.2	4.8	4.4	3.9	3.5
5	1	.239	13700	60.7	9.1	8.2	7.5	6.6	5.9	5.4	5.0	4.4	4.0
5 $\frac{1}{2}$	1	.269	17300	66.6	10.0	9.1	8.3	7.3	6.6	6.0	5.6	5.0	4.5
6	1 $\frac{1}{4}$.284	19300	72.7	10.3	9.4	8.7	7.6	6.9	6.3	5.9	5.2	4.7
7	1 $\frac{1}{4}$.344	28300	84.8	11.9	10.9	10.1	9.0	8.2	7.5	7.0	6.3	5.7
8	1 $\frac{1}{4}$.404	39000	97.0	13.4	12.3	11.5	10.3	9.4	8.7	8.1	7.3	6.6
9	1 $\frac{1}{2}$.449	48100	109.1	14.3	13.3	12.4	11.2	10.2	9.5	8.9	8.0	7.3
10	1 $\frac{1}{2}$.509	61800	121.3	15.6	14.6	13.7	12.4	11.4	10.6	9.9	8.9	8.2
12	1 $\frac{1}{2}$.629	94400	145.5	17.9	16.9	16.0	14.6	13.5	12.6	11.9	10.7	9.9

10. $f_c = 500$ $R = 66$
 $f_s = 18,000$ $p = .0041$

2	$\frac{3}{4}$.061	1200	24.2	3.3	2.9	2.6	2.2	1.9	1.7	1.6	1.4	1.3
2 $\frac{1}{2}$	$\frac{3}{4}$.086	2400	30.3	4.5	3.9	3.5	3.0	2.6	2.4	2.2	1.9	1.7
3	$\frac{3}{4}$.110	4000	36.4	5.6	4.9	4.4	3.8	3.4	3.0	2.8	2.5	2.2
3 $\frac{1}{2}$	$\frac{3}{4}$.135	6000	42.4	6.6	5.9	5.3	4.6	4.0	3.7	3.4	3.0	2.7
4	1	.147	7200	48.4	7.0	6.2	5.7	4.9	4.4	4.0	3.7	3.3	2.9
4 $\frac{1}{2}$	1	.172	9700	54.5	7.8	7.1	6.5	5.6	5.1	4.6	4.3	3.8	3.4
5	1	.196	12700	60.5	8.8	7.9	7.3	6.4	5.7	5.2	4.8	4.3	3.9
5 $\frac{1}{2}$	1	.221	16100	68.5	9.5	8.7	8.0	7.0	6.1	5.8	5.4	4.8	4.3
6	1 $\frac{1}{4}$.233	18000	72.6	9.8	9.0	8.3	7.3	6.6	6.1	5.7	5.0	4.6
7	1 $\frac{1}{4}$.282	26300	84.7	11.4	10.4	9.7	8.6	7.8	7.2	6.7	6.0	5.5
8	1 $\frac{1}{4}$.331	36300	96.8	12.8	11.8	11.0	9.9	9.0	8.3	7.8	7.0	6.4
9	1 $\frac{1}{2}$.368	44800	108.9	13.6	12.7	11.9	10.7	9.8	9.1	8.5	7.7	7.0
10	1 $\frac{1}{2}$.417	57500	121.1	14.9	13.9	13.1	11.9	10.9	10.1	9.5	8.6	7.9
12	1 $\frac{1}{2}$.515	87700	145.3	17.1	16.2	15.4	14.0	13.0	12.1	11.4	10.4	9.5

TABLE NO. 21—Continued.

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{16}wl^2$ multiply given span lengths by 1.12.

11. $f_c = 600$ $R = 110$
 $f_s = 12,000$ $p = .0107$

Total Thickness of Slab, Inches.	Thickness of Concrete below Steel, Inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resistance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.									
					50	75	100	150	200	250	300	400	500	
2		.161	2100	24.4	4.3	3.7	3.3	2.8	2.5	2.2	2.0	1.8	1.6	
2½		.225	4000	30.5	5.8	5.0	4.5	3.8	3.4	3.1	2.8	2.5	2.2	
3		.289	6700	36.6	7.2	6.3	5.7	4.9	4.3	3.9	3.6	3.2	2.9	
3½		.354	10000	42.9	8.5	7.5	6.8	5.8	5.2	4.7	4.4	3.8	3.5	
4	1	.386	11900	48.9	8.9	8.0	7.3	6.3	5.6	5.1	4.7	4.2	3.8	
4½	1	.450	16200	55.0	10.1	9.1	8.3	7.2	6.5	5.9	5.5	4.8	4.4	
5	1	.514	21200	61.2	11.2	10.1	9.3	8.2	7.3	6.7	6.2	5.5	5.0	
5½	1	.579	26800	67.4	12.3	11.1	10.3	9.0	8.1	7.5	6.9	6.1	5.6	
6	1½	.611	29800	73.5	12.7	11.5	10.7	9.4	8.5	7.8	7.3	6.4	5.8	
7	1½	.739	43700	85.8	14.6	13.4	12.5	11.1	10.1	9.3	8.7	7.7	7.0	
8	1½	.868	60300	98.2	16.4	15.2	14.2	12.7	11.6	10.7	10.0	8.9	8.2	
9	1½	.964	74400	110.3	17.5	16.3	15.3	13.8	12.6	11.7	10.9	9.8	9.0	
10	1½	1.093	95500	122.6	19.2	17.9	16.9	15.2	14.0	13.0	12.2	11.0	10.1	
12	1½	1.350	145800	147.2	22.2	20.9	19.8	18.0	16.7	15.6	14.7	13.3	12.2	

12. $f_c = 600$ $R = 102$
 $f_s = 14,000$ $p = .0084$

2		.126	1900	24.3	4.1	3.6	3.2	2.7	2.4	2.2	2.0	1.7	1.6
2½		.176	3800	30.4	5.6	4.9	4.4	3.7	3.3	3.0	2.7	2.4	2.2
3		.226	6200	36.5	6.9	6.1	5.5	4.7	4.2	3.8	3.5	3.1	2.8
3½		.277	9300	42.7	8.2	7.2	6.6	5.7	5.0	4.6	4.2	3.7	3.4
4	1	.302	11000	48.7	8.6	7.7	7.0	6.1	5.4	5.0	4.6	4.0	3.7
4½	1	.352	15000	54.8	9.8	8.8	8.0	7.0	6.3	5.7	5.3	4.7	4.3
5	1	.403	19600	60.9	10.8	9.8	9.0	7.9	7.1	6.5	6.0	5.3	4.8
5½	1	.453	24800	67.0	11.9	10.8	10.0	8.7	7.9	7.2	6.7	6.0	5.4
6	1½	.478	27700	73.1	12.2	11.2	10.3	9.1	8.2	7.5	7.0	6.2	5.7
7	1½	.579	40600	85.4	14.1	13.0	12.1	10.7	9.7	9.0	8.4	7.5	6.8
8	1½	.680	55900	97.8	15.9	14.7	13.7	12.2	11.2	10.3	9.7	8.6	7.9
9	1½	.755	69000	109.8	16.9	15.7	14.8	13.3	12.2	11.3	10.6	9.5	8.7
10	1½	.856	88600	122.0	18.5	17.3	16.3	14.7	13.5	12.6	11.8	10.6	9.7
12	1½	1.057	135300	146.4	21.4	20.1	19.1	17.4	16.1	15.0	14.2	12.8	11.8

TABLE No. 21—*Continued.*

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{10}wl^2$ multiply given span lengths by 1.12.

13. $f_c = 600$ $R = 98$
 $f_s = 15,000$ $p = .0075$

Total Thickness of Slab, inches.	Thickness of Concrete, below Steel, inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resistance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds								
					50	75	100	150	200	250	300	400	500
2	$\frac{3}{4}$.112	1800	24.2	4.1	3.5	3.2	2.7	2.3	2.1	1.9	1.7	1.5
2½	$\frac{3}{4}$.157	3600	30.4	5.5	4.8	4.3	3.7	3.2	2.9	2.7	2.4	2.1
3	$\frac{3}{4}$.202	6000	36.5	6.8	6.0	5.4	4.6	4.1	3.7	3.4	3.0	2.7
3½	$\frac{3}{4}$.247	8900	42.7	8.0	7.1	6.5	5.6	5.0	4.5	4.2	3.7	3.3
4	1	.270	10600	48.7	8.5	7.6	6.9	6.0	5.3	4.9	4.5	4.0	3.6
4½	1	.315	14500	54.8	9.6	8.6	7.9	6.9	6.2	5.6	5.2	4.6	4.2
5	1	.360	18900	60.9	10.7	9.6	8.8	7.7	7.0	6.4	5.9	5.2	4.7
5½	1	.405	23900	67.0	11.7	10.6	9.8	8.6	7.7	7.1	6.6	5.8	5.3
6	1½	.427	26700	73.1	12.0	11.0	10.1	8.9	8.1	7.4	6.9	6.1	5.6
7	1½	.517	39100	85.5	13.9	12.8	11.9	10.5	9.6	8.8	8.2	7.3	6.7
8	1½	.607	53800	97.9	15.6	14.4	13.5	12.1	11.0	10.2	9.5	8.5	7.8
9	1½	.675	66400	109.6	16.7	15.5	14.6	13.1	12.0	11.1	10.4	9.4	8.5
10	1½	.765	85300	121.8	18.2	17.0	16.0	14.5	13.3	12.4	11.6	10.4	9.6
12	1½	.945	130200	146.2	21.1	19.8	18.8	17.1	15.8	14.8	14.0	12.6	11.6

14. $f_c = 600$ $R = 95$
 $f_s = 16,000$ $p = .0068$

2	$\frac{3}{4}$.101	1800	24.2	4.0	3.5	3.1	2.6	2.3	2.1	1.9	1.7	1.5
2½	$\frac{3}{4}$.142	3500	30.3	5.4	4.7	4.2	3.6	3.2	2.9	2.7	2.3	2.1
3	$\frac{3}{4}$.182	5800	36.4	6.7	5.9	5.3	4.5	4.0	3.7	3.4	3.0	2.7
3½	$\frac{3}{4}$.223	8600	42.6	7.9	7.0	6.3	5.5	4.9	4.4	4.1	3.6	3.3
4	1	.243	10300	48.6	8.3	7.4	6.8	5.9	5.2	4.8	4.4	3.9	3.5
4½	1	.284	14000	54.7	9.4	8.5	7.8	6.7	6.0	5.5	5.1	4.5	4.1
5	1	.324	18300	60.8	10.5	9.5	8.7	7.6	6.8	6.3	5.8	5.1	4.7
5½	1	.355	23100	66.9	11.5	10.4	9.6	8.4	7.6	7.0	6.5	5.7	5.2
6	1½	.385	25700	73.0	11.8	10.7	9.9	8.7	7.9	7.3	6.8	6.0	5.5
7	1½	.466	37700	85.2	13.6	12.5	11.6	10.3	9.4	8.7	8.1	7.2	6.5
8	1½	.547	52000	97.7	15.3	14.2	13.2	11.8	10.8	10.0	9.4	8.3	7.6
9	1½	.608	64200	109.4	16.4	15.2	14.3	12.8	11.8	10.9	10.2	9.2	8.4
10	1½	.689	82400	121.6	17.9	16.7	15.7	14.2	13.1	12.2	11.4	10.2	9.4
12	1½	.851	125800	146.2	20.6	19.4	18.4	16.8	15.5	14.5	13.7	12.4	11.4

TABLE NO. 21—Continued.

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{10}wl^2$ multiply given span lengths by 1.12.

15. $f_c = 600$ $R = 89$
 $f_s = 18,000$ $p = .0056$

Total Thickness of Slab, Inches.	Thickness of Con- crete below Steel, Inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resist- ance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.								
					50	75	100	150	200	250	300	400	500
2		.083	1700	24.1	3.9	3.3	3.0	2.5	2.2	2.0	1.8	1.6	1.4
2½		.117	3300	30.3	5.2	4.5	4.1	3.5	3.1	2.8	2.6	2.2	2.0
3		.150	5400	36.4	6.5	5.7	5.1	4.4	3.9	3.5	3.3	2.9	2.6
3½		.183	8100	42.6	7.6	6.8	6.1	5.3	4.7	4.3	4.0	3.5	3.1
4	1	.200	9600	48.6	8.1	7.2	6.6	5.7	5.1	4.6	4.3	3.8	3.4
4½	1	.233	13100	54.7	9.1	8.2	7.5	6.5	5.8	5.3	4.9	4.4	4.0
5	1	.267	17100	60.7	10.1	9.2	8.4	7.4	6.6	6.1	5.6	5.0	4.5
5½	1	.300	21600	66.8	11.1	10.1	9.3	8.2	7.4	6.7	6.3	5.6	5.0
6	1½	.317	24100	72.8	11.4	10.4	9.6	8.5	7.7	7.1	6.6	5.8	5.3
7	1½	.383	35300	85.2	13.2	12.1	11.3	10.0	9.1	8.4	7.8	7.0	6.3
8	1½	.450	48600	97.5	14.8	13.7	12.8	11.4	10.4	9.6	9.0	8.1	7.4
9	1½	.500	60000	109.2	15.9	14.7	13.8	12.4	11.4	10.6	9.9	8.9	8.1
10	1½	.567	77100	121.3	17.3	16.2	15.2	13.8	12.6	11.8	11.0	9.9	9.1
12	1½	.700	117600	145.7	20.0	18.8	17.8	16.3	15.1	14.1	13.3	12.0	11.0

16. $f_c = 700$ $R = 138$
 $f_s = 12,000$ $p = .0136$

2	¾	.204	2600	24.5	4.8	4.2	3.2	3.1	2.8	2.5	2.3	2.0	1.8
2½	¾	.286	5100	30.7	6.5	5.8	5.1	4.3	3.8	3.5	3.2	2.8	2.5
3	¾	.368	8400	36.9	8.0	7.0	6.4	5.5	4.8	4.4	4.1	3.6	3.2
3½	¾	.449	12500	43.2	9.4	8.4	7.6	6.6	5.8	5.3	4.9	4.3	3.9
4	1	.490	14900	49.2	10.0	8.9	8.1	7.0	6.3	5.7	5.3	4.7	4.2
4½	1	.572	20300	55.3	11.3	10.2	9.3	8.1	7.3	6.6	6.2	5.4	4.9
5	1	.654	26500	61.5	12.5	11.3	10.4	9.1	8.2	7.5	7.0	6.2	5.6
5½	1	.735	33500	67.8	13.8	12.5	11.5	10.1	9.1	8.4	7.8	6.9	6.3
6	1½	.776	37400	73.9	14.1	12.9	11.9	10.5	9.5	8.8	8.2	7.2	6.6
7	1½	.939	54700	86.2	16.3	15.0	14.0	12.4	11.3	10.4	9.7	8.7	7.9
8	1½	1.103	75400	98.7	18.3	17.0	15.9	14.2	12.9	12.0	11.2	10.0	9.1
9	1½	1.225	93100	110.9	19.6	18.2	17.1	15.4	14.1	13.1	12.3	11.0	10.1
10	1½	1.389	119600	123.3	21.4	20.0	18.9	17.1	15.7	14.6	13.7	12.3	11.3
12	1½	1.716	182500	148.1	24.7	23.2	22.1	20.1	18.7	17.5	16.3	14.8	13.7

TABLE NO. 21.—Continued.

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{16}wl^2$ multiply given span lengths by 1.12.

17. $f_c = 700$ $R = 1.9$
 $f_s = 14,000$ $p = .0107$

Total Thickness of Slab, Inches.	Thickness of Concrete below Steel, Inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resistance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.								
					50	75	100	150	200	250	300	400	500
2		.161	2400	24.4	4.7	4.0	3.6	3.0	2.7	2.4	2.2	1.9	1.7
2½		.225	4700	30.6	6.3	5.5	4.9	4.2	3.7	3.4	3.1	2.7	2.4
3		.289	7800	36.7	7.8	6.8	6.2	5.3	4.7	4.3	3.9	3.5	3.1
3½		.354	11700	43.0	9.2	8.1	7.4	6.4	5.7	5.2	4.8	4.2	3.8
4	1	.386	13900	48.9	9.7	8.6	7.9	6.8	6.1	5.6	5.1	4.5	4.1
4½	1	.450	18900	55.0	11.0	9.8	9.0	7.8	7.0	6.4	5.9	5.3	4.8
5	1	.514	24700	61.1	12.2	11.0	10.1	8.8	7.9	7.3	6.7	6.0	5.4
5½	1	.579	31200	67.4	13.3	12.1	11.2	9.8	8.8	8.1	7.5	6.7	6.0
6	1½	.611	34800	73.5	13.7	12.5	11.5	10.2	9.2	8.5	7.9	7.0	6.4
7	1¾	.739	51000	85.7	15.8	14.6	13.5	12.0	10.9	10.1	9.4	8.4	7.6
8	1¾	.868	70300	98.1	17.8	16.5	15.4	13.7	12.5	11.6	10.9	9.7	8.9
9	1½	.964	86800	110.3	19.0	17.7	16.6	14.9	13.7	12.7	11.9	10.6	9.7
10	1½	1.093	111500	122.6	20.8	19.4	18.3	16.5	15.2	14.1	13.3	11.9	10.9
12	1½	1.350	170100	147.3	24.0	22.6	21.5	19.6	18.1	16.9	15.9	14.4	13.2

18. $f_c = 700$ $R = 124$
 $f_s = 15,000$ $p = .0096$

2		.144	2300	24.4	4.6	4.0	3.5	3.0	2.6	2.4	2.2	1.9	1.7
2½		.202	4600	30.6	6.1	5.4	4.8	4.1	3.6	3.3	3.0	2.7	2.4
3		.259	7600	36.7	7.6	6.7	6.1	5.2	4.6	4.2	3.9	3.4	3.1
3½		.317	11300	42.9	9.0	8.0	7.3	6.3	5.6	5.1	4.7	4.1	3.7
4	1	.346	13400	48.8	9.5	8.5	7.8	6.7	6.0	5.6	5.1	4.5	4.0
4½	1	.404	18300	55.0	10.8	9.7	8.9	7.7	6.9	6.3	5.9	5.2	4.7
5	1	.461	23900	61.1	12.0	10.8	9.9	8.7	7.8	7.1	6.6	5.9	5.3
5½	1	.519	30200	67.3	13.1	11.9	11.0	9.6	8.7	8.0	7.4	6.6	6.0
6	1½	.548	33700	73.3	13.5	12.3	11.4	10.0	9.1	8.3	7.7	6.9	6.3
7	1½	.663	49300	85.5	15.0	14.3	13.4	11.8	10.7	9.9	9.2	8.2	7.5
8	1¾	.778	68000	97.9	17.5	16.2	15.1	13.5	12.3	11.4	10.7	9.5	8.7
9	1½	.865	83900	110.1	18.7	17.4	16.3	14.7	13.4	12.5	11.7	10.5	9.6
10	1½	.980	107800	122.3	20.4	19.1	18.0	16.2	14.9	13.9	13.0	11.7	10.7
12	1½	1.210	164500	146.9	23.6	22.2	21.1	19.2	17.8	16.6	15.7	14.2	13.0

TABLE NO. 21—Continued.

STRENGTH OF FLOOR-SLABS.

Calculated for $M = \frac{1}{8}wl^2$; for $M = \frac{1}{10}wl^2$ multiply given span lengths by 1.12.

19. $f_c = 700$ $R = 120$
 $f_s = 16,000$ $p = .0087$

Total Thickness of Slab, Inches.	Thickness of Concrete below Steel, Inches.	Required Area of Steel per Foot of Slab, Sq. In.	Moment of Resistance per Foot of Slab, In.-lbs.	Weight of Slab per Square Foot, Lbs.	Span in Feet for Given Net Loads per Square Foot of Floor in Pounds.								
					50	75	100	150	200	250	300	400	500
2	$\frac{3}{4}$.130	2300	24.3	4.5	3.9	3.5	2.9	2.6	2.3	2.1	1.9	1.7
2½	$\frac{3}{4}$.182	4400	30.5	6.1	5.3	4.8	4.0	3.6	3.2	3.0	2.6	2.4
3	$\frac{3}{4}$.234	7300	36.6	7.5	6.6	6.0	5.1	4.5	4.1	3.8	3.3	3.0
3½	$\frac{3}{4}$.286	10900	42.9	8.9	7.9	7.2	6.2	5.5	5.0	4.6	4.0	3.7
4	1	.312	13000	48.8	8.4	8.4	7.6	6.6	5.9	5.4	5.0	4.4	4.0
4½	1	.364	17700	54.9	10.6	9.5	8.7	7.6	6.8	6.2	5.8	5.1	4.6
5	1	.416	23100	61.0	11.8	10.6	9.8	8.5	7.7	7.0	6.5	5.8	5.2
5½	1	.468	29200	67.2	12.9	11.7	10.8	9.5	8.5	7.8	7.3	6.5	5.9
6	1½	.494	32600	73.2	13.3	12.1	11.2	9.9	8.9	8.2	7.6	6.8	6.2
7	1½	.598	47700	85.4	15.4	14.1	13.1	11.6	10.6	9.8	9.1	8.1	7.4
8	1½	.702	65800	97.7	17.3	15.9	14.9	13.3	12.1	11.2	10.5	9.4	8.6
9	1½	.780	81200	109.9	18.4	17.1	16.1	14.4	13.2	12.3	11.5	10.3	9.4
10	1½	.884	104300	122.1	20.1	18.8	17.7	16.0	14.7	13.7	12.9	11.6	10.6
12	1½	1.092	159200	146.6	23.2	21.9	20.8	18.9	17.5	16.4	15.4	14.0	12.8

20. $f_c = 700$ $R = 113$
 $f_s = 18,000$ $p = .0072$

2	$\frac{3}{4}$.107	2100	24.3	4.4	3.8	3.4	2.8	2.5	2.3	2.1	1.8	1.6
2½	$\frac{3}{4}$.150	4200	30.4	5.9	5.1	4.6	3.9	3.5	3.1	2.9	2.5	2.3
3	$\frac{3}{4}$.193	6900	36.4	7.3	6.4	5.8	5.0	4.4	4.0	3.7	3.2	2.9
3½	$\frac{3}{4}$.236	10300	42.7	8.6	7.6	6.9	6.0	5.3	4.8	4.5	3.9	3.5
4	1	.258	12200	48.6	9.1	8.1	7.4	6.4	5.7	5.2	4.8	4.3	3.8
4½	1	.301	16600	54.7	10.3	9.3	8.5	7.4	6.6	6.1	5.6	4.9	4.5
5	1	.344	21700	60.8	11.4	10.3	9.5	8.3	7.5	6.8	6.3	5.6	5.1
5½	1	.387	27500	67.0	12.5	11.3	10.5	9.2	8.3	7.6	7.1	6.3	5.7
6	1½	.408	30600	72.9	12.8	11.7	10.9	9.6	8.6	7.9	7.4	6.6	6.0
7	1½	.494	44800	85.4	14.8	13.6	12.7	11.3	10.2	9.4	8.8	7.8	7.1
8	1½	.580	61800	97.9	16.7	15.4	14.5	12.9	11.7	10.9	10.2	9.1	8.3
9	1½	.644	76300	109.6	17.9	16.6	15.6	14.0	12.8	11.9	11.1	10.0	9.1
10	1½	.730	98000	121.8	19.5	18.2	17.2	15.5	14.3	13.3	12.5	11.2	10.3
12	1½	.902	149500	146.3	22.6	21.2	20.1	18.4	17.0	15.9	15.0	13.5	12.4

CHAPTER VII.

BUILDING CONSTRUCTION.

153. Division of the Subject.—The various elements of building construction relating to reinforced-concrete design may be grouped under the following heads: (1) Beams forming a continuous surface, as floor- and roof-slabs; (2) Floor-beams and girders; (3) Columns; (4) Footings; (5) Walls and partitions. In the discussion of these various elements consideration will be given to the determination of stresses, the design of the members, and the arrangement of connective details.

154. General Arrangement of Concrete Floors.—Two general types of floors may be considered: (1) that in which the floor-slab is supported on steel beams, and (2) that in which concrete beams are used, the floor of the entire structure being of a monolithic character. In the former case the steel skeleton consists of columns, girders, and cross-beams, the beams being spaced commonly about 6 feet apart. The floor-slab is supported mainly by the cross-beams. The same variety of arrangements is used in the case of all-concrete structures, the cross-beams being spaced usually from four to six feet apart. The cross-beams may in this case be entirely omitted, giving span lengths of 15 to 20 feet. Sometimes, also, the cross-beams are inserted only at columns, forming a nearly square panel of the floor-slab, which is then considered as supported on four sides.

155. Stresses in Continuous Beams.—Since floor-slabs and beams are commonly designed to act as continuous beams

it is important to investigate the possible stresses under such conditions, although exact calculation is impracticable and unnecessary. In the case of floor-slabs there is usually a large number of consecutive spans and the loading producing the theoretical maximum moments at various points would involve unreasonable assumptions as to position of live loads. Sufficiently exact analysis may be arrived at by considering certain simple cases. Take, for example, the two cases of a beam of two equal spans and one of three equal spans, in each case the beam being "supported" at the ends. Assume both a fixed, or dead-load, and a moving, or live-load, and that the latter consists of a uniform load distributed over such portion of the floor as to cause the maximum moment at each section. This maximum moment is readily calculated by means of the usual continuous girder formulas. The calculation will not be repeated here. The results are shown graphically to scale in Figs. 71 and 72. The dotted lines relate to dead-load effects and the dashed lines to live-load effects. The span length and the load per foot are assumed equal to unity. If, in any given case, w = dead load per foot, p = live load per foot, and l = span length, the true moments will be found by multiplying the proper ordinates by wl^2 or by pl^2 respectively.

In Fig. 71 the maximum positive moment = $.070wl^2 + .095pl^2$, and the maximum negative moment = $\frac{1}{8}wl^2 + \frac{1}{8}pl^2$.

In Fig. 72 the maximum positive moments are:

$$\text{First span, } M = .080wl^2 + .100pl^2.$$

$$\text{Second span, } M = .025wl^2 + .075pl^2.$$

The maximum negative moments at supports are each

$$M = .100wl^2 + .117pl^2.$$

Assuming, for example, that the dead load is one-half the live load, then there results for the first case

$$\text{Maximum positive moment} = .087(w + p)l^2,$$

$$\text{Maximum negative moment} = \frac{1}{8}(w + p)l^2,$$

and for the second case

$$\text{Maximum positive moment} = .093(w + p)l^2,$$

$$\text{Maximum negative moment} = .111(w + p)l^2.$$




FIG. 71.—Moments in Beams of Two Spans.




FIG. 72.—Moments in Beams of Three Spans.

In Figs. 71 and 72 the full lines represent the maximum moments throughout the beam for the condition that $w = \frac{1}{2}p$;

these lines are particularly useful in showing the relative distances from the supports over which positive and negative moments may occur.

Similar calculations might be made for a greater number of spans, but the results for the second case may be taken as approximately what would be found for a larger number. We may conclude, therefore, that for three or more spans the maximum moment is approximately $\frac{1}{16} (w+p)^2$. This is in accordance with a common rule of practice. The maximum shears near supports are not greatly affected by moving loads. For intermediate spans the maximum end shear may be taken at one-half of the span load; for end spans the shear near the second support will be approximately six-tenths of a span load.

These suggested values of moments should be modified where the relation of live to dead load is greatly different from that here assumed. Where, for example, the load is all fixed load, the center moments would be much smaller, and in the case of three or more spans the moments over the supports would be somewhat smaller than here estimated.

156. Effect of Rigid Supports on the Resisting Moment.

If a flat slab is held between unyielding supports, such as fixed I-beams, a strength, or resisting moment, will be developed in the slab even though there be no steel reinforcement. Failure cannot take place without the crushing of the concrete either at the center or at the support. For short spans this resisting moment (the so-called "arch action") is about as great as will exist in the slab if reinforced and simply supported at the ends. In the case of a flat reinforced slab such rigid supports likewise add considerably to the strength of the slab, giving the effect of partial continuity. This strengthening effect of rigid supports is roughly proportional to the square of the slab thickness and inversely proportional to the square of its length.

In practice, the supports of slabs of short span length, whether consisting of I-beams or of concrete beams of which

the slab is a part, are rendered very rigid by reason of the action of the adjoining floor-panels. Even where the slabs are simply supported on the tops of steel beams the adjoining slabs prevent to some extent lateral motion, rendering all such spans partially continuous. The strengthening effect of rigid supports is, therefore, especially great in the case of narrow floor-spans and where there is a large number of consecutive unbroken panels. Under such conditions reinforcement against negative moment is hardly necessary. For long spans and for spans on the outside of a system the effect is small.

157. Slabs Reinforced in Two Directions.—If the panel between beams is square, or nearly so, the slab may advantageously be reinforced in both directions. The exact analysis of stresses in such a case is difficult, if not impossible, as the effect of the more or less rigid supports is especially important and the problem is otherwise difficult of exact treatment.

The following solution for square and rectangular slabs will serve to show, approximately, the relation of the loads carried by the two systems of reinforcement. The results are certainly safe and do not vary much from rules of practice, but point to a somewhat more economical use of material.

158. Square Slabs.—In this case the reinforcement should be of equal amount in the two directions. It may be calculated on the assumption that one half the load is carried by each system of reinforcement. The concrete is proportioned for only one system, or one-half the load, as the stresses due to the two systems are at right angles to each other and it is assumed that the stresses in one direction do not weaken the concrete with respect to stresses in the other direction. The loading on each system is usually assumed to be uniformly distributed, resulting in an equal spacing of rods throughout the beam. This assumption is, however, far from the truth, and while giving safe results it is desirable to consider a more exact analysis of the problem which will show that the rods should be spaced closer at the center than at the edge.

In Fig 73, *ABCD* represents a square slab supported on

all sides and loaded with a uniform load w per unit area. Consider the relative amounts of load carried by the system parallel to aa' and the system parallel to mm' . At the centre O , and at all points on the diagonal lines AD and CB , it follows from symmetry that the loading is equally distributed on the two systems and is equal to $w/2$. At point E the proportion of the load carried by the system aa' will be much greater than that carried by the system mm' , since for given loads the beam element along aa' will deflect much less at point E than will the element along mm' . In general, therefore, as we approach the support BD the proportion of load carried by the system aa' increases, reaching a value of w at




FIG. 73.




FIG. 74.

the extreme end a' . The distribution of load on aa' may then be roughly represented by the ordinates from AB to the curved line aOa' of Fig. 74. Consider now the load along a line bb' . At points F and F' the load will be $w/2$; at point G' it will be less than $w/2$, being the same as the load on the system mm' at G . It will be shown in Fig. 74 by the ordinate GH from Oa' to the line aa' . At the end b' the load will be w . The curve of distribution will then be somewhat as represented by the line $aG'a'$ in Fig. 74, in which $G'K = GH$.

Assuming the curve aOa' to be a parabola it is found that the centre bending moment along the line aa' , for a beam one foot wide, will be $\frac{7}{48} (w/2)l^2$ instead of $\frac{9}{48} (w/2)l^2$, as results

from the usual assumption. The spacing of the rods at the centre may then be determined on this basis. At points intermediate between the centre and the edge, the rods might well be spaced so that the number per foot would vary from the required number at the centre to zero at the edge, following the law of the parabola. If N represents the total number required on the ordinary assumption of equal spacing, then $\frac{7}{6}N \times \frac{2}{3}$, or $\frac{7}{9}N$, would represent the more correct number when spaced as here calculated. Practically as good results will be secured if the rods are spaced uniformly at the usual spacing, determined by the formula $M = \frac{1}{8}(w/2)l^2$, for the centre half of the slab, then gradually reduce the number per foot to the edge of the slab, using one-half as many rods for the remaining two quarters. The total number used would then be $\frac{3}{2}N$ instead of $\frac{7}{9}N$ as above determined, but the strength would be ample. If the slabs are continuous, then $\frac{1}{16}$ or $\frac{1}{12}$ should be substituted for $\frac{1}{8}$ in the formula for M , as may be permissible.

159. Rectangular Slabs of Greater Length than Breadth.—

As a slab becomes oblong in form the relative amount of load carried by the longitudinal system becomes rapidly less. Consider the case of a slab twice as long as wide (Fig. 75). For equal fibre stresses the longitudinal system aa' will deflect four times as much as the transverse system mm' . Hence




FIG. 75.

the same deflection involves only one fourth the unit stress on the bars aa' as on the bars mm' . If equal spacing be used, then the load carried by the longitudinal system will be that which produces one-fourth the fibre stress as in the system mm' . Finally, since the stress for given loads is proportional to the span, we find that only one-eighth as much load will be carried by the longitudinal system as by the transverse system with equal spacing of rods. For points nearer the ends of the slab the proportion carried by the longitudinal system will be greater, but in any

case the longitudinal rods will be much under-stressed. If the length is 1.25 times the breadth, then the working stress in the longitudinal rods will be about two-thirds that in the cross-rods (at the centre) and they will carry about one-half as much load when spaced the same.

From this discussion it is evident that longitudinal reinforcement should not be used to carry load in oblong panels where the length exceeds the breadth by more than 15 to 20 %. An excess of 25% would seem to be about the practical limit. Whatever steel is placed in the longitudinal direction is used uneconomically.

160. Reinforcement to Prevent Cracks.—While longitudinal reinforcement is of little value in carrying loads, a small amount is nevertheless often desirable in preventing cracks and in binding the entire structure together. For a close beam spacing such reinforcement is hardly necessary, as the beam reinforcement itself thoroughly ties the structure longitudinally along the beam lines. For wide beam spacing it is more important. Just what amount of steel is needed is a matter of experience. The use of $\frac{1}{4}$ -inch or $\frac{3}{8}$ -inch rods spaced about two feet apart is common practice. If a metal fabric is used for oblong panels, the longitudinal metal should be proportioned in accordance with the principles discussed in this and the preceding articles.

161. Floor-slabs Supported on Steel Beams.—Many "systems" have been developed of this type of construction, differing from each other in form of steel used, position of the concrete relative to the beam, use of curved or flat slabs, use of various kinds of hollow tile in connection with the concrete, etc. Sufficient examples only will be given to illustrate the principles involved; further information regarding the many systems can readily be had from trade catalogues.

Fig. 76 shows the floor placed directly on the tops of the beams. The reinforcement may be small rods or a mesh-work of expanded metal or woven fabric. If reinforced as shown, the slab must be calculated as a simple beam, there

being no reinforcement against negative moment over the support. For spans of considerable length some reinforcement for negative moments is desirable to secure economy and to



FIG. 76.

prevent cracks in the upper surface, although the lateral rigidity due to adjoining panels is of much assistance, as explained in Art. 156.

Fig. 77 represents a slab constructed after Hennebique's



FIG. 77.

system, to be supported by walls or steel beams. Small rods are used for reinforcement, every alternate rod being bent up and stirrups of flat steel looped on the straight rods. This is a very effective design to secure strength against shear or diagonal tensile stresses, but except where the floor-load is very heavy special shear reinforcement is hardly needed in floor-slabs. Fig. 78 shows a more common design of non-




FIG. 78.

continuous slab, the concrete being supported on the lower flange and the entire beam surrounded.

Fig. 79 shows a standard form of construction in which




FIG. 79.

the slab is practically continuous. The reinforcing material may be rods or a metal fabric continuous over several spans.

Figs. 80 and 81 show two forms in which a bar is hooked around the beam flange.




FIG. 80.




FIG. 81.

Many other forms are employed, some using a concrete arch with more or less reinforcement. In some, also, the concrete slab is brought down somewhat below the beam, giving a plane surface on the under side.

162. Floor-slabs in All-concrete Construction.—Where concrete beams are used the slab and beam are usually built simultaneously, giving a monolithic structure. The slab thus constitutes part of the beam, but to be effective these two parts must be well tied together. Where cross-beams are used the span of the slab will commonly range from 4 to 6 feet in length. For such short spans a reinforcement of rods or metal meshwork near the bottom only will be effective as explained in Art. 156. This reinforcement, if of rods, should be laid with lapped and broken joints to give continuity and to prevent the localization of contraction cracks in undesirable places (Fig. 82). The




FIG. 82.

beam, if well bonded to the slab, will make a very rigid support comparable to the I-beam.

In the case of spans longer than 5 to 6 feet it becomes desirable to reinforce against negative moment. This may readily be done by bending up a part or all of the rods and extending

the bent ends beyond the beam. Fig. 83 illustrates two arrangements of this kind. In either case the amount of steel at the




FIG. 83.

top above the beam is the same as at the bottom in the centre of the slab. The result may also be arrived at by using separate straight rods, as shown in Fig. 84. The plan of bent




FIG. 84.

rods has a slight advantage as it reinforces somewhat against shearing failures, but this is not usually important in slabs. For very heavy loads, however, it becomes of importance, and the same care should be used as in the design of large beams.

Fig. 85 shows the Hennebique bent-rod and stirrup system applied to long-span slabs.




FIG. 85

The length of span over which negative moment is likely to exist may be estimated from Fig. 72. It is seen that in the centre span of a three-span girder, where the dead load is one-half the live load, negative moment may, under extreme conditions, occur entirely across the beam. For long spans a top reinforcement at least to the third point will be desirable,

but for short spans a less extensive reinforcement will be sufficient. The effect of a less amount of steel is discussed in Art. 165. Other examples of slab construction are shown in Art. 168.

163. Beams and Girders.—*Economical Arrangement.*—The arrangement of columns, girders, and beams is determined according to the same principles as in steel construction. The spacing of columns and girders will be determined largely by architectural considerations. The best spacing of cross-beams will differ in different cases. Where the spacing of girders is not too great (12 to 15 feet) and where cross-beams are not needed to secure lateral stiffness, it will be a question of omitting all cross-beams, of inserting them only at columns so as to form a square or nearly square panel, or of spacing them at closer intervals of 4 to 8 feet, using two or more to a girder-panel. The preceding analysis shows that double reinforcement will not be economical for oblong panels. Cross-beams, if used, should therefore be arranged to give very nearly square panels or else be spaced much more closely, designing the reinforcement so as to carry the entire load to the beams and thence to the girders.

If not otherwise needed, the use of cross-beams to secure square panels effects little if any saving. The amount of concrete will be less, but the amount of steel required will be more, and the extra beam will be more costly per unit volume than the slab. However, for the sake of lateral stiffness it will usually be desirable to place cross-beams at columns.

Where close spacing of beams is adopted the best arrangement depends upon the loading and the working stresses, as well as upon the cost of the material and forms. Heavy loads and low stresses call for large weights of concrete and tend to require the use of the material more in the form of deep ribs or beams, as the deeper the beam the greater its moment of resistance for a given volume. If cross-beams are used, a spacing greater than 10 or 12 feet or less than 4 or 5 feet will seldom be economical. Architectural considerations will often

govern, and frequently building regulations relative to ratio of span to depth will control.

164. Distribution of Floor-loads to Beams.—Where the floor-slab is reinforced in one direction only the load will practically all be transmitted to the corresponding beams, but at the ends of the panels a small part will be transferred directly to the girder. This may be neglected in the calculations. In the case of reinforcement in two directions, unless the panel is nearly square, the load may still be assumed as all transferred to the side beams. If the panels are square, or nearly so, the distribution may be assumed in accordance with the discussion of Art. 158. Thus the load brought to point a' (Fig. 74) will be one-half of the area below the curve aOa' ,




FIG. 86.

and the load brought to b' will be one-half the area below the curve $bG'b'$, etc. The distribution along the beam will then follow some such law as represented by the shaded area in Fig. 86 (a), the total load being necessarily $\frac{1}{4}wl$, where w = floor-load per square foot. It will be sufficiently accurate to assume this curve a parabola. The centre bending moment in the beam, assumed as a simple beam, will then be equal to

$$M = \frac{5}{128}wl^2.$$

A distribution of load as represented in Fig. 86 (b), as is sometimes assumed, gives a centre moment equal to $\frac{1}{4}wl^2$, a value about 7% higher than the above. A uniform distribution gives a moment equal to $\frac{1}{8}wl^2$, a value 20% lower.

165. Design of Cross-beams.—In the design of beams the chief features are the determination of the cross-section, the amount of steel and its make-up, provision for shearing stress, provision for negative bending moment and connections with slabs, other beams, and columns. The proportions of the beam, whether considered as a rectangular beam or as a T-beam, will be determined by considerations discussed in Chapter V. Ratios of depth to width greater than 2 or $2\frac{1}{2}$ are seldom used. Requirements of head-room, space for rods, and shearing strength will limit the possible variations in proportions to a comparatively narrow range. Deep beams are economical of concrete but cost more for forms than do shallow beams.

If the beam may be calculated as a T-beam, the width of slab which may be counted on as a part of the beam is an important question. Specifications usually allow a width of six to ten times the thickness of the slab, but not to exceed the width between beams. As regards *strength* it would be very difficult to secure so thorough a reinforcement of web as to make it possible to crush a flange as much as four times the width of the web; the excessive shearing stresses in the web would cause failure. As regards *stiffness*, which controls the position of the neutral axis, the width of the slab to be counted as part of the beam may and should be taken relatively great. The width of flange being known, the design of the T-beam consists chiefly in the design of the web and the calculation of the steel cross-section. It will be only in the case of large girders that the compressive stress in the concrete will be a determining factor. Usually there is a large excess of material.

If the beam is to be considered as continuous over supports, the moment of resistance at the support must also be investigated. At this point the tension side is uppermost and the effective beam is now a *rectangular* beam. The maximum moment is about the same as at the centre, thus requiring about the same amount of steel at the top as is required in the centre of the span at the bottom. The maximum compression in the concrete will be greater than in the centre and

will probably determine the size of beam required unless, as is often done, the depth of beam is increased near the end. (See Fig. 87.) Furthermore, if a part of the bottom steel is carried



FIG. 87.

well through the joint, it furnishes considerable compressive reinforcement at this point. The necessary top steel at the end may be provided, as in the slab, by bending up a portion of the lower rods, or by using separate short rods, or by both methods combined. To provide thoroughly for negative moment the upper reinforcement should extend to about the third point, and in some cases still farther. Various arrangements of bent-up rods are illustrated in the examples cited in Art. 168.

It is often required that beams shall be calculated as simple beams, using $\frac{1}{2}wl^2$ for the maximum moment. In such a case it is still desirable to provide some steel at the top over supports to prevent cracks. The beams will then act as partially continuous, the flexibility over the support being greater than when fully reinforced. This results in some excess of stress in this steel, but without danger. The presence of this steel should be taken account of in arranging the web reinforcement.

The treatment of girders is the same as described for beams, it being especially important that the reinforcement pass well through the column.

The arrangement of shear or web reinforcement for beams and girders is of great importance, as it is in these forms where the web tensile stresses will be high. At points where the allowable shearing stress in the concrete is exceeded steel must be added in some form to carry a part of the stress, as explained in Art. 125. Where bent-up rods are used, as in Fig. 87, these rods aid greatly in carrying shear, and where not spaced too widely may be counted on to add perhaps 50% to the strength

of the web. For thorough web reinforcement the stirrup is usually employed, or some form of bent bar closely spaced. This reinforcement may be calculated as explained in Art. 125, not too much reliance being placed on one or two bent rods. Web reinforcement will usually be needed only for the end quarter or third of the beam. Near the support, where the moment is negative, the tendency is for diagonal cracks to start at the top, while farther along the cracks tend to start at the bottom, as shown in Fig. 87. Stirrups at points of negative moment should loop about the upper bars, and at points of positive moment should loop about the lower bars. A correct appreciation of the diagonal stresses in such continuous beams is important.

The beam should be well bonded to the slab, especially near the end where the differential stresses between the two parts are large. This is well accomplished by means of the bent rods brought up as high as possible, and by means of the slab reinforcement which crosses the beam. Along the centre of the beam the matter is not of so great importance, but it is better to provide such bond by some form of vertical rein-




FIG. 88.

forcement, such as stirrups, extending up into the slab at occasional intervals. This is of especial importance in the case of girders where the main slab reinforcement runs parallel to the beam. A good bond is also more necessary the thinner the sections. Sections shown in Fig. 88, (a) and (b), are more favorable than such a section as in Fig. 88 (c). Sharp reentrant angles in such a brittle material as concrete are points of weakness, and where they exist a steel bond is desirable.

166. Columns.—There is little to be said here relative to column design. Much difference of opinion still exists as to

the use of large or small quantities of steel and methods of calculation. A conservative course should be pursued in this matter, as the *columns* and *beams* in a reinforced structure are the vital parts of the structure. Working stresses in columns such as 700 or 800 lbs/in² should not be employed. Where large areas of steel are used, and figured at ordinary working stresses, such steel skeleton should not rely upon the concrete for rigidity. Concrete may, however, be relied upon to transmit loads from girders to columns. Where small areas of steel are used the rods should be well lapped at the floor-level, and those from the lower columns should extend upwards the full depth of the connecting beams. The rods should be well banded together by steel bands or large wire so as to hold all parts in position and to strengthen the column circumferentially. Unless such banding is spaced very closely it should not be counted upon, however, as "hooping." Brackets under all connecting girders are serviceable in stiffening the frame as well as in decreasing the stress in the girders. Rods of connecting girders should pass well through the columns.

167. Eccentric Loads on Columns.—Where loads are applied on free brackets or cantilevers the load is definitely eccentric, and the moment due to the same can readily be calculated. Moments are also caused in columns by unevenly loaded panels through the rigid beam connections. Assuming the beams rigidly fixed at the ends, a panel load on one without a load on the corresponding one on the opposite side will cause a bending moment in the beam at the column equal to $\frac{1}{12}pl^2$, where p =live load per lineal foot of beam. This moment is resisted mainly by the column and the members attached to it in the same plane as the loaded beam, and in proportion to their moments of inertia divided by their lengths.* If the two beams are about as rigid as the column, then the moment in the column above and below the floor will be about one-fourth of the given moment, $=\frac{1}{48}pl^2$. This indicates, roughly, what

* See Johnson's Framed Structures, Art. 154.

may be expected from unequally loaded floors. In the lower stories of a high building such a moment would be of little consequence, but in the upper floors it might add a large percentage to the column stress.

168. Examples of Floor and Column Design.—The following examples have been selected from published designs as representing good practice and as illustrating more or less specifically various features of design.




FIG. 89.—Details of the Robert Gair Factory, Brooklyn.

Fig. 89 illustrates the details of the Robert Gair factory, Brooklyn.* The reinforcement of the columns varies from eight $1\frac{1}{8}$ -in. round rods at the base to four $\frac{3}{4}$ -in. rods at the top. In the lower stories the bars are threaded and connected by sleeves. The rods are connected by hoops spaced from 4 to 10 in. apart. The girders are about 16 ft. apart, and the

* Eng. Record, Vol. 51, 1905, p. 279.

beams about one-third of this distance. Features of design to be noted are the brackets on the columns, bent rods and stirrups in the beams, bent rods in the slabs, and longitudinal reinforcement by the use of $\frac{1}{8}$ -inch bars. The stirrups are rather widely spaced. The Ransome bar was used except in the columns.

Fig. 90 shows the details of the Park Square Garage, Boston.* The slabs are reinforced with expanded metal brought




FIG. 90.—Details of the Park Square Garage, Boston.

near to the top surface over the beams. They were calculated as continuous girders. Beams and girders were calculated as T sections and figured on the basis of 375 lbs/in² compressive stress, and 30 lbs/in² shearing stress with no web reinforcement, and 100 lbs/in² with such reinforcement. The column reinforcement consisted of round rods from 2 $\frac{1}{4}$ in. to $\frac{7}{8}$ in. in diameter. They were banded by $\frac{1}{4}$ in. bands. The concrete used in the columns was 1:1 $\frac{1}{2}$:3; for the lower parts of the beams, 1:2 $\frac{1}{2}$:4; and for the upper parts of the beams and for slabs 1:2 $\frac{1}{2}$:5. The close spacing of the stirrups is noteworthy.

* Eng. Record, Vol. 52, 1905, p. 373.

Fig. 91 shows the construction for the Thompson and Morris factory, Brooklyn. Corrugated bars are used throughout.




FIG. 91.—Details of the Thompson and Morris Factory, Brooklyn.

The girders are spaced 12 to 15 ft. apart and the beams 3 ft. 9 in. apart, four to a panel. The heavy reinforcement for negative moment should be noted.

Fig. 92 shows details of the Citizens' National Bank Building, Los Angeles, Cal.* Large girders connect the columns in both directions, forming panels 17 ft. by 22 ft. These panels are then subdivided into four smaller ones by cross-beams in both directions, a somewhat peculiar arrangement used probably for architectural effect. The slabs are reinforced both




FIG. 92.—Details of the Citizens' National Bank Building, Los Angeles.

ways by $\frac{3}{8}$ -in. twisted bars, $4\frac{1}{2}$ in. apart. The stirrups are flat bands $\frac{3}{16}$ " \times "2" and spaced 18 ins. apart except near the end, as shown. They are looped about the rods in a very effective

* Eng. News, Vol. 56, 1906, p. 16

manner. Note the sleeve-splice for the column bars. The beams and columns are made of 1:2:3 concrete.

Fig. 93 shows a typical girder constructed with the Kahn bar illustrated in Fig. 7, Art. 33. By using inverted bars over the supports negative moment can be provided for, and at the same time additional shear reinforcement.




FIG. 93.—Reinforcement with the Kahn Bar.

In executing work a practical difficulty of considerable importance is that of placing and keeping all bars in their proper position until the concrete is in place. Very considerable labor is required in wiring bars in position, or in providing other means of support, and careful supervision is necessary during construction to see that they remain in place. To avoid these difficulties various arrangements have been devised for fastening together all, or a part, of the rods of a single span into a group which can be handled as a unit, giving rise to the so-called "unit frame". These units are obviously not so adaptable to a great variety of conditions as single independent bars, but their advantages are considerable and they are being used to quite an extent. Fig. 94 illustrates one such type of




FIG. 94.—Unit Frame.

construction manufactured by the Unit Concrete Steel Frame Co. of Philadelphia, and has been used in several buildings. Some of the transverse slab rods pass through the upper ends of the stirrups as shown.

Fig. 95 illustrates a kind of unit reinforcement on the Bertine system and used in the warehouse of the Bush Terminal Co., Brooklyn.* Round rods are used and tied together by round steel stirrups.




FIG. 95.—Unit Frame.

In all the examples here given it is to be noted that the differences of detail refer almost entirely to the method of caring for the shearing stresses and in handling the reinforcing members. The beam and slab arrangement is used in all.

A system of construction quite radically different from the foregoing is shown in Fig. 96, called the "mushroom" system, devised by Mr. C. A. P. Turner. No beams or ribs are used, the loads being transmitted from floor-slab directly to the column. The reinforcement is essentially radial and the column is enlarged at the top to increase the circumference at the line of maximum stress in the slab. The floor is of uniform thickness throughout.

To a certain extent this type of construction follows the natural lines of stress more closely than the rectangular ribbed-panel type; it is best adapted to large areas with few large openings.

The analysis of stresses in this system may be made approximately by the application of the method given in Art. 150, Chapter VI, and Plates X and XI. In applying this method to a continuous floor like the "mushroom" system, an estimate must first be made of the position of the "line" of inflexion with reference to the column. Noting that the point of inflexion of a beam fixed at the ends and uniformly

* Eng. Record, Vol. 53, 1906, p. 36.

loaded is about one-fifth the span length from the end, a sufficiently close estimate of the "line" of inflexion can be made. It will evidently be nearer the column than if the support were a continuous wall. Having estimated the line of inflexion the area within may be treated roughly as a circular plate loaded with the given uniform load on its area and a vertical load along its periphery equal to the remaining part of the load




FIG. 96.—The "Mushroom" System.

tributary to the column. The diagrams then apply directly. Thus, suppose the columns are spaced 16 ft. apart and are 20 ins. in diameter at their upper ends. Suppose the load to be 150 lbs/in² over the entire area. With columns 16 ft. apart, the diagonal spacing will be about 22.5 ft. The line of inflexion will probably not be less than 3 ft. nor more than 4 ft. from the column centre. Call it 3.5 ft. The area of this circle will

be 38.5 sq. ft. The area of the entire square tributary to the column is $16 \times 16 = 256$ sq. ft. Hence the total load applied along the periphery will be $(256 - 38.5) \times 150 = 32,600$ lbs., which will be equal to 1480 lbs. per lineal ft. From Plates X and XI the value of M_1 and M_2 are found to be: (a) for the direct load of 150 lbs/ft², $M_1 = 280$ ft.-lbs., $M_2 = 1040$ ft.-lbs.; (b) for the peripheral load of 1480 lbs/ft, $M_1 = 2960$ ft.-lbs., $M_2 = 8650$ ft.-lbs. If r_1 had been assumed at 4 ft. the values of M_2 would have been 1500 and 9180 ft.-lbs., respectively. An increase in column diameter to 30 ins. would reduce the moments M_2 to about 980 and 6600 ft.-lbs. respectively, assuming a value of r_1 of 4 ft.

In the illustrations shown the columns have been mainly reinforced by longitudinal rods. Various types of banded or hooped columns are used more or less, but usually in connection with longitudinal reinforcement. From the discussion of Chapter IV it would seem that large amounts of hooped reinforcement should not be counted upon too greatly in the strength of the column. In some forms the columns are banded with spirally wound hooping, as in the Considère column, in others flat steel is used in riveted or welded hoops. Expanded metal is also used by wrapping around longitudinal bars.

169. Footings.—The problem of the design of footings is in general the same as that of floors. On account of the heavy concentrated loads and the large unit upward pressures of the earth against the footings the beam construction will be relatively heavy. The beams will be short and deep and will require special attention to provide against excessive shearing and bond stresses. For single footings of ordinary size a single symmetrical slab is most convenient. For larger footings and for footings carrying more than one column, a combination of beam and slab, similar to floor construction, is often most economical.

It is difficult to calculate accurately the stresses in a square footing, but assumptions may be made which will simplify the problem and give results well on the safe side (see Fig. 97).

As a general principle the pressures should be carried as directly as possible from the extremities to the centre. Two sets of main reinforcing rods aa' and bb' will then be used as shown in the figure. The reinforcing of the remaining corners can best be done by sets of diagonal rods dd' . If these cannot cover the area, then a few short cross-rods may be used. Reinforced in this way the total pressure on the area $ABCD$ may be assumed to be carried to the line BC , where the bending moment and shear will be a maximum. Figured as a free cantilever the resulting stresses will be higher than actually exist. If the entire square be reinforced by rods in




FIG. 97.

two directions only, as ee' , then a considerable part of such rods in the corners of the square are ineffective.

The method of analysis of Art. 150, Chapter VI, may also be applied to this problem.

In the case of cantilever beams such as in footings the maximum shearing stress is near the centre where the maximum moment occurs. Shear cracks tend to form on the dotted curved lines, Fig. 97 (b). Bent rods, if used, must be bent up just outside the column, and not at the end of the beam, and stirrups must be spaced closely at this point. The beam being short it may require special attention to bond stress.

For large individual footings a beam and slab may be economical. To secure the benefit of a T section and to give

a flat upper surface the beam may be placed under the slab as shown in Fig. 98. This arrangement requires some attention as to connection of slab to beam, as the upward pressure against the slab tends to pull it away from the beam. The use of an extra horizontal rod in the top of the main beam




FIG. 98.

bonded by stirrups will give a thoroughly good anchorage for the transverse rods of the slab. For still larger areas a system of girders and beams may be adopted constituting a floor reversed as to loads.

170. Walls and Partitions.—The reinforcing of these parts is largely for the purpose of preventing cracks or of localizing them to desired lines. Where lateral pressures occur, of course the beam action must be considered. Walls are usually 3-6 inches thick and reinforced both ways with $\frac{1}{4}$ - to $\frac{1}{2}$ -in. rods, spaced about 2 feet apart.

CHAPTER VIII.

ARCHES.

171. Advantages of the Reinforced Arch.—If the loads on an arch were all fixed loads, it would be possible in any case to construct an arch ring so that the resultant pressure at all sections would intersect the centre of gravity of the section. The compressive stress at any section would then be uniformly distributed over the section, and the arch would be proportioned only for this uniform compression. The “line of pressure” would lie at the axis of the arch throughout. If, however, the arch ring is not made to fit the “line of pressure”, or if part of the load is a live load, then the resultant pressure will not in general coincide with the axis of the arch. There will exist both bending and direct compression. If the resultant pressure and its position are known, the analysis of the stresses at any section is made in accordance with the method explained in Arts. 80–85, Chapter III.

In ordinary masonry or concrete arches tensile stresses are not permissible. The ring must therefore be designed so that the line of pressure will not pass outside the middle third. In reinforced arches this limitation does not exist. The arch rib is a beam, and if properly reinforced it may carry heavy bending moments involving tensile stresses in the steel.

Theoretically the gain in economy by the use of steel in a concrete arch is not great. If the pressure line does not depart from the middle third, the steel reinforces only in compression and in this respect is not as economical as concrete. If the line of pressure deviates farther from the centre, resulting in tensile stresses in the steel, the conditions are such that

those stresses must be provided for by the use of the steel at very low working values. That is to say, the direct compression in the arch is so large a factor that the limiting stresses in the concrete will always result in very small unit tensile stresses in the steel where any tension exists at all.

Practically the value of reinforcement is very considerable. It renders an arch a much more secure and reliable structure, it greatly aids in preventing cracks due to any slight settlement, and by furnishing a form of construction of greater reliability makes possible the use of working stresses in the concrete considerably higher than is usual in plain masonry. Furthermore, in long-span arches where the dead load constitutes by far the larger part of the load, any possible increase in average working stress counts greatly towards economy. It affects not only the arch but the abutments and foundations.

172. Methods of Reinforcement.—The reinforcement of arches is arranged in various ways. Since the arch is a beam subject to either positive or negative bending moments it is essential that it should be reinforced on both sides, but the shearing stresses due to beam action are relatively small, so that little is needed in the way of web reinforcement. The arch is also subjected to heavy compression, so that it is desirable that the inner and outer reinforcement be tied together, somewhat as in a column, although in this case the necessity therefor is much less.

A large proportion of the arches which have been constructed have been built according to some one of the various "systems" that have been devised. The most important of these systems are the Monier and the Melan. In the Monier system, invented about 1865, the reinforcement consists of wire netting, one net being placed near the intrados and one near the extrados. The longitudinal wires are made smaller than those following the arch ring, as they serve only to aid in equalizing the load and in preventing cracks. A large number of bridges have been built in Europe on this system.

In the Melan type, invented about 1890, the steel is in

the form of ribs of rolled I sections, or of built-up lattice girders, which are spaced two to three feet apart. The flanges constitute the principal reinforcement, but the web enables the steel frame to be self-supporting and to carry shearing stresses, and in the open lattice type it furnishes a good bond with the concrete. The Melan arch has been built extensively in this country, largely under the direction of Mr. Edwin Thacher.

Many arches are now being constructed in which reinforcing bars of any satisfactory form are employed without reference to any particular system, being used in accordance with the requirements of the case. The problem of reinforcement is quite as simple as in a beam, after the moments and thrusts in the arch have been found.

ANALYSIS OF THE ARCH.

173. General Method of Procedure.—The method of analysis presented here is based on the elastic theory and is of general application to arches of variable moment of inertia and loaded in any manner. It is mainly an algebraic method, although certain simple graphical aids may be used advantageously. It necessarily assumes that a preliminary design has been made by the aid of approximate or empirical rules or by reference to the proportions of existing arches. This arch is then exactly analyzed and the results used in correcting the design; the corrected design may then in turn be analyzed if it departs too greatly from the one first assumed. A discussion of the various rules for thickness of crown and form of arch will not be entered upon here. For this information the reader is referred to the various treatises on the arch, and especially to those of Professor Cain and Professor M. A. Howe. The work of Professor Howe on "Symmetrical Masonry Arches"* contains a very useful table of data of existing masonry and reinforced-concrete arches.

* New York, 1906.

The analysis of an arch consists in the determination of the forces acting at any section, usually expressed as the *thrust*, the *shear* and the *bending moment*, at such section. The thrust is here taken to be the component of the resultant parallel to the arch axis at the given point, and the shear is the component at right angles to such axis. The thrust causes simple compressive stresses; the shear causes stresses similar to those produced by the vertical shear in a simple beam.

The method of procedure will be to determine, first, the thrust, shear, and bending moment at the crown. These being known, the values of similar quantities for any other section can readily be determined. A length of arch of one unit will be considered.

174. Thrust, Shear, and Moment at the Crown (H_0, V_0, M_0).

Notation. (See Fig. 100.)

Let H_0 = thrust at the crown;

V_0 = shear at the crown;

M_0 = bending moment at the crown, assumed as positive when causing compression in the upper fibres;

N, V , and M = thrust, shear, and moment at any other section;

R = resultant pressure at any section = resultant of N and V ;

δs = length of a division of the arch ring measured along the arch axis;

n = number of divisions in one-half of the arch;

I = moment of inertia of any section = I_{concrete} + nI_{steel} (see p. 92);

P = any load on the arch;

x, y = co-ordinates of any point on the arch axis referred to the crown as origin, and all to be considered as positive in sign;

m = bending moment at any point in the cantilever, Fig. 100, due to external loads.

Let AB , Fig. 99, be a symmetrical arch loaded in any manner with loads P_1, P_2 , etc. Divide the arch into an even number of divisions (ten to twenty usually), making the divisions of such a length that the ratio $\delta s:I$ will be constant. This may be done by trial or by the more direct method explained in Art. 178. Mark the centre point of each division and num-




FIG. 99.

ber the points as shown. Consider the arch to be cut at the crown and each half to act as a cantilever subjected to exactly the same forces as exist in the arch itself, that is, the given loads, the reactions, and the stresses at the crown, represented




FIG. 100.

by H_0 , V_0 , and M_0 (Fig. 100). H_0 is applied at the gravity axis.

Let m = bending moment at any point, 1, 2, 3, etc., due to the given external loads P (considering the arch as two cantilevers). Denote by m_R the moments in the right half and by m_L those in the left half of the arch. All the moments m

will be negative. The values of H_0 , V_0 , and M_0 will then be given by the following equations:

$$H_0 = \frac{n \sum my - \sum m \sum y}{2[(\sum y)^2 - n \sum y^2]}, \quad \dots \quad (1)$$

$$V_0 = \frac{\sum (m_R - m_L)x}{2 \sum x^2}, \quad \dots \quad (2)$$

$$M_0 = -\frac{\sum m + 2H_0 \sum y}{2n}. \quad \dots \quad (3)$$

In these equations the summations $\sum y$, $\sum y^2$, and $\sum x^2$ are for one-half of the arch only; the summation $\sum m$ is for the entire arch and is equal to $\sum m_R + \sum m_L$; the summation $\sum (m_R - m_L)x$ is a summation of the products $(m_R - m_L)x$, in which m_R and m_L are the bending moments at corresponding points in the right and left halves which have equal abscissas x ; and the summation $\sum my$ is for the entire arch, but since symmetrical points have equal y 's this quantity may be calculated as $\sum (m_R + m_L)y$. A positive result for V_0 indicates action as shown in Fig. 100. All quantities are readily calculated. Distances should be scaled and quantities tabulated.*

* *Demonstration.*—Consider the left-hand cantilever of Fig. 100. Under the forces acting the point C will deflect and the tangent to the axis at this point will change direction (the abutment at A being fixed). Let Δy , Δx , and $\Delta \phi$ be, respectively, the vertical and horizontal components of this motion and the change in angle of the tangent. Then according to the principles relating to curved beams¹ we have the values

$$\Delta y = \sum Mx \frac{\delta s}{EI}, \quad \Delta x = \sum Mx' \frac{\delta s}{EI}, \quad \text{and} \quad \Delta \phi = \sum M \frac{\delta s}{EI}, \quad \dots \quad (a)$$

in which the various quantities have the same significance as in Art. 174.

In like manner, referring to the right cantilever, let $\Delta y'$, $\Delta x'$, and $\Delta \phi'$ represent the components of the movement of C and the change of angle of the tangent. These may be expressed in terms similar to Eq. (a).

Now evidently

$$\Delta y = \Delta y', \quad \Delta x = -\Delta x', \quad \text{and} \quad \Delta \phi = -\Delta \phi'. \quad \dots \quad (b)$$

Furthermore, since $\delta s/I$ is constant and likewise E , the quantity $\delta s/EI$ may be placed outside the summation sign.

¹ See Church's *Mechanics*, or Johnson's *Framed Structures*, p. 236.

175. Thrust, Shear, and Moment at any Section.—The values of H_0 , V_0 , and M_0 having been found, the total bending moment at any section, 1, 2, etc., is

$$M = m + M_0 + H_0y \pm V_0x. \quad . \quad . \quad . \quad (4)$$

The plus sign is to be used for the left half and the minus sign for the right half of the arch.

The resultant pressure, R , at any section of the arch is equal in magnitude to the combined resultant of the external loads between the crown and the section in question, and the forces H_0 and V_0 . These resultants can best be found graphically. The thrust, N , is the component of the resultant, R , parallel to the arch axis and the shear, V , is the component perpendicular to this axis.

176. Partial Graphical Calculation.—Where the loads are vertical the calculation of the quantities m can be advantageously performed by means of an equilibrium polygon as follows:

Let AB , Fig. 101, represent the arch axis. The load line is $a-c-b$. Select any convenient pole O on a horizontal line through

Using the subscript L to denote left side and R to denote right side we then derive the relations

$$\left. \begin{aligned} \Sigma M_L x &= \Sigma M_R x, \\ \Sigma M_L y &= -\Sigma M_R y, \\ \Sigma M_L &= -\Sigma M_R. \end{aligned} \right\} \quad . \quad . \quad . \quad . \quad . \quad . \quad (c)$$

The moment M may in general be expressed in terms of known and unknown quantities thus:

$$M_L = m_L + M_0 + H_0y + V_0x \text{ for the left side}$$

and

$$M_R = m_R + M_0 + H_0y - V_0x \text{ for the right side.}$$

Hence, substituting in (c) and combining terms, and noting that ΣM_0 for one half is equal to nM_0 , we have

$$\Sigma m_L x - \Sigma m_R x + 2V_0 \Sigma x = 0, \quad . \quad . \quad . \quad . \quad . \quad . \quad (d)$$

$$\Sigma m_L y + \Sigma m_R y + 2M_0 \Sigma y + 2H_0 \Sigma y^2 = 0, \quad . \quad . \quad . \quad . \quad . \quad . \quad (e)$$

$$\Sigma m_L + \Sigma m_R + 2nM_0 + 2H_0 \Sigma y = 0, \quad . \quad . \quad . \quad . \quad . \quad . \quad (f)$$

From Eq. (d) is obtained Eq. (2), p. 268; and from Eqs. (e) and (f) are obtained Eqs. (1) and (3), noting that $\Sigma m_L + \Sigma m_R = \Sigma m$, and $\Sigma m_L y + \Sigma m_R y = \Sigma my$.

the point c , at the junction of loads P_3 and P_4 , the loads adjacent to the crown C . Construct the equilibrium polygon $efgh$, producing to i and k the segment fg between loads P_3 and P_4 . Drop verticals from the points 1, 2, 3, etc. The desired bending moments m , at the several points, will then be equal to the corresponding intercepts z_2, z_3 , etc., on these verticals between the equilibrium polygon and the line ik , multiplied by the pole distance H ; or in general $m = Hz$.




FIG. 101.

Finally, after the values of H_0 , V_0 , and M_0 are found by Eqs. (1), (2), and (3), the true equilibrium polygon can be drawn, if desired, and values of thrust, shear, and moment at various points determined graphically. The true pole is found by laying off V_0 and H_0 from the point c . The distance of the equilibrium polygon above or below the axis at the crown is equal to M_0/H_0 . It lies above the axis if the result is positive and below if negative. The equilibrium polygon is then drawn from the crown each way towards the ends.

Where the loads are inclined at various angles it is still possible to use a graphical process for getting values of m , but there is little to be gained in such a case. After the values of H_0 , V_0 , and M_0 are found, however, it will be expedient to draw a final equilibrium polygon, or line of pressure, as explained above.

177. General Observations.—The method of analysis just described is brief, general, and easily followed. The arithmetical calculations are not longer than those required in the usual graphical process, while the graphical aids here suggested are of the simplest character.

The loads and their points of application have been considered apart from the divisions of the arch ring, as the two things are in no wise related. Where no spandrel arches are used and the entire load is applied continuously along the arch ring, the load may for convenience be divided to correspond with the arch divisions and applied at the center points, 1, 2, 3, etc. This division is, however, of no importance, the only requirement being a sufficiently small subdivision of the arch ring and of the load so that the errors of approximation will be negligible. Where spandrel arches are used, the live load and a large part of the dead load will be applied at the centers of the arch piers. The weight of the main arch ring may also be considered as concentrated at these same points.

If calculations are to be made for more than one loading it will be noted that the denominators of the values for H_0 , V_0 , and M_0 do not change. The quantities involving m are the only ones requiring recalculation, and if the load on but one-half of the arch is changed, then the values of m for that half only need be recalculated. In the case of a symmetrical loading, or a load on one-half only, the calculation of m is also necessary for one-half the arch only. For symmetrical loads, $V_0 = 0$.

178. Division of Arch Ring to give Constant $\delta s/I$.—In most cases the depth of the arch ring increases from crown towards springing line, giving a variable moment of inertia. Consider-

ing the concrete only, the moment of inertia will increase as d^3 so that a comparatively small change in depth will cause a large change in moment of inertia. To maintain $\delta s/I$ constant, the value of δs will therefore be much greater near the springing line than at the crown, and hence to secure the desired accuracy the length of division at the crown will need to be made fairly short. The value of $\delta s/I$ to adopt so that there will be no fractional division may be determined as follows:

$$\text{Let } i = \frac{1}{I};$$

i_a = mean value of i ;

s = half length of the arch ring measured along the axis;

n = desired number of divisions in one-half the arch.

Calculate first the mean value of i for the half arch ring by determining several values at equal intervals along the arch. Then the desired value of $\delta s/I$ is

$$\frac{\delta s}{I} = \frac{s i_a}{n} \quad . \quad . \quad . \quad . \quad . \quad . \quad . \quad (5)$$

The value of $\delta s/I$ being known, the proper length of δs for any part of the arch ring can readily be determined. Beginning at the crown, the length of the first division is determined, then the second, third, etc., to the end. The length of a division not being exactly known beforehand, the value of I for that division will not be exactly known, but the necessary adjustment is very simple.

In determining the value of I the steel reinforcement must be duly considered.

179. Temperature Stresses.—For a rise of temperature of t degrees the increase in span-length, if the arch be not restrained, would be equal to ctl , where c = coefficient of expan-

sion and l =span. The restraint of the abutments induces a thrust H_0 at the crown given by the equation

$$H_0 = \frac{EI}{\delta s} \cdot \frac{ctln}{2[n\Sigma y^2 - (\Sigma y)^2]} \quad (6)$$

The summations refer to one-half the arch.

Having determined H_0 , then

$$M_0 = -\frac{H_0 \Sigma y}{n} \quad (7)$$

The bending moment at any point is

$$M = M_0 + H_0 y. \quad (8)$$

The thrust and shear at any point in the arch are found by resolving H_0 parallel and normal to the arch axis at that point. Graphically, the true equilibrium polygon is a horizontal line drawn a distance below the crown equal to $M_0/H_0 = \Sigma y/n$.

180. Stresses Due to Shortening of Arch from Thrust.—A thrust throughout the arch producing an average stress on the concrete equal to f_c lbs/in² would shorten the arch span an amount equal to $f_c l/E$ if unrestrained. This action develops horizontal reactions in the same manner as a *lowering* of tem-

* *Demonstration.*—For temperature stresses $\Delta\phi$ of Eq. (a), p. 268, is zero and Δx is equal to the change in length of the half-span, $= \frac{ctl}{2}$. We therefore have

$$\Sigma M_{Ly} \frac{\delta s}{EI} = \frac{ctl}{2},$$

and

$$\Sigma M_L = 0.$$

In this case, there being no external loads, $m=0$, and from symmetry, $V_0=0$, hence $M=M_0+H_0 y$. Substituting this value of M in the above equations we have

$$M_0 \Sigma y + H_0 \Sigma y^2 = \frac{ctl}{2} \cdot \frac{EI}{\delta s},$$

and

$$nM_0 + H_0 \Sigma y = 0.$$

From these are readily derived Eqs. (6) and (7).

perature. The value of the resulting reactions, or the crown thrust, may then be found by substituting $f_c l/E$ for ctl of Eq. (6). There results

$$H_0 = -\frac{I}{\delta s} \cdot \frac{f_c l n}{2[n\Sigma y^2 - (\Sigma y)^2]} \quad \dots \quad (9)$$

The moments at crown and elsewhere are given by Eqs. (7) and (8), using the value of H_0 from Eq. (9).

The thrusts and moments due to arch shortening will not usually be large. They may be applied as corrections to the thrusts and moments found before.

181. Deflection of the Crown.—The downward deflection of the crown under a load is given by Eq. (a), p. 268. It is

$$\Delta y = -\frac{\delta s}{EI} \Sigma Mx. \quad \dots \quad (10)$$

If M is not determined for all points, use the value of M from Eq. (4), deriving

$$\Delta y = -\frac{\delta s}{EI} [\Sigma mx + M_0 \Sigma x + H_0 \Sigma xy + V_0 \Sigma x^2]. \quad \dots \quad (11)$$

The summations are for one-half only.

The *rise* of crown due to an increase of temperature is obtained from Eq. (11) by substituting from Eqs. (6) and (7). There results

$$\Delta y = \frac{ctl}{2} \cdot \frac{n\Sigma xy - \Sigma x \Sigma y}{n\Sigma y^2 - (\Sigma y)^2} \quad \dots \quad (12)$$

182. Unsymmetrical Arches.—If the arch is unsymmetrical the value of $\delta s/I$ should be made constant for the entire arch, and the number of divisions made even as before. The central point of the arch with reference to the *number* of divisions may then be taken as the crown, and the X -axis made tangent to the arch at this point. The two halves of the arch are now unlike and all terms resulting from substitution in Eq. (c), p. 269, must be retained. Explicit formulas for H_0 ,

V_0 , and M_0 are very cumbersome, but the three equations derived from (c) are as follows:

$$(\Sigma_L x - \Sigma_R x)M_0 + (\Sigma_L xy - \Sigma_R xy)H_0 + \Sigma x^2 V_0 = \Sigma_R mx - \Sigma_L mx, \quad (13)$$

$$\Sigma y M_0 + \Sigma y^2 H_0 + (\Sigma_L xy - \Sigma_R xy)V_0 = -\Sigma my, \quad . \quad . \quad (14)$$

$$2nM_0 + H_0 \Sigma y + (\Sigma_L x - \Sigma_R x)V_0 = -\Sigma m. \quad . \quad . \quad (15)$$

Where no subscript is used the summation is for the entire arch. Numerical values of the coefficients of M_0 , H_0 , and V_0 should be obtained and the equations then solved.

183. Application of the Preceding Theory.—Example 1.—

An arch ring will be assumed of the dimensions shown in Fig. 102. Span length with reference to the axis = 30 ft., rise = 8 ft. Thickness at crown = 1 ft., at springing lines = 1 ft. 6 in. For a small arch such as this great accuracy is not needed, hence a small number of divisions may be used. The number will be four for each half. These divisions are determined so that $\delta s/I$ is constant. The loads are applied at the centre-points 1, 2, 3, 4, and are assumed to be somewhat inclined (excepting loads P_4 and P_5), the several vertical and horizontal components being as given in the figure.

TABLE A.
CALCULATIONS FOR H_0 , V_0 , AND M_0 .

1	2	3	4	5	6	7	8	9
Point.	x	y	x^2	y^2	m_L	m_R	$(m_L + m_R)y$	$(m_R - m_L)x$
1	1.55	.09	2.40	.01	0	0	0	0
2	4.90	.68	24.01	.46	- 13,840	- 8,640	- 15,300	+ 25,500
3	8.45	2.10	71.40	4.41	- 46,800	- 29,560	- 160,400	+ 145,700
4	12.85	5.35	165.12	28.62	- 116,680	- 75,490	- 1,028,100	+ 529,300
Σ		8.22	262.93	33.50	- 291,010		- 1,203,800	+ 700,500
Spring- ing.	15.00	8.00			- 180,820	- 120,640		

$$\text{Eq. (1) gives } H_0 = \frac{4(-1203800) - (-291010 \times 8.22)}{2[(8.22)^2 - 4 \times 33.50]} = + 18,230 \text{ lbs.}$$

$$\text{Eq. (2) gives } V_0 = \frac{700500}{2 \times 262.93} = + 1,330 \text{ lbs.}$$

$$\text{Eq. (3) gives } M_0 = - \frac{-291010 + 2 \times 18230 \times 8.22}{2 \times 4} = - 1,090 \text{ ft.-lbs.}$$

TABLE B.

BENDING MOMENTS, THRUSTS, AND ECCENTRIC DISTANCES.

1	2	3	4	5	6	7	8	9
Point.	H_0y	V_0x	Bending Moment M .		Thrusts.		Eccentric Distances.	
			Left.	Right.	Left.	Right.	Left.	Right.
1	1,640	2,060	+2,610	-1,520	18,450	18,640	+ .14	-.08
2	12,400	6,530	+4,000	-3,860	19,580	19,310	+ .21	-.20
3	38,300	11,260	+1,650	-3,620	22,050	20,770	+ .07	-.17
4	97,500	17,120	-3,100	+3,850	28,800	24,970	-.11	+ .15
Springing.	145,900	20,000	-16,070	+4,140	28,800	24,970	-.56	+ .17

The calculations of the several quantities in the formulas for H_0 , V_0 , and M_0 (p. 268) are given in Table A. The coordinates x , y of the several points are given in cols. 2 and 3; then x^2 and y^2 in cols. 4 and 5; then in cols. 6 and 7 are given the quantities m_L and m_R , considering each half-arch a cantilever. These are readily calculated. Thus, on the left, for point 1, $m=0$; for point 2, $m=4130 \times (4.90 - 1.55) = 13,840$; for point 3, $m=4130 \times (8.45 - 1.55) + 5035 \times (8.45 - 4.90) + 310 \times (2.10 - .68) = 46,800$; and for point 4, $m=4130 \times (12.85 - 1.55) + 5035 \times (12.85 - 4.90) + 5950 \times (12.85 - 8.45) + 310 \times (5.35 - .68) + 725(5.35 - 2.10) = 116,680$. The value of m at the springing line is also calculated and placed in this table for future use. The moments on the right are similarly found. All moments m are negative. In cols. 8 and 9 are then given the products $(m_L + m_R)y$ and $(m_R - m_L)x$.

Substituting in Eqs. (1), (2), and (3), p. 268, there are obtained the values for H_0 , V_0 , and M_0 given below the table.

The values of the bending moments, thrusts, and shears at any point may now be found either graphically or algebraically. The force-diagram method will be much the better for obtaining thrusts and shears; the moments may then be obtained either

by constructing an equilibrium polygon or by the application of Eq. (4), p. 269.

In Fig. 102 the graphical construction is given. The load-line is $a-c-b$. The true pole is found by laying off $V_0 = +1330$ from point c (at the junction of the loads adjacent to the crown, P_4 and P_5); then $H_0 = 18,230$ horizontally to O . The




FIG. 102.

force diagram is drawn and then the equilibrium polygon, beginning at the crown and drawing the segment 1-1 at a distance *below* the crown equal to $1090/18230 = .06$ ft. The resultant, R , acting at any section may be scaled from the force polygon, and the moment at any point will be equal to this resultant multiplied by the perpendicular distance at that point from the arch axis to the equilibrium polygon. For example, the bending moment at point g is equal to the force Od multiplied by the arm gk . The tangential component of the

resultant R (the true thrust N) may be found by resolving the force R parallel and normal to the arch axis at the point in question. In most cases the thrust N may be taken as equal to R . The shear V will be the normal component of R ; it will not usually require consideration.

Table B contains calculated values of moments and eccentric distances for points 1, 2, 3, 4 and the springing lines. The moments are calculated from the formula (Eq. (4)) $M = m + M_0 + H_0y \pm V_0x$. The quantities m are obtained from Table A, cols. 6 and 7. The thrusts are scaled from the force polygon, being in each case the thrust on the abutment side of the point in question. The eccentric distances are equal to the moments divided by the thrusts; they are of use in calculating stresses in the arch. Obviously the bending moment at any other point, such as g , may be calculated in the same way as those here given.

184. Example 2. (Fig. 103.)—For another example an arch will be assumed of 100-ft. span and 20-ft. rise; thickness at crown=30 in., thickness at springing line=42 in. It will be assumed that the roadway is supported on spandrel piers 10 ft. apart, thus concentrating most of the load at points 10 ft. apart as shown; the weight of the arch ring will also be assumed as applied at these points. The loads as given represent an arch with live load on the left half only. The half arch is divided into ten divisions, making $\delta s/I$ constant. The loads in this case are vertical, so that the graphical method may be used to advantage in determining the cantilever moments m . The load line $a-c-b$ is drawn and a pole O' selected on a horizontal line through c at the center of the crown load P_5 . The pole distance is H . An equilibrium polygon, $efgh$, is then drawn, and the moments m will be equal to the intercepts, z , from this polygon to the horizontal line ik , multiplied by H . These moments, and the remainder of the calculations for H_0 , V_0 , and M_0 are given in Table C. The true pole O is then found as before and the correct equilibrium polygon drawn. The thrusts are then scaled from the force polygon, and the eccentric




Fig. 103.

distances from the equilibrium polygon. These are given in Table D, together with resulting bending moments. The bending moments may also be calculated as done in Example 1.

TABLE C.
CALCULATIONS FOR H_0 , V_0 , AND M_0 .

1	2	3	4	5	6	7	8	9
Point	x	y	x^2	y^2	m_L	m_R	$(m_L + m_R)y$	$(m_R - m_L)x$
1	2.07	.07	4.3	.00	13,500	13,500	2,000	—
2	5.96	.30	35.5	.09	38,700	38,700	23,000	—
3	10.00	.72	100.0	.52	65,000	65,000	94,000	—
4	14.18	1.40	201.1	1.96	148,800	127,700	387,000	+ 296,000
5	18.43	2.37	339.7	5.62	233,800	191,400	1,007,000	+ 777,000
6	23.06	3.77	531.8	14.21	369,000	288,400	2,479,000	+ 1,859,000
7	28.06	5.64	787.4	31.81	539,000	408,400	5,348,000	+ 3,665,000
8	33.60	8.23	1129.0	67.73	781,400	577,400	11,183,000	+ 6,854,000
9	39.60	11.80	1568.2	139.24	1,075,400	781,400	21,910,000	+ 11,642,000
10	46.40	16.80	2153.0	282.24	1,511,000	1,083,000	43,580,000	+ 19,859,000
Σ		51.10	6650.0	543.42	— 8,350,100		— 86,013,000	+ 44,952,000

$$H_0 = \frac{10 \times (-86013000) - (-8350100) \times 51.10}{2[(51.10)^2 - 10 \times 543.42]} = +76,760 \text{ lbs.},$$

$$V_0 = \frac{44952000}{2 \times 6850} = +3,280 \text{ lbs.}$$

$$M_0 = -\frac{-8350100 + 2 \times 76760 \times 51.10}{2 \times 10} = +25,260 \text{ ft.-lbs.}$$

TABLE D.
THRUSTS, ECCENTRIC DISTANCES, AND MOMENTS.

1	2	3	4	5	6	7
Point.	Thrusts.		Eccentric Distances.		Bending Moments.	
	Right.	Left.	Left.	Right.	Left.	Right.
1	76,800	77,400	+ .31	+ .13	+ 23,700	+ 10,100
2	76,800	77,400	+ .38	— .13	+ 29,200	— 10,100
3	78,600	78,800	+ .61	— .22	+ 48,000	— 17,300
4	78,600	78,800	+ .39	— .53	+ 30,700	— 41,700
5	78,600	78,800	+ .44	— .57	+ 34,700	— 45,000
6	82,700	81,500	+ .26	— .61	+ 21,200	— 49,700
7	82,700	81,500	+ .14	— .52	+ 11,400	— 42,400
8	89,300	85,300	— .15	— .36	— 13,400	— 30,700
9	89,300	85,300	— .16	+ .23	— 14,300	+ 19,600
10	98,600	90,700	— .44	+ .88	— 43,400	+ 80,000
Springing	98,600	90,700	— .21	+ 1.67	— 20,700	+ 152,000

Temperature Stresses.—Suppose in Ex. 2 it is desired to know the thrust and bending moment at the crown due to a rise of temperature of 30° . Eqs. (6) and (7), Art. 179, will be used. Assume $E=2,000,000$ lbs./in² $=288,000,000$ lbs./ft². Suppose the value $\delta s/I$, in foot-units, is 3.1. Then from Eq. (6)

$$H_0 = \frac{288,000,000}{3.1} \times \frac{.000006 \times 30 \times 100 \times 10}{2(10 \times 543 - (51.1)^2)} = 2970 \text{ lbs.},$$

$$M_0 = -2970 \times \frac{51.1}{10} = -15,200 \text{ ft-lbs.}$$

The equilibrium polygon is a horizontal line drawn a distance below the crown equal to $15200/2970=5.11$ ft. The moment at any point is equal to the thrust H_0 multiplied by the vertical distance from such point to this equilibrium polygon. At the springing line, $M=H_0 \times (20-5.11)=2970 \times 14.89=44,200$ ft-lbs. This may also be calculated by Eq. (8).

Stresses Due to Shortening of Arch.—The modification of the thrust due to the compressive deformations of the arch ring is found by Eq. (9). The average compressive stress at any section is found by dividing the thrust at that section by the area of the transformed section of arch ring. This is nearly uniform throughout the arch and equal to about 150 lbs/in². Then.

$$H_0 = -\frac{1}{3.1} \times \frac{150 \times 144 \times 100 \times 10}{2[10 \times 543 - (51.1)^2]} = 1240 \text{ lbs.}$$

This thrust is equal to 42% of the thrust due to temperature change, already found. The resulting moments and stresses will then be 42% of those due to temperature change. They will be of opposite sign.

185. Maximum Stresses in the Arch Ring.—From the values of thrust, moment, and eccentric distance, as given in Tables B and D, the stresses in the concrete and steel can be found at any section of the arch, as explained in Chap. III and also in Art. 147, Chap. VI. The maximum value of fibre stress

will be where the sum of the stresses due to thrust, N , and moment, M , is a maximum. This will not in general be where either the thrust or the moment is a maximum; but as the thrust varies slowly along the arch ring the maximum stress will occur very near to the point of maximum moment.

The position of live load causing maximum moment at any point will differ in arches of different proportions. In designing an arch it is sufficient generally to determine the maximum stresses at the crown, the haunch, and the springing line. This will require several different positions of the live load. For the crown the maximum positive moments are caused when a short length of the arch (one-fourth to one-third) at the center is loaded, and the maximum negative moments when the remaining portions are loaded. The maximum positive and negative moments at the haunch (about the $\frac{1}{4}$ point) are caused when the arch is loaded about two-thirds the span length and one-third the span length respectively. The same loading will give practically the maximum moments at the springing lines.

These conditions make it desirable to analyze the arch for various assumed loadings about as follows: full load; one-third of span loaded; two-thirds of span loaded; center third loaded; and end thirds loaded. In the case of large and important structures it may be found desirable to place the loads somewhat differently than here indicated. A complete and exact solution can readily be made by analyzing the arch for a load of unity at each load-point of one-half of the arch. Influence lines can then be drawn for moment or fibre stress and the exact maximum values determined.

186. Illustrative Examples of Arch Design.—Fig. 104 shows a longitudinal section and part plan of a bridge at Grand Rapids, Mich.* It consists of five spans of lengths from 79 to 87 feet. The reinforcement is composed of $1\frac{1}{4}$ -in. Thacher bars spaced 14 in. apart near both the extrados and intrados. Each pair is connected by $\frac{5}{8}$ -in. connecting-rods spaced 4 ft. apart.

* Eng. News, Vol. LII, 1904, p. 490.




FIG. 104.—Arch Bridge at Grand Rapids, Mich.




FIG. 105.—Arch Bridge on the Chicago & Eastern Illinois R.R.

Concrete-Steel Engineering Co., of New York City, and is a typical Melan arch. The reinforcement consists of built-up ribs of $3'' \times 3'' \times \frac{3}{8}''$ angles connected by lattice bars $2'' \times \frac{1}{4}''$.




FIG. 107.

The ribs are spaced 3 ft. apart. These ribs are designed to carry the entire bending moment at a stress of 18,000 lbs/in². The stress in the concrete was limited to 500 lbs/in² in com-

pression, or 600 lbs/in² including temperature stresses. The roadway is supported over a considerable portion of the span length by means of a reinforced floor carried on vertical walls.




FIG. 109.

The viaduct contains eight spans of the dimensions shown in the illustration.

Figs. 108 and 109 illustrate another design for the same viaduct mentioned in the preceding paragraph.* This design was

* Eng. News, Vol. LVII, 1907, p. 178.

submitted by Mr. C. A. P. Turner, of Minneapolis, Minn. In this case the arch is composed of three ribs 4 ft. 9 in. square at the crown and 7 ft. 3 in. square at the pier. The rib reinforcement is composed of longitudinal rods arranged in a circle and connected at frequent intervals by bands of $2\frac{1}{8}'' \times \frac{3}{8}''$ metal. The stirrups and bent bars in the floor-beams and slabs give a very effective reinforcement.

CHAPTER IX.

RETAINING-WALLS AND DAMS.

187. Advantages of Reinforced Concrete.—Retaining-walls, dams, bridge abutments, and the like constitute a class of structures in which the outside forces acting are mainly horizontal, and in which, therefore, the question of stability is largely a question of safety against overturning. Where ordinary masonry is used in these structures the weight of the material must be depended upon to balance the overturning forces; for though the structure be anchored to the foundation no tensile stresses can be allowed in the masonry. As a consequence of these limitations the maximum compressive stresses in such structures are not high, except in extreme cases, so that generally the dimensions are determined by the weight of the material. The application of reinforced concrete in such cases enables the design to be so modified as to utilize the weight of the material to be retained as part of the resisting weight and to calculate the sections to develop more nearly the full strength of the concrete. A very considerable gain in economy therefore results.

RETAINING-WALLS.

188. Method of Determining Stability.—No attempt will be made here to present the various mathematical theories of earth pressure. Unless the results obtained from such theories are carefully controlled by the results of experience they are apt to be very misleading. Probably the most satisfactory way to design a reinforced concrete retaining-wall, as regards stability against overturning, is to proportion it so that it will be,

as nearly as possible, equivalent to a solid masonry wall of such a section as is known to have given satisfactory results under the given conditions. Rules of practice as to solid masonry walls have long been established. They represent the accumulated experience of many engineers and are based upon data obtained from many failures as well as from successful designs. Until experience is had directly with the reinforced type of wall its stability may, therefore, well be determined by comparison with the older form of construction. The analysis given here will consequently be limited to a convenient method of comparison of the two types. It may be said in passing that good construction requires quite as much attention to the earth filling itself and to its drainage as to the design and construction of the wall.

In dimensioning a reinforced concrete wall which will possess stability equal to that of a given solid wall, it will be convenient to determine the equivalent fluid pressure under which the solid wall will be stable and then apply this pressure to the reinforced type of wall. The basis of the calculation of this fluid pressure will be to determine the weight per cubic foot of a fluid which will exert such a pressure against the solid wall as to cause the resultant of all forces above the base to intersect the base at the edge of the middle third. If, then, the reinforced wall be designed so that it will be equally stable against this pressure, it will be practically equivalent to the solid wall.

It will be seen that this method is very simple and adapts itself readily to the utilization of present rules of practice. If desired, the theory of earth pressure may of course be directly applied to the problem.

189. Equivalent Fluid Pressure for Ordinary Masonry Walls.—Two forms of wall will be considered (Fig. 110). Form (a) is the more common form of wall. A small batter is usually given to the front face, and the back face is sloped in an irregular line, the width of the top being as narrow as circumstances may warrant. Such a wall will be stable when the width of the base is made from one-third to one-half the height,

four-tenths being a common rule of practice. Form (b) is used for relatively low walls. Its width may be a little less than that of form (a) for equal stability. While the calculations here given apply only to the two forms as represented in Fig. 110, the results will be but little different for walls similar in form but which vary considerably therefrom.

Form (a).—The height is h and the bottom width l . The batter of the front face will be taken at 1:12, and the top width at $1/6$ of the bottom width. The weight of the masonry will be assumed at 150, and that of the earth filling at 100 lbs/ft³. It will be assumed that the fluid pressure acts against a vertical plane FC ; the stability of the entire volume to the left of this




FIG. 110.

plane, including the weight of the earth, will be determined. Let W_1 denote the weight of masonry per lineal foot, and W_2 the weight of the earth filling to the left of FC . Let P denote the resultant fluid pressure acting at a distance $\frac{1}{3}h$ above the base. Let p denote the weight per cubic foot of such fluid. Then $P = \frac{1}{2}ph^2$.

Assume that the resultant pressure due to the weight of the wall W_1 , the weight of the earth W_2 , and the pressure P , intersects the base at the edge of the middle third. Equating moments about this point we derive the relation

$$p = 132 \frac{l^2}{h^2} \quad \dots \dots \dots (1)$$

Form (b).—In this form the only forces to be considered are the weight W_1 and the pressure P . Equating these as before there results

$$p = 150 \frac{l^2}{h^2} \quad \dots \dots \dots (2)$$

wall AE by means of buttresses. In either case the earth pressures act in essentially the same manner and the necessary width of base is found in the same way.

Let l = width of base;

x = distance from toe to back of wall AE ;

h = height;

p = equivalent fluid weight as determined in Art. 189;

w_2 = weight of earth filling per cubic foot;

W_1 = weight of masonry per lineal foot;

W_2 = weight per lineal foot of earth above the floor EC ;

a = lever-arm of W_1 about point F , the edge of the middle third;

P = total fluid pressure = $\frac{1}{2}ph^2$.

Then equating moments about the point F we have

$$W_1a + W_2\left(\frac{2}{3}l - \frac{l-x}{2}\right) = \frac{Ph}{3}, \quad \dots \dots \dots (3)$$

or

$$W_1a + w_2h(l-x)\left(\frac{2}{3}l - \frac{l-x}{2}\right) = \frac{ph^3}{6} \dots \dots \dots (4)$$

If the wall AE is placed well towards the front the moment of the masonry will be small. Neglecting this term and putting $x = kl$ we may solve for l , getting

$$l = h\sqrt{\frac{p}{w_2(1+2k-3k^2)}} \dots \dots \dots (5)$$

This is a minimum for $k = \frac{1}{3}$, that is, for $x = \frac{1}{3}l$. With this value of k we have

$$l = .87\sqrt{\frac{p}{w}}.h \dots \dots \dots (6)$$

For $w = 100$

$$l = .087\sqrt{p}.h \dots \dots \dots (7)$$

If, for example, the value of p be taken at 21.1, corresponding to a value of $l/h = 4/10$ for a solid wall, the value of l is

equal to $.087 \times \sqrt{21.1} \times h = .4h$, or the same as the width of the solid wall.

As it may be desirable to use a smaller or larger value of x than $\frac{1}{3}l$, Table No. 22 has been prepared giving the values of l/h for various values of x/l and various values of p . An examination of the table shows plainly that the length of the projection x makes very little difference in the required total length of base. However, with x made very small or very large the weight of the wall should be taken into account. A further fact brought out by the table and by the table of Art. 189 is that the stability of the reinforced wall is about the same as a solid wall of form (a) shown in Fig. 110 and having the same base length.

TABLE No. 22.

PROPORTIONS OF REINFORCED-CONCRETE RETAINING-WALLS.

(See Fig. 111.)

VALUES OF l/h FOR DIFFERENT VALUES OF p AND FOR $w_2=100$ (Eq. (5)).

Values of $k=x/l$	Values of Equivalent Fluid Weight p . Pounds per Cubic Foot.			
	15	20	25	33
.5	.35	.40	.45	.51
.33	.34	.39	.43	.50
.25	.34	.39	.44	.50
.20	.34	.40	.44	.51
.15	.35	.40	.45	.52
.10	.36	.41	.46	.53
0	.39	.45	.50	.57

The resultant forces acting upon the three parts of the wall AE , DE , and EG must be determined. On the wall AE the force may be taken as a horizontal force equal to $P = \frac{1}{2}ph^2$, and applied a distance $\frac{1}{3}h$ above the base. The resultant force acting on any length h' from the top is likewise $\frac{1}{2}ph'^2$ and applied a distance $\frac{2}{3}h'$ below the top. The pressure on the foundation will equal the total weight $W_1 + W_2$ and will be applied a distance $\frac{1}{3}l$ from point D . The average unit pressure will be

$(W_1 + W_2)/l$, and the maximum pressure at D will be twice this value.

The upward pressure under the cantilever DE will vary from a maximum of $2\frac{W_1 + W_2}{l}$ at D to a value under the point E of $2\frac{W_1 + W_2}{l} \times \frac{l-x}{l}$. This is a "trapezoid" of pressure, and where x is large the centre of gravity of the trapezoid may be found and the resultant applied at this point. Usually it will be accurate enough to assume the pressure on DE as uniformly distributed at an average value and applied at the centre of the projection outside of the vertical wall.

The upward pressure on the floor EC varies from the value above given at E , to zero at C . It varies uniformly between these points. The downward pressure is the weight of the earth above the floor, $= W_2$. This may be assumed as uniformly distributed and equal to $w_2 h$ per unit area at all points. The total downward pressure on EC will be greater than the upward pressure unless x is very small.




FIG. 112.

191. Design of Wall.—In discussing the design it will be necessary to consider two forms: (1) the cantilever wall without back tie-walls as in Fig. 112, and the wall provided with such back walls as in Fig. 113.

The form of Fig. 112 is adapted to heights of about 12 to 18 feet. For high walls the form of Fig. 113 will be more economical.

Form (a). (Fig. 112.)—The maximum moment in the upright portion AE is $P\frac{h}{3} = \frac{ph^3}{6}$. At any distance h' below the top the moment is $\frac{ph'^3}{6}$. Only a portion of the reinforcing-rods need be carried up the full height. The shear at the bottom is $P = \frac{ph^2}{2}$. This will be very small and will require no

special attention. The reinforcing-rods of a cantilever beam have their maximum stress at the end of the beam, hence special care must be given to secure an effective bond or anchorage. In the figure the vertical rods have an insufficient length below the point of maximum moment to develop their full strength, and therefore they should be anchored in a substantial manner. This may be done by screw-ends and nuts, or by looping the rods around anchor-bars near the bottom of the floor *DC*.

The cantilever *DE* must be treated in the same manner as the upright cantilever. The pressures will be much heavier and the shear and bond stress may need attention. The reinforcement should extend far enough beyond *E* for bond strength.

The cantilever *EC* is acted upon by an upward and a downward force as shown in the figure. The maximum moment will be at *E* and will be negative. It is provided for by reinforcement as shown.

To secure maximum economy each one of the cantilevers may be tapered towards the end to a minimum practicable thickness. The bending moments at various sections in a cantilever beam uniformly loaded vary as the squares of the distances from the free end. The resisting moments vary approximately as the squares of the depths of the beam. Hence a beam tapering uniformly to zero depth at the end would be of the necessary depth at all points. The moments in the vertical beam *AE* vary as the cubes of the distances below the top, so that a straight taper will in this case give a beam whose weakest point will be at the bottom. At the top point *A* some form of coping is usually added, of a width according to the requirements of the case.

To prevent unsightly cracks a certain amount of longitudinal reinforcement is necessary. The amount required per square foot of cross-section will be less the heavier the wall, as temperature changes will be less in such a wall. On the basis of the discussion in Chap. V, Art. 142, the percentage required may be placed at about 0.4% as a maximum for thin walls, to

perhaps one-half of this for heavy walls. High elastic-limit material is advantageous for this purpose.

Form (b). (Fig. 113.)—So far as the external pressures are concerned they have been explained in Art. 189, and are practically the same as in the previous case considered. The loads or pressures on the concrete are, however, carried quite differently. The toe DE is the same as in form (a) and reinforced in the same way. The pressure against the longitudinal wall AE is carried laterally for the most part and given over to the inclined




FIG. 113.

back walls. The wall AE must therefore be designed as a slab supported along the lines AE and $A'E'$ (Fig. 113 (b)), and subjected to a pressure per square foot at any point a distance h' below the top equal to ph' . Near the bottom, the load on AE is transmitted more or less to the floor EC . The wall should therefore be bonded to the floor with a small amount of vertical reinforcement, which may well extend to the top to prevent cracks, although under ordinary conditions the wall AE is under some vertical pressure.

The floor EC is subjected to both upward and downward pressures, the latter exceeding the former towards the end C ,

and possibly throughout, as previously explained. This floor is supported by the back wall AEC and is therefore reinforced longitudinally as a floor-slab in accordance with the resultant pressure at any point. Here, again, it is well to bond the floor to the wall AE by extending the transverse reinforcement of the toe DE into the portion EC .

The back wall ACE acts as a cantilever beam anchored to the floor. It is also a T-beam, the flange being the longitudinal wall AE . The tension along the edge AC is carried by rods near this edge, whose stress at any point is found with sufficient accuracy by an equation of moments taken about the center of the front wall. The maximum stress will be at the bottom, if the wall is made with a straight profile. At the connection of the wall AEC to the floor, it is to be noted that the floor load is transferred to the wall along the line EC , but mainly near the end C . The main tension-rods in AC should therefore be distributed somewhat at their lower ends and well anchored to the reinforcing-rods of the floor EC . A few additional vertical rods should also be put in to insure thorough bonding of floor to wall. These will also carry a part of the tension in the back wall, but will not be as efficient as the rods nearer the outside edge. It is desirable, likewise, to bond the vertical wall AE to the back wall with short horizontal rods as shown. The slabs formed by the walls AE and the floor EC are continuous over supports, and if the span is long should be provided with some reinforcement for negative moments at these supports.




FIG. 114.

Fig. 114 shows some additional features of design which have been used. A longitudinal beam is built at C and the floor is thus supported on all four edges. The main rods along AC are then anchored into the beam.

A horizontal beam may also be made of the coping at A , thus giving some support to the wall AB along its upper edge.

A projection may be necessary at the toe *D*, or elsewhere, in order to increase the resistance against forward sliding. The beam *C* aids in this respect.

. 192. **Illustrative Examples.**—Fig. 115 shows the form of retaining-wall used on the Great Northern R.R. at Seattle,




FIG. 115.—Retaining-wall, Great Northern Railway.

Wash.* This is a good illustration of the second type above discussed. An estimate by Mr. C. F. Graff of the amounts of material per lineal foot required in reinforced and plain con-

* Eng. News, Vol. LIII, 1905, p. 262:




Fig. 116.—Standard Abutment, Wabash Railroad.

crete walls, made in connection with the design of Fig. 115, gave the following results:

Height of Wall, Feet.	Amount of Concrete per Lineal Foot.		Saving: Per Cent of Reinforced Wall.
	Plain Wall, Cubic Feet.	Reinforced Wall, Cubic Feet.	
40	396.4	218	45
30	226	127.8	43.3
20	110	69.9	36.4
10	44	34.9	20.4

The steel was included by adding its concrete equivalent.

Fig. 116 illustrates a standard form of abutment used by the Wabash R.R. Co.*

193. Retaining-walls Supported at the Top.—Frequently a retaining-wall may be supported at the top. In such a case it is designed as a simple beam supported at the top and bottom; or vertical ribs or beams may thus be calculated and the slab reinforced horizontally and supported by these ribs.

A wall AB (Fig. 117) acted upon by a pressure uniformly varying from zero at the top to a maximum at the bottom will be subjected to a bending moment whose maximum value will be determined. Let the pressure be that due to a fluid weighing p lbs/ft³. Then $P = \frac{1}{2}ph^2$, $R_1 = \frac{1}{3}P = \frac{1}{6}ph^2$, $R_2 = \frac{1}{3}ph^2$.




FIG. 117.

The bending moment M at a distance x below

$$A = R_1x - \frac{1}{6}px^3 = p/6 (h^2x - x^3).$$

This is a maximum for $x = h\sqrt{\frac{1}{3}} = .58h$. The maximum moment is then

$$M = .064ph^3. \quad \dots \dots \dots (8)$$

If the pressure is water pressure, as in a reservoir, the value of the maximum moment becomes equal to

$$M = 4h^3, \quad \dots \dots \dots (9)$$

where the units are the foot and pound. For an earth retaining-wall with $p = 20$, then $M = 1.3h^3$, etc.

* Ry. Rev., Vol. XLV, 1905, p. 523.

DAMS.

194. The dam is a form of retaining-wall, but is subject to somewhat different conditions as to pressures. For this case a form of wall as shown in Fig. 118 is poorly adapted, owing to the fact that the water pressure will probably penetrate beneath the floor DC and exert an upward force nearly equal to the downward pressure, thus destroying the usefulness of the floor EC . To obviate these objections the wall AE must be brought back to the point C . Increased stability will then be secured by making it inclined. In this position it will naturally be supported by transverse walls or buttresses, resting on a floor DC , or directly on the foundation material, as shown in Fig. 119. The water pressure on the floor may then be relieved by




FIG. 118.




FIG. 119.

drain-openings allowing free exit for seepage-water. Thus built it forms a stable and efficient type of dam. Its design as to stresses and sections is simple and obvious. The wall or floor AC may be supported directly on the cross-walls and reinforced with longitudinal rods, or longitudinal beams may be used as shown and the slab supported on these. The pressure on the foundation is determined by considering the resultant of water pressure and weight of dam. The buttresses or cross-walls are subjected only to compressive stresses. Ample longitudinal reinforcement should be provided to thoroughly bind the structure together. Dams are often subjected to dynamic loads as well as static pressures, and sections must be provided more liberally than in many other structures.

The form shown in Fig. 119 is not suited to act as a spillway except for low falls. For a spillway the down-stream edge of the buttresses is also covered with a floor which may be curved in the usual manner.




FIG. 120.—Dam at Schuylerville, N. Y.

Fig. 120 illustrates a dam of this type built at Schuylerville, N. Y., by the Ambursen Hydraulic Construction Co.* A footway is provided for in the interior. The design as to strength is obvious.

* Eng. News, Vol. LIII, p. 448.

CHAPTER X.

MISCELLANEOUS STRUCTURES.

GIRDER BRIDGES AND CULVERTS.

195. For short spans, the girder bridge or box culvert is likely to be a more economical form than the arch, owing to the less rigid requirements for foundations and abutments. For purposes of analysis this type of structure may be divided roughly into three classes: (1) Simple spans in which the girder rests upon independent abutments or piers; (2) concrete trestles or bridges in which the girders, abutments and piers form a monolithic structure; and (3) pipe culverts and box culverts built as square or rectangular pipes.

196. **The Simple Beam Bridge.**—These are designed in the same manner as any other concrete floor. Spans up to 20 to 30 feet may well be made as a simple slab of uniform thickness spanning the opening. For railroad structures the loads are relatively so large that shearing stresses will usually require careful attention. For longer spans a gain in economy will result by the use of main horizontal girders of relatively great depth, with a floor supported by the girders and reinforced transversely. The bridge may be made either a "through" or "deck" girder, according to the requirements of the case, the latter being the more economical. Floors of reinforced concrete are also used for steel truss and girder bridges to a considerable extent where a solid floor is desired. The details are arranged in a variety of ways, but the calculation and design of the reinforcement to meet the given conditions require no special consideration. The proper allowance for impact is an

important point in this connection. Durability is an important factor favorable to the use of reinforced concrete for bridge floors.

197. Concrete Trestles. — Where several short spans are required and concrete is used for both the girders and the piers, the latter may usually be made of comparatively small cross-section, — much smaller than possible if ordinary masonry be used. The structure then approaches the ordinary floor and column construction in the relations of its parts. The piers, if lightly loaded, may consist merely of two or more columns connected by a suitable portal. In some extreme cases designs have been carried out in which the supporting piers or towers have been arranged in a manner similar to a steel trestle, even to the diagonal bracing. It would seem, however, that the treatment of concrete should be on somewhat different lines than is best suited to such a material as steel, and that structural forms in concrete should be somewhat massive and limited in general to the beam and the compression member.

Where the piers are made small, as here assumed, they must be built rigidly in connection with the girders of one or more spans, as are the columns in a building. The girders must be designed with proper reference to their continuity, and the piers must be able to resist a certain amount of bending moment. This moment can be estimated in the manner suggested in Chapter VII, Art. 167.

As an example, let Fig. 121 represent a concrete trestle of monolithic construction. The girders are continuous and the




FIG. 121.

piers are rigidly attached to them. The greatest moment in the pier BF will occur when one of the spans AB or BC is loaded.

Suppose BC be loaded. Then calculate the negative moment at B , assuming BC to be fixed at the ends. This moment will be equal to $-\frac{1}{8} pl^2$, where p = load per foot and l = span length. Now this moment is distributed at the joint B among the three members AB , BF , and BC in proportion to the value of I/l for the three members, the length l being taken as the estimated length to the point of inflection in each case (the full length of BF). This will determine approximately the moment in BF . The *maximum* negative moment in BC and AB will occur when both spans are loaded and will be approximately equal to $\frac{1}{8} pl^2$. (See Chapter VII, Art. 155.) The end piers or abutments must be designed also as retaining walls.

198. Pipe and Box Culverts. — For small openings the monolithic pipe or box form is very advantageous. This form of structure is a complete opening in itself and so long as intact will do good service. Considerable settlement, as a whole, may be permissible, and hence solid foundations may not be needed.

The cross-section may be circular, elliptical or rectangular. Theoretically, the elliptical form is the best as corresponding more nearly to the requirements for resisting the earth pressure. The circular is practically as good for small openings, while for large openings the rectangular form will often be the best on account of its simplicity and the lesser head room required. Where the culvert is manufactured at a shop and transported to the site, the circular or elliptical forms will usually be the most advantageous. As the loads coming upon such structures are not accurately known an exact analysis of the stresses is impossible, but the results obtained for certain simple cases will be useful as a guide to the judgment. The general method of analysis employed in Chapter VIII has been used. The details of the analysis will be omitted.

199. The Circular Culvert. — Two cases have been analyzed; (1) for a uniform load, and (2) for a concentrated load.

Case I; Uniform load. (Fig. 122.) It is assumed that the pressure on the pipe is exerted in parallel lines (as downward and upward) and is uniformly distributed with respect to a plane perpendicular to the direction of the pressure.

Let d = diameter of pipe;

p = pressure per unit area as measured perpendicularly to the pressure;

M = bending moment in pipe in a length of one unit;




FIG. 122.

Then the following equations result.

$$M_a = M_b = \frac{1}{8} pd^2 \quad . \quad . \quad . \quad . \quad . \quad (1)$$

$$M_c = M_d = -\frac{1}{8} pd^2 \quad . \quad . \quad . \quad . \quad . \quad (2)$$

If the lateral pressure, measured in a similar way, be p' per unit area, then the moments due to this pressure will be

$$M_a = M_b = -\frac{1}{8} p'd^2 \quad . \quad . \quad . \quad . \quad . \quad (3)$$

and

$$M_c = M_d = \frac{1}{8} p'd^2 \quad . \quad . \quad . \quad . \quad . \quad (4)$$

For equal horizontal and vertical forces (equivalent to a uniform radial pressure), the moments at all points are zero. Usually the lateral pressure will be much less than the vertical pressure; probably not more than one-fourth or one-fifth as much. Assuming a ratio of one-fourth, the resulting total bending moments at the points a, b, c, d , will be $\frac{3}{8} pd^2$, positive at the top and bottom and negative at the sides.




FIG. 123.

Case II; Concentrated loads at opposite points (Fig. 123).

In this case the moments are

$$M_a = M_b = .16 Pd \quad . \quad . \quad . \quad . \quad . \quad (5)$$

$$M_c = M_d = -.09 Pd \quad . \quad . \quad . \quad . \quad . \quad (6)$$

200. *The Rectangular Culvert.*—Case I; Uniform loads (Fig. 124).

Let l_1 = width of culvert;

l_2 = height of culvert;

I_1 = moment of inertia of top and bottom, assumed as equal;

I_2 = moment of inertia of sides;

p = vertical load and foundation reaction per unit area.

Then

$$M_a = M_b = \frac{pl_1^2}{8} \cdot \frac{\frac{1}{2}l_1/I_1 + l_2/I_2}{l_1/I_1 + l_2/I_2} \quad \dots \quad (7)$$

$$M_c = M_d = M_a - \frac{1}{8} pl_1^2 \quad \dots \quad (8)$$

The moments at e and f are equal to M_c .




FIG. 124.




FIG. 125.

For a square culvert with uniform section $M_a = \frac{1}{12} pl^2$ and $M_c = -\frac{1}{24} pl^2$.

For equal vertical and lateral loads the moments in the square culvert become $M_a = M_c = +\frac{1}{24} pl^2$ and $M_e = -\frac{1}{12} pl^2$ as in a beam with fixed ends.

Case II; Concentrated loads. (Fig. 125.)

For vertical loads applied centrally,

$$M_a = M_b = \frac{Pl_1}{4} \cdot \frac{\frac{1}{2}l_1/I_1 + l_2/I_2}{l_1/I_1 + l_2/I_2} \quad \dots \quad (9)$$

$$M_c = M_d = M_a - \frac{1}{4} Pl_1 \quad \dots \quad (10)$$

For the square form, $M_a = \frac{3}{16} Pl_1$ and $M_c = -\frac{1}{16} Pl_1$; and for equal lateral and vertical forces $M_a = M_c = \frac{1}{8} Pl_1$ and $M_e = -\frac{1}{8} Pl_1$ as for fixed beams.

201. Arrangement of Reinforcement.—The bending moments here determined are based on the assumption that the entire section is reinforced so as to act as a monolithic structure. This of course requires proper reinforcement for negative as well as positive moments.

In the circular form a wire mesh is convenient, especially for small diameters. A single mesh will be sufficient, placed near the intrados at top and bottom and near the extrados at the sides, crossing the central axis at about the quarter point.

In the rectangular form, if reinforcement for negative moments at the corners is omitted, then the four sides will act as simple beams, the concrete cracking more or less on the outside near the corners.

Longitudinal reinforcement should be provided to some extent. Where foundations are good a very small amount will be sufficient, but if settlement is likely to occur the longitudinal reinforcement becomes of much importance. The entire culvert will act as a beam subjected in the main to positive bending moments. Most of the reinforcement should therefore be placed along the bottom of the culvert.

202. Illustrative Examples.—Fig. 126 illustrates a simple beam bridge or "trestle" on the Chicago, Burlington and Quincy R.R.* The girder consists of a slab twenty-four inches in thickness, reinforced as shown in the illustration. The piers are separate structures.

Fig. 127 represents a concrete highway bridge as an overhead crossing of the Big Four R.R. This design illustrates the deep girder with floor-slab reinforced transversely, and also the "trestle" in which the piers are columns built as one piece with the girders.†

* R. R. Gaz., Vol. XL, 1906, p. 713.

† R. R. Gaz. Vol. XL, 1906, p. 497.




FIG. 126.




FIG. 127.

Fig. 128 illustrates a standard design for a monolithic box culvert. It is not reinforced for negative moment at the




FIG. 128.

corners. This form of construction is applicable to many other structures as subways, tunnel linings, etc. No special consideration of these various applications of the reinforced beam is required in this place. A clear understanding of the general principles of reinforced concrete design will enable the details to be suitably modified to meet the conditions of the case.

CONDUITS AND PIPE LINES.

203. For conduits not under pressure, large sewers and the like, reinforced concrete lends itself to convenient and economi-




FIG. 129.

cal construction. As to the analysis and design, these structures are only special cases of the monolithic pipe or box discussed in preceding articles. The character of the foundation

and convenience in construction will lead to various modifications of design.

Fig. 129 is a typical cross-section of a large sewer for Harrisburg, Pa. A mesh of expanded metal is used for reinforcement, arranged to resist positive moments excepting at bottom and corners.

Fig. 130 illustrates a large conduit of the Jersey City Water Supply. This section is employed where the bottom is soft,




FIG 130.

special reinforcement being used in the invert. The position of the reinforcement to carry positive moments at crown and negative moments at sides should be noted.

Reinforced concrete has also been used to some extent for pipes under pressure, but it is very difficult to secure imperviousness under heads of considerable magnitude. In pressure pipes the tensile stress is entirely taken by the steel, the concrete furnishing merely the impervious layer and resisting bending due to earth loading.

TANKS, RESERVOIRS, BINS, ETC.

204. For covered reservoirs reinforced concrete is very well adapted. The rectangular form with flat cover is usually the most convenient; its design involves the same features as build-

ing design with the additional one of imperviousness. Elevated towers and tanks may also be made of concrete, but high pressures are difficult to deal with.

Bins and coal pockets are structures for which concrete is well adapted. For the storage of coal unprotected steel is not durable, but reinforced concrete furnishes an almost ideal material, lending itself readily to the necessary form for strength and furnishing the desired durability.

Tall chimneys constitute also a type of structure for which reinforced concrete is well suited, and several good examples exist of these structures. They are built monolithic, usually in sections of a size that can be completed in one working day. The entire structure is designed as a cantilever beam subjected to bending moments from the wind pressure and direct compression due to its own weight. At any section the stresses would be found as explained for the case of flexure and compression in Chapter V. Vertical reinforcement provides for these stresses, while circumferential reinforcement is provided sufficient in amount to thoroughly bond the structure together. Working stresses similar to those used in other structures may be employed if the work is carefully executed. Foundations are designed as one mass and proportioned with reference to the allowed pressure on the earth under the maximum overturning moment.


Reinforced concrete is advantageously used in other minor forms of structures and structural elements. For further illustrations the reader is referred to the larger works on the subject and especially to the American works of Messrs. Buell and Hill and Mr. Reid.

INDEX.

- Adhesion, 33
 of concrete and reinforcing bars, 33
 tests of, 34
 working values of, 172
- Analysis of arches, 265-282
- Arches,
 advantages of reinforced, 6, 263
 analysis of, 265-282
 deflection of, 274
 examples of, 282
 methods of reinforcing, 264
 stresses in, 266, 281
 temperature stresses in, 272
 unsymmetrical, 274
- Bars,
 forms of, 30
 spacing of, 174
- Beams,
 advantages of reinforced concrete
 for, 5
 applicability of theory of, 131, 169
 compression reinforcement in, 147
 continuous, 237, 240, 250
 depth of, 177
 diagonal tension failures of, 131,
 138
 diagrams for simple, 213-217
 double reinforced, 84
 double reinforcement of, 147
 economical proportions of, 175
 flexure and direct stress in, 90, 204
 formulas for (*see* Formulas)
 methods of failure of, 111
 shear failures of, 131, 138
 shear reinforcement for, 133
 shearing stresses in, 100, 133, 207
 T-beams (*see* T-beams)
 tension failures of, 119
 tests of, 120, 138
 variation of stress in, 43
 web reinforcement in, 133, 173
 working stresses in, 170
- Bins, 312
- Bond, 33
 mechanical, 35
 tests of, 34
- Bond stress, 105, 207
 working values of, 172
- Bridges (*see* Arches and Girders)
- Broken stone, general requirements, 9
- Building construction, 237
 advantages of reinforced concrete
 in, 6
- Cement, general requirements, 9
- Chimneys, advantages of reinforced
 concrete for, 7
- Cinder concrete, properties of, 29
- Coefficient of expansion of
 concrete, 26
 steel, 33
- Columns,
 advantages of reinforced concrete
 for, 5
 details of, 254
 diagram for, 221
 eccentric loads on, 253
 economy of reinforced concrete for,
 188
 examples of design of, 254
 formulas for, 107, 110
 hooped, 110, 159, 191
 notation for, 106, 208
 reinforcement of, 106
 steel for, 189
 tests of plain concrete, 151
 tests of reinforced, 153, 159
 working stresses for, 185
- Concrete,
 cinder, 29
 coefficient of expansion of, 26
 consistency of, 10, 13
 crushing strength of, 11
 in beams, 129
 elastic limit of, 25

- Concrete,
 - elastic properties of, 19
 - elongation of, 37
 - expansion of, 26, 27
 - general requirements, 8
 - modulus of elasticity of, 20, 36
 - proportions of ingredients of, 10
 - temperature stresses in, 40
 - tensile strength of, 15
 - transverse strength of, 16
 - shearing strength of, 17
 - shrinkage of, 27
 - shrinkage stresses in, 40
 - stress-strain curves of, 26
 - variation in, 9
 - weight of, 29
 - working stresses for, 170
- Conduits, 311
 - advantages of reinforced concrete for, 7
- Continuous beams, 237, 240, 250
- Culverts,
 - advantages of reinforced concrete for, 6
 - examples of, 309
 - reinforcement for, 309
 - stresses in, 306
- Dams, 302
 - advantages of reinforced concrete for, 6
- Diagrams for
 - circular slabs, 222, 223
 - columns, 221
 - double reinforcement, 218
 - flexure and direct stress, 219, 220
 - simple beams, 213-217
- Double reinforcement, diagram for, 218
- Double reinforcement of
 - beams, 84, 147
 - T-beams, 84
- Eccentric column loads, 253
- Factor of safety, 166
- Fireproofing, reinforced concrete for, 193
- Flexure and direct stress, 90, 204
 - diagram for, 219, 220
- Floors, 237
 - design of, 244
 - examples of, 254
- Floor-beams,
 - arrangement of, 248
 - continuous, 237
 - loads on, 249
- Floor-slabs,
 - continuity of, 240
 - design of, 244
 - reinforced in two directions, 241
 - shrinkage reinforcement for, 244
 - tables for, 227-236
- Footings, 260
- Formulas for
 - beams, compared, 77
 - beams, double-reinforced, 84, 202
 - beams, Talbot's, 69
 - beams, ultimate loads, 62, 65, 199
 - beams, variety of, 52
 - beams, working loads, 55, 65, 169, 197
 - columns, 107, 110
 - T-beams, 79, 201
- Frictional resistance of bars, 35
- Girders (*see* Beams)
- Girder bridges 304
- Gravel, general requirements, 9
- Historical sketch, 1
- Live load, effect of, 167
- Mechanical bond, 35
- Melan system, 1
- Modulus of elasticity of
 - concrete, 20, 36
 - steel, 32
- Monier system, 1
- Mushroom system, 259
- Notation for
 - beams, 55, 197
 - beams, double-reinforced, 84, 202
 - columns, 107, 208
 - flexure and direct stress, 91, 205
 - T-beams, 79, 201
- Piles, use of reinforced concrete for, 7
- Pipes, 306, 311
- Plates, circular,
 - diagrams for, 222, 223
 - stresses in, 210
- Railroad ties, use of reinforced concrete for, 7
- Ransome system, 2
- Reinforced concrete,
 - advantages of, 4
 - durability of, 191
 - fire resisting qualities of, 193
 - history of, 1
 - repeated load tests of, 164
 - shrinkage stresses in, 40

- Reinforced concrete,
 - temperature stresses in, 40
 - use of, 4
 - working stresses for, 166, 211
- Reservoirs, 312
 - advantages of reinforced concrete for, 6
- Retaining walls,
 - advantages of reinforced concrete for, 6, 289
 - design of, 295
 - examples of, 299
 - fluid pressure on, 290
 - proportions of, 294
 - stability of, 289, 292
 - supported at top, 301
- Rods,
 - spacing of, 174
 - tables for, 224, 225
- Sand,
 - effect of size of grains, 14
 - general requirements, 9
- Shear failure of beams, 131, 138
- Shear reinforcement of beams, 133
- Shearing strength of
 - concrete, 17
 - T-beams, 144
- Shearing stress,
 - effect of, on tensile stress, 102
 - in beams, 100, 133, 207
 - working values of, 173
- Shrinkage of concrete, 27
- Shrinkage stresses, 40
- Spacing of rods or bars, 174
- Steel,
 - coefficient of expansion of, 33
 - corrosion of, in concrete, 191
 - elongation of, 32
 - for columns, 189
 - general requirements, 30
 - modulus of elasticity of, 32
- Steel,
 - quality of, 32, 172
 - tensile strength of, 32
 - working stresses for, 170
- Stirrups, 134
- Stress-strain curves, 26
- Tables for
 - floor-slabs, 227, 236
 - rods, 224, 225
- Tanks, advantages of reinforced concrete for, 7
- T-beams,
 - double reinforced, 84
 - economical proportions for, 184
 - formulas for, 79, 201
 - notation for, 79, 201
 - shearing strength of, 144
 - strength of, 142
 - tests of, 142
- Temperature stresses, 40, 194
 - in arches, 272
- Tests of
 - adhesion, 34
 - beams, 120, 138
 - columns, 151, 153, 159
 - T-beams, 142
- Trestles,
 - analysis of stresses in, 305
 - examples of, 309
- Unit frames, 257
- Walls, 262
- Web reinforcement, 133, 173
- Working stresses, 166, 211
- Working stresses for
 - beams, 170
 - bond, 172
 - columns, 185, 221
 - concrete, 170
 - steel, 170



SHORT-TITLE CATALOGUE

OF THE
PUBLICATIONS

OF
JOHN WILEY & SONS,

NEW YORK.

LONDON: CHAPMAN & HALL, LIMITED.

ARRANGED UNDER SUBJECTS.

Descriptive circulars sent on application. Books marked with an asterisk (*) are sold at *net* prices only. All books are bound in cloth unless otherwise stated.

AGRICULTURE.

Armsby's Manual of Cattle-feeding.	12mo,	\$1 75
Principles of Animal Nutrition.	8vo,	4 00
Budd and Hansen's American Horticultural Manual:		
Part I. Propagation, Culture, and Improvement.	12mo,	1 50
Part II. Systematic Pomology.	12mo,	1 50
Elliott's Engineering for Land Drainage.	12mo,	1 50
Practical Farm Drainage.	12mo,	1 00
Graves's Forest Mensuration.	8vo,	4 00
Green's Principles of American Forestry.	12mo,	1 50
Grotenfelt's Principles of Modern Dairy Practice. (Woll).	12mo,	2 00
Hanausek's Microscopy of Technical Products. (Winton).	8vo,	5 00
Herrick's Denatured or Industrial Alcohol	8vo,	4 00
Maynard's Landscape Gardening as Applied to Home Decoration.	12mo,	1 50
* McKay and Larsen's Principles and Practice of Butter-making	8vo,	1 50
Sanderson's Insects Injurious to Staple Crops.	12mo,	1 50
* Schwarz's Longleaf Pine in Virgin Forest	12mo,	1 25
Stockbridge's Rocks and Soils.	8vo,	2 50
Winton's Microscopy of Vegetable Foods.	8vo,	7 50
Woll's Handbook for Farmers and Dairymen.	16mo,	1 50

ARCHITECTURE.

Baldwin's Steam Heating for Buildings.	12mo,	2 50
Bashore's Sanitation of a Country House.	12mo,	1 00
Berg's Buildings and Structures of American Railroads.	4to,	5 00
Birkmire's Planning and Construction of American Theatres.	8vo,	3 00
Architectural Iron and Steel.	8vo,	3 50
Compound Riveted Girders as Applied in Buildings.	8vo,	2 00
Planning and Construction of High Office Buildings.	8vo,	3 50
Skeleton Construction in Buildings.	8vo,	3 00
Brigg's Modern American School Buildings.	8vo,	4 00
Carpenter's Heating and Ventilating of Buildings.	8vo,	4 00

Freitag's Architectural Engineering.	8vo,	3 50
Fireproofing of Steel Buildings.	8vo,	2 50
French and Ives's Stereotomy.	8vo,	2 50
Gerhard's Guide to Sanitary House-inspection.	16mo,	1 00
Sanitation of Public Buildings.	12mo,	1 50
Theatre Fires and Panics.	12mo,	1 50
*Greene's Structural Mechanics.	8vo,	2 50
Holly's Carpenters' and Joiners' Handbook.	18mo,	75
Johnson's Statics by Algebraic and Graphic Methods.	8vo,	2 00
Kellaway's How to Lay Out Suburban Home Grounds.	8vo,	2 00
Kidder's Architects' and Builders' Pocket-book. Rewritten Edition.	16mo, mor.,	5 00
Merrill's Stones for Building and Decoration.	8vo,	5 00
Non-metallic Minerals: Their Occurrence and Uses.	8vo,	4 00
Monckton's Stair-building.	4to,	4 00
Patton's Practical Treatise on Foundations.	8vo,	5 00
Peabody's Naval Architecture.	8vo,	7 50
Rice's Concrete-block Manufacture.	8vo,	2 00
Richey's Handbook for Superintendents of Construction.	16mo, mor.,	4 00
* Building Mechanics' Ready Reference Book:		
* Carpenters' and Woodworkers' Edition.	16mo, morocco,	1 50
* Cementworkers and Plasterer's Edition. (In Press.)		
* Stone- and Brick-mason's Edition.	12mo, mor.,	1 50
Sabin's Industrial and Artistic Technology of Paints and Varnish.	8vo,	3 00
Siebert and Biggin's Modern Stone-cutting and Masonry.	8vo,	1 50
Snow's Principal Species of Wood.	8vo,	3 50
Sondericker's Graphic Statics with Applications to Trusses, Beams, and Arches.	8vo,	2 00
Towne's Locks and Builders' Hardware.	18mo, morocco,	3 00
Turneure and Maurer's Principles of Reinforced Concrete Construction.	8vo,	3 00
Walt's Engineering and Architectural Jurisprudence.	8vo,	6 00
	Sheep,	6 50
Law of Operations Preliminary to Construction in Engineering and Architecture.	8vo,	5 00
	Sheep,	5 50
Law of Contracts.	8vo,	3 00
Wilson's Air Conditioning, (In Press.)		
Wood's Rustless Coatings: Corrosion and Electrolysis of Iron and Steel.	8vo,	4 00
Worcester and Atkinson's Small Hospitals, Establishment and Maintenance, Suggestions for Hospital Architecture, with Plans for a Small Hospital.	12mo,	1 25
The World's Columbian Exposition of 1893.	Large 4to,	1 00

ARMY AND NAVY.

Bernadou's Smokeless Powder, Nitro-cellulose, and the Theory of the Cellulose Molecule.	12mo,	2 50
Chase's Screw Propellers and Marine Propulsion.	8vo,	3 00
Cloke's Gunner's Examiner.	8vo,	1 50
Craig's Azimuth.	4to,	3 50
Crehore and Squier's Polarizing Photo-chronograph.	8vo,	3 00
* Davis's Elements of Law.	8vo,	2 50
* Treatise on the Military Law of United States.	8vo,	7 00
	Sheep,	7 50
De Brack's Cavalry Outposts Duties. (Carr.).....	24mo, morocco,	2 00
Dietz's Soldier's First Aid Handbook.	16mo, morocco,	1 25
* Dudley's Military Law and the Procedure of Courts-martial.	Large 12mo,	2 50
Durand's Resistance and Propulsion of Ships.	8vo,	5 00

* Dyer's Handbook of Light Artillery.	12mo,	3 00
Eissler's Modern High Explosives.	8vo,	4 00
* Fieheger's Text-book on Field Fortification.	Small 8vo,	2 00
Hamilton's The Gunner's Catechism	18mo,	1 00
* Hoff's Elementary Naval Tactics.	8vo,	1 50
Ingalls's Handbook of Problems in Direct Fire.	8vo,	4 00
* Lissak's Ordnance and Gunnery.	8vo,	6 00
* Lyons's Treatise on Electromagnetic Phenomena. Vols. I. and II.	8vo, each,	6 00
* Mahan's Permanent Fortifications. (Mercur.)	8vo, half morocco,	7 50
Manual for Courts-martial.	16mo, morocco,	1 50
* Mercur's Attack of Fortified Places.	12mo,	2 00
* Elements of the Art of War.	8vo,	4 00
Metcalf's Cost of Manufactures—And the Administration of Workshops.	8vo,	5 00
* Ordnance and Gunnery. 2 vols.	12mo,	5 00
Murray's Infantry Drill Regulations.	18mo, paper,	10
Nixon's Adjutants' Manual.	24mo,	1 00
Peabody's Naval Architecture.	8vo,	7 50
* Phelps's Practical Marine Surveying.	8vo,	2 50
Powell's Army Officer's Examiner.	12mo,	4 00
Sharpe's Art of Subsisting Armies in War.	18mo, morocco,	1 50
* Tupes and Poole's Manual of Bayonet Exercises and Musketry Fencing.	24mo, leather,	50
Weaver's Military Explosives.	8vo,	3 00
Wheeler's Siege Operations and Military Mining.	8vo,	2 00
Winthrop's Abridgment of Military Law.	12mo,	2 50
Woodhull's Notes on Military Hygiene.	16mo,	1 50
Young's Simple Elements of Navigation.	16mo, morocco,	2 00

ASSAYING.

Fletcher's Practical Instructions in Quantitative Assaying with the Blowpipe.	12mo, morocco,	1 50
Furman's Manual of Practical Assaying.	8vo,	3 00
Lodge's Notes on Assaying and Metallurgical Laboratory Experiments.	8vo,	3 00
Low's Technical Methods of Ore Analysis.	8vo,	3 00
Miller's Manual of Assaying.	12mo,	1 00
Cyanide Process.	12mo,	1 00
Minet's Production of Aluminum and its Industrial Use. (Waldo.)	12mo,	2 50
O'Driscoll's Notes on the Treatment of Gold Ores.	8vo,	2 00
Ricketts and Miller's Notes on Assaying.	8vo,	3 00
Robine and Lenglen's Cyanide Industry. (Le Clerc.)	8vo,	4 00
Ulke's Modern Electrolytic Copper Refining.	8vo,	3 00
Wilson's Cyanide Processes.	12mo,	1 50
Chlorination Process.	12mo,	1 50

ASTRONOMY.

Comstock's Field Astronomy for Engineers.	8vo,	2 50
Craig's Azimuth.	4to,	3 50
Crandall's Text-book on Geodesy and Least Squares.	8vo,	3 00
Doolittle's Treatise on Practical Astronomy.	8vo,	4 00
Gore's Elements of Geodesy.	8vo,	2 50
Hayford's Text-book of Geodetic Astronomy.	8vo,	3 00
Merriman's Elements of Precise Surveying and Geodesy.	8vo,	2 50
* Michie and Harlow's Practical Astronomy.	8vo,	3 00
* White's Elements of Theoretical and Descriptive Astronomy.	12mo,	2 00

BOTANY.

Davenport's Statistical Methods, with Special Reference to Biological Variation.	16mo, morocco,	1 25
Thomé and Bennett's Structural and Physiological Botany.....	16mo,	2 25
Westermaier's Compendium of General Botany. (Schneider.).....	8vo,	2 00

CHEMISTRY.

* Abegg's Theory of Electrolytic Dissociation. (Von Ende.).....	12mo,	1 25
Adrian's Laboratory Calculations and Specific Gravity Tables.....	12mo,	1 25
Alexeyeff's General Principles of Organic Synthesis. (Matthews.).....	8vo,	3 00
Allen's Tables for Iron Analysis.	8vo,	3 00
Arnold's Compendium of Chemistry. (Mandel.).....	Small 8vo,	3 50
Austen's Notes for Chemical Students	12mo,	1 50
Beard's Mine Gases and Explosions. (In Press.)		
Bernadou's Smokeless Powder.—Nitro-cellulose, and Theory of the Cellulose Molecule.....	12mo,	2 50
Bolduan's Immune Sera.....	12mo,	1 50
* Browning's Introduction to the Rarer Elements.....	8vo,	1 50
Brush and Penfield's Manual of Determinative Mineralogy.....	8vo,	4 00
* Claassen's Beet-sugar Manufacture. (Hall and Rolfe.).....	8vo,	3 00
Classen's Quantitative Chemical Analysis by Electrolysis. (Boltwood.).....	8vo,	3 00
Cohn's Indicators and Test-papers.....	12mo,	2 00
Tests and Reagents.....	8vo,	3 00
Crafts's Short Course in Qualitative Chemical Analysis. (Schaeffer.).....	12mo,	1 50
* Danneel's Electrochemistry. (Merriam.).....	12mo,	1 25
Dolezalek's Theory of the Lead Accumulator (Storage Battery). (Von Ende.).....	12mo,	2 50
Drechsel's Chemical Reactions. (Merrill.).....	12mo,	1 25
Duhem's Thermodynamics and Chemistry. (Burgess.).....	8vo,	4 00
Eissler's Modern High Explosives.....	8vo,	4 00
Effront's Enzymes and their Applications. (Prescott.).....	8vo,	3 00
Erdmann's Introduction to Chemical Preparations. (Dunlap.).....	12mo,	1 25
* Fischer's Physiology of Alimentation.....	Large 12mo,	2 00
Fletcher's Practical Instructions in Quantitative Assaying with the Blowpipe.		
	12mo, morocco,	1 50
Fowler's Sewage Works Analyses.....	12mo,	2 00
Fresenius's Manual of Qualitative Chemical Analysis. (Wells.).....	8vo,	5 00
Manual of Qualitative Chemical Analysis. Part I. Descriptive. (Wells.)	8vo,	3 00
Quantitative Chemical Analysis. (Cohn.) 2 vols.....	8vo,	12 50
Fuertes's Water and Public Health.....	12mo,	1 50
Furman's Manual of Practical Assaying.....	8vo,	3 00
* Getman's Exercises in Physical Chemistry.....	12mo,	2 00
Gill's Gas and Fuel Analysis for Engineers.....	12mo,	1 25
* Gooch and Browning's Outlines of Qualitative Chemical Analysis. Small	8vo,	1 25
Grotenfelt's Principles of Modern Dairy Practice. (Woll.).....	12mo,	2 00
Groth's Introduction to Chemical Crystallography (Marshall).....	12mo,	1 25
Hammarsten's Text-book of Physiological Chemistry. (Mandel.).....	8vo,	4 00
Hanausek's Microscopy of Technical Products. (Winton.).....	8vo,	5 00
* Haskin's and MacLeod's Organic Chemistry.....	12mo,	2 00
Helm's Principles of Mathematical Chemistry. (Morgan.).....	12mo,	1 50
Hering's Ready Reference Tables (Conversion Factors).....	16mo, morocco,	2 50
Herrick's Denatured or Industrial Alcohol.....	8vo,	4 00
Hind's Inorganic Chemistry.....	8vo,	3 00
* Laboratory Manual for Students.....	12mo,	1 00
Holleman's Text-book of Inorganic Chemistry. (Cooper.).....	8vo,	2 50
Text-book of Organic Chemistry. (Walker and Mott).....	8vo,	2 50
* Laboratory Manual of Organic Chemistry. (Walker.).....	12mo,	1 00

Holley and Ladd's Analysis of Mixed Paints, Color Pigments, and Varishes. (In Press)		
Hopkins's Oil-chemists' Handbook.....	8vo,	3 00
Iddings's Rock Minerals.....	8vo,	5 00
Jackson's Directions for Laboratory Work in Physiological Chemistry.....	8vo,	1 25
Johannsen's Key for the Determination of Rock-forming Minerals in Thin Sections. (In Press)		
Keep's Cast Iron.....	8vo,	2 50
Ladd's Manual of Quantitative Chemical Analysis.....	12mo,	1 00
Landauer's Spectrum Analysis. (Tingle.).....	8vo,	3 00
* Langworthy and Austen. The Occurrence of Aluminium in Vegetable Products, Animal Products, and Natural Waters.....	8vo,	2 00
Lassar-Cohn's Application of Some General Reactions to Investigations in Organic Chemistry. (Tingle.).....	12mo,	1 00
Leach's The Inspection and Analysis of Food with Special Reference to State Control.....	8vo,	7 50
Löb's Electrochemistry of Organic Compounds. (Lorenz.).....	8vo,	3 00
Lodge's Notes on Assaying and Metallurgical Laboratory Experiments.....	8vo,	3 00
Low's Technical Method of Ore Analysis.....	8vo,	3 00
Lunge's Techno-chemical Analysis. (Cohn.).....	12mo	1 00
* McKay and Larsen's Principles and Practice of Butter-making.....	8vo,	1 50
Maire's Modern Pigments and their Vehicles. (In Press.)		
Mandel's Handbook for Bio-chemical Laboratory.....	12mo,	1 50
* Martin's Laboratory Guide to Qualitative Analysis with the Blowpipe.....	12mo,	60
Mason's Water-supply. (Considered Principally from a Sanitary Standpoint.) 3d Edition, Rewritten.....	8vo,	4 00
Examination of Water. (Chemical and Bacteriological.).....	12mo,	1 25
Matthew's The Textile Fibres. 2d Edition, Rewritten.....	8vo,	4 00
Meyer's Determination of Radicles in Carbon Compounds. (Tingle.).....	12mo,	1 00
Miller's Manual of Assaying.....	12mo,	1 00
Cyanide Process.....	12mo,	1 00
Minet's Production of Aluminum and its Industrial Use. (Waldo.).....	12mo,	2 50
Mixter's Elementary Text-book of Chemistry.....	12mo,	1 50
Morgan's An Outline of the Theory of Solutions and its Results.....	12mo,	1 00
Elements of Physical Chemistry.....	12mo,	3 00
* Physical Chemistry for Electrical Engineers.....	12mo,	5 00
Morse's Calculations used in Cane-sugar Factories.....	16mo, morocco,	1 50
* Muir's History of Chemical Theories and Laws.....	8vo,	4 00
Mulliken's General Method for the Identification of Pure Organic Compounds. Vol. I.....	Large 8vo,	5 00
O'Driscoll's Notes on the Treatment of Gold Ores.....	8vo,	2 00
Ostwald's Conversations on Chemistry. Part One. (Ramsey.).....	12mo,	1 50
" " " " Part Two. (Turnbull.).....	12mo,	1 50
* Palmer's Practical Test Book of Chemistry.....	12mo,	1 00
* Pauli's Physical Chemistry in the Service of Medicine. (Fischer.).....	12mo,	1 25
* Penfield's Notes on Determinative Mineralogy and Record of Mineral Tests. 8vo, paper,		50
Pictet's The Alkaloids and their Chemical Constitution. (Biddle.).....	8vo,	5 00
Pinner's Introduction to Organic Chemistry. (Austen.).....	12mo,	1 50
Poole's Calorific Power of Fuels.....	8vo,	3 00
Prescott and Winslow's Elements of Water Bacteriology, with Special Reference to Sanitary Water Analysis.....	12mo,	1 25
* Reisig's Guide to Piece-dyeing.....	8vo,	25 00
Richards and Woodman's Air, Water, and Food from a Sanitary Standpoint.....	8vo,	2 00
Ricketts and Miller's Notes on Assaying.....	8vo,	3 00
Rideal's Sewage and the Bacterial Purification of Sewage.....	8vo,	4 00
Disinfection and the Preservation of Food.....	8vo,	4 00
Riggs's Elementary Manual for the Chemical Laboratory.....	8vo,	1 25
Robine and Lenglen's Cyanide Industry. (Le Clerc.).....	8vo,	4 00

Ruddiman's Incompatibilities in Prescriptions.	8vo,	2 00
* Whys in Pharmacy	12mo,	1 00
Sabin's Industrial and Artistic Technology of Paints and Varnish.	8vo,	3 00
Salkowski's Physiological and Pathological Chemistry. (Orndorff.)	8vo,	2 50
Schimpf's Text-book of Volumetric Analysis.	12mo,	2 50
Essentials of Volumetric Analysis.	12mo,	1 25
* Qualitative Chemical Analysis.	8vo,	1 25
Smith's Lecture Notes on Chemistry for Dental Students. ...	8vo,	2 50
Spencer's Handbook for Chemists of Beet-sugar Houses.	16mo, morocco,	3 00
Handbook for Cane Sugar Manufacturers.	16mo, morocco,	3 00
Stockbridge's Rocks and Soils.	8vo,	2 50
* Tillman's Elementary Lessons in Heat.	8vo,	1 50
* Descriptive General Chemistry.	8vo,	3 00
Treadwell's Qualitative Analysis. (Hall.)	8vo,	3 00
Quantitative Analysis. (Hall.)	8vo,	4 00
Turneure and Russell's Public Water-supplies.	8vo,	5 00
Van Deventer's Physical Chemistry for Beginners. (Boltwood.)	12mo,	1 50
* Walke's Lectures on Explosives.	8vo,	4 00
Ware's Beet-sugar Manufacture and Refining. Vol. I.	Small 8vo,	4 00
" " " " " " Vol. II.	Small 8vo,	5 00
Washington's Manual of the Chemical Analysis of Rocks.	8vo,	2 00
Weaver's Military Explosives.	8vo,	3 00
Wehrenfennig's Analysis and Softening of Boiler Feed-Water.	8vo,	4 00
Wells's Laboratory Guide in Qualitative Chemical Analysis.	8vo,	1 50
Short Course in Inorganic Qualitative Chemical Analysis for Engineering Students.	12mo,	1 50
Text-book of Chemical Arithmetic.	12mo,	1 25
Whipple's Microscopy of Drinking-water.	8vo,	3 50
Wilson's Cyanide Processes.	12mo,	1 50
Chlorination Process.	12mo,	1 50
Winton's Microscopy of Vegetable Foods.	8vo,	7 50
Wulling's Elementary Course in Inorganic, Pharmaceutical, and Medical Chemistry.	12mo,	2 00

CIVIL ENGINEERING.

BRIDGES AND ROOFS. HYDRAULICS. MATERIALS OF ENGINEERING RAILWAY ENGINEERING.

Baker's Engineers' Surveying Instruments.	12mo,	3 00
Bixby's Graphical Computing Table. Paper 19 $\frac{1}{2}$ X 24 $\frac{1}{2}$ inches.		25
Breed and Hosmer's Principles and Practice of Surveying.	8vo,	3 00
* Burr's Ancient and Modern Engineering and the Isthmian Canal.	8vo,	3 50
Comstock's Field Astronomy for Engineers.	8vo,	2 50
* Corthell's Allowable Pressures on Deep Foundations.	12mo,	1 25
Crandall's Text-book on Geodesy and Least Squares.	8vo,	3 00
Davis's Elevation and Stadia Tables.	8vo,	1 00
Elliott's Engineering for Land Drainage.	12mo,	1 50
Practical Farm Drainage.	12mo,	1 00
* Fieheger's Treatise on Civil Engineering.	8vo,	5 00
Flemer's Phototopographic Methods and Instruments.	8vo,	5 00
Folwell's Sewerage. (Designing and Maintenance.)	8vo,	3 00
Freitag's Architectural Engineering. 2d Edition, Rewritten.	8vo,	3 50
French and Ives's Stereotomy.	8vo,	2 50
Goodhue's Municipal Improvements.	12mo,	1 50
Gore's Elements of Geodesy.	8vo,	2 50
* Hauch and Rice's Tables of Quantities for Preliminary Estimates.	12mo,	1 25
Hayford's Text-book of Geodetic Astronomy.	8vo,	3 00

Hering's Ready Reference Tables (Conversion Factors).	16mo, morocco,	2 50
Howe's Retaining Walls for Earth.	12mo,	1 25
Hoyt and Grover's River Discharge.	8vo,	2 00
* Ives's Adjustments of the Engineer's Transit and Level.	16mo, Bds.	25
Ives and Hilt's Problems in Surveying.	16mo, morocco,	1 50
Johnson's (J. B.) Theory and Practice of Surveying.	Small 8vo,	4 00
Johnson's (L. J.) Statics by Algebraic and Graphic Methods.	8vo,	2 00
Laplace's Philosophical Essay on Probabilities. (Truscott and Emory.)	12mo,	2 00
Mahan's Treatise on Civil Engineering. (1873.) (Wood.)	8vo,	5 00
* Descriptive Geometry.	8vo,	1 50
Merriman's Elements of Precise Surveying and Geodesy.	8vo,	2 50
Merriman and Brooks's Handbook for Surveyors.	16mo, morocco,	2 00
Nugent's Plane Surveying.	8vo,	3 50
Ogden's Sewer Design.	12mo,	2 00
Parsons's Disposal of Municipal Refuse.	8vo,	2 00
Patton's Treatise on Civil Engineering.	8vo half leather,	7 50
Reed's Topographical Drawing and Sketching.	4to,	5 00
Rideal's Sewage and the Bacterial Purification of Sewage.	8vo,	4 00
Riemer's Shaft-sinking under Difficult Conditions. (Corning and Peele.)	8vo,	3 00
Siebert and Biggin's Modern Stone-cutting and Masonry.	8vo,	1 50
Smith's Manual of Topographical Drawing. (McMillan.)	8vo,	2 50
Sondericker's Graphic Statics, with Applications to Trusses, Beams, and Arches.	8vo,	2 00
Taylor and Thompson's Treatise on Concrete, Plain and Reinforced.	8vo,	5 00
Tracy's Plane Surveying.	16mo, morocco,	3 00
* Trautwine's Civil Engineer's Pocket-book.	16mo, morocco,	5 00
Venable's Garbage Crematories in America.	8vo,	2 00
Wait's Engineering and Architectural Jurisprudence.	8vo,	6 00
Law of Operations Preliminary to Construction in Engineering and Archi- tecture.	Sheep,	6 50
Law of Contracts.	8vo,	5 00
Warren's Stereotomy—Problems in Stone-cutting.	8vo,	2 50
Webb's Problems in the Use and Adjustment of Engineering Instruments.	16mo, morocco,	1 25
Wilson's Topographic Surveying.	8vo,	3 50

BRIDGES AND ROOFS.

Boller's Practical Treatise on the Construction of Iron Highway Bridges.	8vo,	2 00
Burr and Falk's Influence Lines for Bridge and Roof Computations.	8vo,	3 00
Design and Construction of Metallic Bridges.	8vo,	5 00
Du Bois's Mechanics of Engineering. Vol. II.	Small 4to,	10 00
Foster's Treatise on Wooden Trestle Bridges.	4to,	5 00
Fowler's Ordinary Foundations.	8vo,	3 50
Greene's Roof Trusses.	8vo,	1 25
Bridge Trusses.	8vo,	2 50
Arches in Wood, Iron, and Stone.	8vo,	2 50
Grimm's Secondary Stresses in Bridge Trusses. (In Press.)		
Howe's Treatise on Arches.	8vo,	4 00
Design of Simple Roof-trusses in Wood and Steel.	8vo,	2 00
Symmetrical Masonry Arches.	8vo,	2 50
Johnson, Bryan, and Turneure's Theory and Practice in the Designing of Modern Framed Structures.	Small 4to,	10 00
Merriman and Jacoby's Text-book on Roofs and Bridges:		
Part I. Stresses in Simple Trusses.	8vo,	2 50
Part II. Graphic Statics.	8vo,	2 50
Part III. Bridge Design.	8vo,	2 50
Part IV. Higher Structures.	8vo,	2 50

Morison's Memphis Bridge.	4to,	10 00
Waddell's De Pontibus, a Pocket-book for Bridge Engineers. .	16mo, morocco,	2 00
* Specifications for Steel Bridges.	12mo.	50
Wright's Designing of Draw-spans. Two parts in one volume.	8vo,	3 50

HYDRAULICS.

Barnes's Ice Formation.	8vo,	3 00
Bazin's Experiments upon the Contraction of the Liquid Vein Issuing from an Orifice. (Trautwine.).	8vo,	2 00
Bovey's Treatise on Hydraulics.	8vo,	5 00
Church's Mechanics of Engineering.	8vo,	6 00
Diagrams of Mean Velocity of Water in Open Channels.	paper,	1 50
Hydraulic Motors.	8vo,	2 00
Coffin's Graphical Solution of Hydraulic Problems.	16mo, morocco,	2 50
Flather's Dynamometers, and the Measurement of Power.	12mo,	3 00
Folwell's Water-supply Engineering.	8vo,	4 00
Frizell's Water-power.	8vo,	5 00
Fuertes's Water and Public Health.	12mo,	1 50
Water-filtration Works.	12mo,	2 50
Ganguillet and Kutter's General Formula for the Uniform Flow of Water in Rivers and Other Channels. (Hering and Trautwine.).	8vo,	4 00
Hazen's Clean Water and How to Get It.	Large 12mo,	1 50
Filtration of Public Water-supply.	8vo,	3 00
Hazlehurst's Towers and Tanks for Water-works.	8vo,	2 50
Herschel's 115 Experiments on the Carrying Capacity of Large, Riveted, Metal Conduits.	8vo,	2 00
* Hubbard and Klersted's Water-works Management and Maintenance. .	8vo,	4 00
Mason's Water-supply. (Considered Principally from a Sanitary Standpoint.)	8vo,	4 00
Merriman's Treatise on Hydraulics.	8vo,	5 00
* Michle's Elements of Analytical Mechanics.	8vo,	4 00
Schuyler's Reservoirs for Irrigation, Water-power, and Domestic Water-supply.	Large 8vo,	5 00
* Thomas and Watt's Improvement of Rivers.	4to,	6 00
Turneure and Russell's Public Water-supplies.	8vo,	5 00
Wegmann's Design and Construction of Dams. 5th Edition, enlarged. .	4to,	6 00
Water-supply of the City of New York from 1658 to 1895.	4to,	10 00
Whipple's Value of Pure Water.	Large 12mo,	1 00
Williams and Hazen's Hydraulic Tables.	8vo,	1 50
Wilson's Irrigation Engineering.	Small 8vo,	4 00
Wolf's Windmill as a Prime Mover.	8vo,	3 00
Wood's Turbines.	8vo,	2 50
Elements of Analytical Mechanics.	8vo,	3 00

MATERIALS OF ENGINEERING.

Baker's Treatise on Masonry Construction.	8vo,	5 00
Roads and Pavements.	8vo,	5 00
Black's United States Public Works.	Oblong 4to,	5 00
* Bovey's Strength of Materials and Theory of Structures.	8vo,	7 50
Burr's Elasticity and Resistance of the Materials of Engineering.	8vo,	7 50
Byrne's Highway Construction.	8vo,	5 00
Inspection of the Materials and Workmanship Employed in Construction.	16mo,	3 00
Church's Mechanics of Engineering.	8vo,	6 00
Du Bois's Mechanics of Engineering. Vol. I.	Small 4to,	7 50
*Eckel's Cements, Limes, and Plasters.	8vo,	6 00

Johnson's Materials of Construction.	Large 8vo,	6 00
Fowler's Ordinary Foundations.	8vo,	3 50
Graves's Forest Mensuration.	8vo,	4 00
* Greene's Structural Mechanics.	8vo,	2 50
Keep's Cast Iron.	8vo,	2 50
Lanza's Applied Mechanics.	8vo,	7 50
Martens's Handbook on Testing Materials. (Henning.) 2 vols.	8vo,	7 50
Maurer's Technical Mechanics.	8vo,	4 00
Merrill's Stones for Building and Decoration.	8vo,	5 00
Merriman's Mechanics of Materials.	8vo,	5 00
* Strength of Materials	12mo,	1 00
Metcalfe's Steel. A Manual for Steel-users.	12mo,	2 00
Patton's Practical Treatise on Foundations.	8vo,	5 00
Richardson's Modern Asphalt Pavements.	8vo,	3 00
Richey's Handbook for Superintendents of Construction.	16mo, mcr.,	4 00
* Ries's Clays: Their Occurrence, Properties, and Uses.	8vo,	5 00
Rockwell's Roads and Pavements in France.	12mo,	1 25
Sabin's Industrial and Artistic Technology of Paints and Varnish.	8vo,	3 00
* Schwarz's Longleaf Pine in Virgin Forest.	12mo,	1 25
Smith's Materials of Machines.	12mo,	1 00
Snow's Principal Species of Wood.	8vo,	3 50
Spalding's Hydraulic Cement.	12mo,	2 00
Text-book on Roads and Pavements.	12mo,	2 00
Taylor and Thompson's Treatise on Concrete, Plain and Reinforced.	8vo,	5 00
Thurston's Materials of Engineering. 3 Parts.	8vo,	8 00
Part I. Non-metallic Materials of Engineering and Metallurgy.	8vo,	2 00
Part II. Iron and Steel.	8vo,	3 50
Part III. A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents.	8vo,	2 50
Tillson's Street Pavements and Paving Materials.	8vo,	4 00
Turneure and Maurer's Principles of Reinforced Concrete Construction.	8vo,	3 00
Waddell's De Pontibus. (A Pocket-book for Bridge Engineers.)	16mo, mor.,	2 00
* Specifications for Steel Bridges.	12mo,	50
Wood's (De V.) Treatise on the Resistance of Materials, and an Appendix on the Preservation of Timber.	8vo,	2 00
Wood's (De V.) Elements of Analytical Mechanics.	8vo,	3 00
Wood's (M. P.) Rustless Coatings: Corrosion and Electrolysis of Iron and Steel.	8vo,	4 00

RAILWAY ENGINEERING.

Andrew's Handbook for Street Railway Engineers.	3x5 inches, morocco,	1 25
Berg's Buildings and Structures of American Railroads	4to,	5 00
Brook's Handbook of Street Railroad Location.	16mo, morocco,	1 50
Butt's Civil Engineer's Field-book.	16mo, morocco,	2 50
Crandall's Transition Curve.	16mo, morocco,	1 50
Railway and Other Earthwork Tables.	8vo,	1 50
Crookett's Methods for Earthwork Computations. (In Press)		
Dawson's "Engineering" and Electric Traction Pocket-book.	16mo, morocco,	5 00
Dredge's History of the Pennsylvania Railroad: (1879).	Paper,	5 00
Fisher's Table of Cubic Yards.	Cardboard,	25
Godwin's Railroad Engineers' Field-book and Explorers' Guide.	16mo, mor.,	2 50
Hudson's Tables for Calculating the Cubic Contents of Excavations and Em- bankments.	8vo,	1 00
Molitor and Beard's Manual for Resident Engineers.	16mo,	1 00
Nagle's Field Manual for Railroad Engineers.	16mo, morocco,	3 00
Philbrick's Field Manual for Engineers.	16mo, morocco,	3 00
Raymond's Elements of Railroad Engineering. (In Press.)		

Searles's Field Engineering.	16mo. morocco,	3 00
Railroad Spiral.	16mo, morocco,	1 50
Taylor's Prismoidal Formulæ and Earthwork.	8vo,	1 50
* Trautwine's Method of Calculating the Cube Contents of Excavations and Embankments by the Aid of Diagrams,	8vo,	2 00
The Field Practice of Laying Out Circular Curves for Railroads.	12mo, morocco,	2 50
Cross-section Sheet.	Paper,	25
Webb's Railroad Construction.	16mo, morocco,	5 00
Economics of Railroad Construction.	Large 12mo,	2 50
Wellington's Economic Theory of the Location of Railways.	Small 8vo,	5 00

DRAWING.

Barr's Kinematics of Machinery.	8vo,	2 50
* Bartlett's Mechanical Drawing.	8vo,	3 00
* " " Abridged Ed.	8vo,	1 50
Coolidge's Manual of Drawing.	8vo, paper,	1 00
Coolidge and Freeman's Elements of General Drafting for Mechanical Engi- neers.	Oblong 4to,	2 50
Durley's Kinematics of Machines.	8vo,	4 00
Emch's Introduction to Projective Geometry and its Applications.	8vo,	2 50
Hill's Text-book on Shades and Shadows, and Perspective.	8vo,	2 00
Jamison's Elements of Mechanical Drawing.	8vo,	2 50
Advanced Mechanical Drawing.	8vo,	2 00
Jones's Machine Design:		
Part I. Kinematics of Machinery.	8vo,	1 50
Part II. Form, Strength, and Proportions of Parts.	8vo,	3 00
MacCord's Elements of Descriptive Geometry.	8vo,	3 00
Kinematics; or, Practical Mechanism.	8vo,	5 00
Mechanical Drawing.	4to,	4 00
Velocity Diagrams.	8vo,	1 50
MacLeod's Descriptive Geometry.	Small 8vo,	1 50
* Mahan's Descriptive Geometry and Stone-cutting.	8vo,	1 50
Industrial Drawing. (Thompson.).	8vo,	3 50
Moyer's Descriptive Geometry.	8vo,	2 00
Reed's Topographical Drawing and Sketching.	4to,	5 00
Reid's Course in Mechanical Drawing.	8vo,	2 00
Text-book of Mechanical Drawing and Elementary Machine Design.	8vo,	3 00
Robinson's Principles of Mechanism.	8vo,	3 00
Schwamb and Merrill's Elements of Mechanism.	8vo,	3 00
Smith's (R. S.) Manual of Topographical Drawing. (McMillan.).	8vo,	2 50
Smith (A. W.) and Marx's Machine Design.	8vo,	3 00
* Tittsworth's Elements of Mechanical Drawing.	Oblong 8vo,	1 25
Warren's Elements of Plane and Solid Free-hand Geometrical Drawing.	12mo,	1 00
Drafting Instruments and Operations.	12mo,	1 25
Manual of Elementary Projection Drawing.	12mo,	1 50
Manual of Elementary Problems in the Linear Perspective of Form and Shadow.	12mo,	1 00
Plane Problems in Elementary Geometry.	12mo,	1 25
Elements of Descriptive Geometry, Shadows, and Perspective.	8vo,	3 50
General Problems of Shades and Shadows.	8vo,	3 00
Elements of Machine Construction and Drawing.	8vo,	7 50
Problems, Theorems, and Examples in Descriptive Geometry.	8vo,	2 50
Weisbach's Kinematics and Power of Transmission. (Hermann and Klein.).	8vo,	5 00
Whelpley's Practical Instruction in the Art of Letter Engraving.	12mo,	2 00
Wilson's (H. M.) Topographic Surveying.	8vo,	3 50

Wilson's (V. T.) Free-hand Perspective.	8vo,	2 50
Wilson's (V. T.) Free-hand Lettering.	8vo,	1 00
Woolf's Elementary Course in Descriptive Geometry.	Large 8vo,	3 00

ELECTRICITY AND PHYSICS.

* Abegg's Theory of Electrolytic Dissociation. (Von Ende.)	12mo,	1 25
Anthony and Brackett's Text-book of Physics. (Magie.)	Small 8vo,	3 00
Anthony's Lecture-notes on the Theory of Electrical Measurements.	12mo,	1 00
Benjamin's History of Electricity.	8vo,	3 00
Voltaic Cell.	8vo,	3 00
Betts's Lead Refining and Electrolysis. (In Press.)		
Classen's Quantitative Chemical Analysis by Electrolysis. (Boltwood.)	8vo,	3 00
* Collins's Manual of Wireless Telegraphy.	12mo,	1 50
	Morocco,	2 00
Crehore and Squier's Polarizing Photo-chronograph.	8vo,	3 00
* Danneel's Electrochemistry. (Merriam.)	12mo,	1 25
Dawson's "Engineering" and Electric Traction Pocket-book.	16mo, morocco,	5 00
Dolezalek's Theory of the Lead Accumulator (Storage Battery). (Von Ende.)		
	12mo,	2 50
Duhem's Thermodynamics and Chemistry. (Burgess.)	8vo,	4 00
Flather's Dynamometers, and the Measurement of Power.	12mo,	3 00
Gilbert's De Magnete. (Mottelay.)	8vo,	2 50
Hanchett's Alternating Currents Explained.	12mo,	1 00
Hering's Ready Reference Tables (Conversion Factors).	16mo, morocco,	2 50
Hobart and Ellis's High-speed Dynamo Electric Machinery. (In Press.)		
Holman's Precision of Measurements.	8vo,	2 00
Telescopic Mirror-scale Method, Adjustments, and Tests.	Large 8vo,	75
Karapetoff's Experimental Electrical Engineering. (In Press.)		
Kinzbrunner's Testing of Continuous-current Machines.	8vo,	2 00
Landauer's Spectrum Analysis. (Tingle.)	8vo,	3 00
Le Chatelier's High-temperature Measurements. (Boudouard—Burgess.)	12mo,	3 00
Löb's Electrochemistry of Organic Compounds. (Lorenz.)	8vo,	3 00
* Lyons's Treatise on Electromagnetic Phenomena. Vols. I. and II.	8vo, each,	6 00
* Michie's Elements of Wave Motion Relating to Sound and Light.	8vo,	4 00
Niaudet's Elementary Treatise on Electric Batteries. (Fishback.)	12mo,	2 50
Norris's Introduction to the Study of Electrical Engineering. (In Press.)		
* Parshall and Hobart's Electric Machine Design.	4to, half morocco,	12 50
Reagan's Locomotives: Simple, Compound, and Electric. New Edition.		
	Large 12mo,	3 50
* Rosenberg's Electrical Engineering. (Haldane Gee—Kinzbrunner.)	8vo,	2 00
Ryan, Norris, and Hoxie's Electrical Machinery. Vol. I.	8vo,	2 50
Thurston's Stationary Steam-engines.	8vo,	2 50
* Tillman's Elementary Lessons in Heat.	8vo,	1 50
Tory and Pitcher's Manual of Laboratory Physics.	Small 8vo,	2 00
Ulke's Modern Electrolytic Copper Refining.	8vo,	3 00

LAW.

* Davis's Elements of Law.	8vo,	2 50
* Treatise on the Military Law of United States.	8vo,	7 00
	Sheep,	7 50
* Dudley's Military Law and the Procedure of Courts-martial.	Large 12mo,	2 50
Manual for Courts-martial.	16mo, morocco,	1 50
Wait's Engineering and Architectural Jurisprudence.	8vo,	6 00
	Sheep,	6 50
Law of Operations Preliminary to Construction in Engineering and Architecture.	8vo,	5 00
	Sheep,	5 50
Law of Contracts.	8vo,	3 00
Winthrop's Abridgment of Military Law.	12mo,	2 50

MANUFACTURES.

Bernadou's Smokeless Powder—Nitro-cellulose and Theory of the Cellulose Molecule	12mo,	2 50
Bolland's Iron Founder	12mo,	2 50
The Iron Founder," Supplement	12mo,	2 50
Encyclopedia of Founding and Dictionary of Foundry Terms Used in the Practice of Moulding	12mo,	3 00
* Claassen's Beet-sugar Manufacture. (Hall and Rolfe.)	8vo,	3 00
* Eckel's Cements, Limes, and Plasters	8vo,	6 00
Eissler's Modern High Explosives	8vo,	4 00
Effront's Enzymes and their Applications. (Prescott.)	8vo,	3 00
Fitzgerald's Boston Machinist	12mo,	1 00
Ford's Boiler Making for Boiler Makers	18mo,	1 00
Herrick's Denatured or Industrial Alcohol	8vo,	4 00
Holley and Ladd's Analysis of Mixed Paints, Color Pigments, and Varnishes. (In Press.)		
Hopkins's Oil-chemists' Handbook	8vo,	3 00
Keep's Cast Iron	8vo,	2 50
Leach's The Inspection and Analysis of Food with Special Reference to State Control	Large 8vo,	7 50
* McKay and Larsen's Principles and Practice of Butter-making	8vo,	1 50
Maire's Modern Pigments and their Vehicles. (In Press.)		
Matthews's The Textile Fibres. 2d Edition, Rewritten	8vo,	4 00
Metcalf's Steel. A Manual for Steel-users	12mo,	2 00
Metcalf's Cost of Manufactures—And the Administration of Workshops	8vo,	5 00
Meyer's Modern Locomotive Construction	4to,	10 00
Morse's Calculations used in Cane-sugar Factories	16mo, morocco,	1 50
* Reising's Guide to Piece-dyeing	8vo,	25 00
Rice's Concrete-block Manufacture	8vo,	2 00
Sabin's Industrial and Artistic Technology of Paints and Varnish	8vo,	3 00
Smith's Press-working of Metals	8vo,	3 00
Spalding's Hydraulic Cement	12mo,	2 00
Spencer's Handbook for Chemists of Beet-sugar Houses	16mo, morocco,	3 00
Handbook for Cane Sugar Manufacturers	16mo, morocco,	3 00
Taylor and Thompson's Treatise on Concrete, Plain and Reinforced	8vo,	5 00
Thurston's Manual of Steam-boilers, their Designs, Construction and Operation	8vo,	5 00
Ware's Beet-sugar Manufacture and Refining. Vol. I	Small 8vo,	4 00
" " " " " Vol. II	8vo,	5 00
Weaver's Military Explosives	8vo,	3 00
West's American Foundry Practice	12mo,	2 50
Moulder's Text-book	12mo,	2 50
Wolff's Windmill as a Prime Mover	8vo,	3 00
Wood's Rustless Coatings: Corrosion and Electrolysis of Iron and Steel. 8vo.		4 00

MATHEMATICS.

Baker's Elliptic Functions	8vo,	1 50
Briggs's Elements of Plane Analytic Geometry	12mo,	1 00
Buchanan's Plane and Spherical Trigonometry. (In Press.)		
Compton's Manual of Logarithmic Computations	12mo,	1 50
Davis's Introduction to the Logic of Algebra	8vo,	1 50
* Dickson's College Algebra	Large 12mo,	1 50
* Introduction to the Theory of Algebraic Equations	Large 12mo,	1 25
Emch's Introduction to Projective Geometry and its Applications	8vo,	2 50
Halsted's Elements of Geometry	8vo,	1 75
Elementary Synthetic Geometry	8vo,	1 50
* Rational Geometry	12mo,	1 50

* Johnson's (J. B.) Three-place Logarithmic Tables: Vest-pocket size paper,	15
	100 copies for 5 00
* Mounted on heavy cardboard, 8×10 inches,	25
	10 copies for 2 00
Johnson's (W. W.) Elementary Treatise on Differential Calculus. Small 8vo,	3 00
Elementary Treatise on the Integral Calculus Small 8vo,	1 50
Johnson's (W. W.) Curve Tracing in Cartesian Co-ordinates 12mo,	1 00
Johnson's (W. W.) Treatise on Ordinary and Partial Differential Equations.	
	Small 8vo, 3 50
Johnson's Treatise on the Integral Calculus Small 8vo,	3 00
Johnson's (W. W.) Theory of Errors and the Method of Least Squares. 12mo,	1 50
* Johnson's (W. W.) Theoretical Mechanics 12mo,	3 00
Laplace's Philosophical Essay on Probabilities. (Truscott and Emory.) 12mo,	2 00
* Ludlow and Bass. Elements of Trigonometry and Logarithmic and Other	
Tables 8vo,	3 00
Trigonometry and Tables published separately Each,	2 00
* Ludlow's Logarithmic and Trigonometric Tables 8vo,	1 00
Manning's Irrational Numbers and their Representation by Sequences and Series	
	12mo, 1 25
Mathematical Monographs. Edited by Mansfield Merriman and Robert	
S. Woodward. Octavo, each	1 00
No. 1. History of Modern Mathematics, by David Eugene Smith.	
No. 2. Synthetic Projective Geometry, by George Bruce Halsted.	
No. 3. Determinants, by Laenas Gifford Weld. No. 4. Hyper-	
bolic Functions, by James McMahon. No. 5. Harmonic Func-	
tions, by William E. Byerly. No. 6. Grassmann's Space Analysis,	
by Edward W. Hyde. No. 7. Probability and Theory of Errors,	
by Robert S. Woodward. No. 8. Vector Analysis and Quaternions,	
by Alexander Macfarlane. No. 9. Differential Equations, by	
William Woolsey Johnson. No. 10. The Solution of Equations,	
by Mansfield Merriman. No. 11. Functions of a Complex Variable,	
by Thomas S. Fiske.	
Maurer's Technical Mechanics. 8vo,	4 00
Merriman's Method of Least Squares. 8vo,	2 00
Rice and Johnson's Elementary Treatise on the Differential Calculus. Sm. 8vo,	3 00
Differential and Integral Calculus. 2 vols. in one. Small 8vo,	2 50
* Veblen and Lennes's Introduction to the Real Infinitesimal Analysis of One	
Variable 8vo,	2 00
Wood's Elements of Co-ordinate Geometry. 8vo,	2 00
Trigonometry: Analytical, Plane, and Spherical 12mo,	1 00

MECHANICAL ENGINEERING.

MATERIALS OF ENGINEERING, STEAM-ENGINES AND BOILERS.

Bacon's Forge Practice. 12mo,	1 50
Baldwin's Steam Heating for Buildings. 12mo,	2 50
Barr's Kinematics of Machinery. 8vo,	2 50
* Bartlett's Mechanical Drawing. 8vo,	3 00
* " " " Abridged Ed. 8vo,	1 50
Benjamin's Wrinkles and Recipes. 12mo,	2 00
Carpenter's Experimental Engineering. 8vo,	6 00
Heating and Ventilating Buildings. 8vo,	4 00
Clerk's Gas and Oil Engine. Small 8vo,	4 00
Coolidge's Manual of Drawing. 8vo, paper,	1 00
Coolidge and Freeman's Elements of General Drafting for Mechanical En-	
gineers. Oblong 4to,	2 50
Cromwell's Treatise on Toothed Gearing. 12mo,	1 50
Treatise on Belts and Pulleys. 12mo,	1 50

Durley's Kinematics of Machines.	8vo,	4 00
Flather's Dynamometers and the Measurement of Power.	12mo,	3 00
Rope Driving.	12mo,	2 00
Gill's Gas and Fuel Analysis for Engineers.	12mo,	1 25
Hall's Car Lubrication.	12mo,	1 00
Haring's Ready Reference Tables (Conversion Factors).	16mo, morocco,	2 50
Hutton's The Gas Engine.	8vo,	5 00
Jamison's Mechanical Drawing.	8vo,	2 50
Jones's Machine Design:		
Part I. Kinematics of Machinery.	8vo,	1 50
Part II. Form, Strength, and Proportions of Parts.	8vo,	3 00
Kent's Mechanical Engineers' Pocket-book.	16mo, morocco,	5 00
Kerr's Power and Power Transmission.	8vo,	2 00
Leonard's Machine Shop, Tools, and Methods.	8vo,	4 00
* Lorenz's Modern Refrigerating Machinery. (Pope, Haven, and Dean.) ..	8vo,	4 00
MacCord's Kinematics; or, Practical Mechanism.	8vo,	5 00
Mechanical Drawing.	4to,	4 00
Velocity Diagrams.	8vo,	1 50
MacFarland's Standard Reduction Factors for Gases.	8vo,	1 50
Mahan's Industrial Drawing. (Thompson.)	8vo,	3 50
Poole's Calorific Power of Fuels.	8vo,	3 00
Reid's Course in Mechanical Drawing.	8vo,	2 00
Text-book of Mechanical Drawing and Elementary Machine Design.	8vo,	3 00
Richard's Compressed Air.	12mo,	1 50
Robinson's Principles of Mechanism.	8vo,	3 00
Schwamb and Merrill's Elements of Mechanism.	8vo,	3 00
Smith's (O.) Press-working of Metals.	8vo,	3 00
Smith (A. W.) and Marx's Machine Design.	8vo,	3 00
Thurston's Treatise on Friction and Lost Work in Machinery and Mill Work.	8vo,	3 00
Animal as a Machine and Prime Motor, and the Laws of Energetics.	12mo,	1 00
Tillson's Complete Automobile Instructor.	16mo,	1 50
	Morocco,	2 00
Warren's Elements of Machine Construction and Drawing.	8vo,	7 50
Weissbach's Kinematics and the Power of Transmission. (Herrmann—Klein.) ..	8vo,	5 00
Machinery of Transmission and Governors. (Herrmann—Klein.) ..	8vo,	5 00
Wolff's Windmill as a Prime Mover.	8vo,	3 00
Wood's Turbines.	8vo,	2 50

MATERIALS OF ENGINEERING.

* Bovey's Strength of Materials and Theory of Structures.	8vo,	7 50
Burr's Elasticity and Resistance of the Materials of Engineering. 6th Edition. Reset.	8vo,	7 50
Church's Mechanics of Engineering.	8vo,	6 00
* Greene's Structural Mechanics.	8vo,	2 50
Johnson's Materials of Construction.	8vo,	6 00
Keep's Cast Iron.	8vo,	2 50
Lanza's Applied Mechanics.	8vo,	7 50
Martens's Handbook on Testing Materials. (Henning.)	8vo,	7 50
Maurer's Technical Mechanics.	8vo,	4 00
Merriman's Mechanics of Materials.	8vo,	5 00
* Strength of Materials.	12mo,	1 00
Metcalf's Steel. A Manual for Steel-users.	12mo,	2 00
Sabin's Industrial and Artistic Technology of Paints and Varnish.	8vo,	3 00
Smith's Materials of Machines.	12mo,	1 00
Thurston's Materials of Engineering.	3 vols., 8vo,	8 00
Part II. Iron and Steel.	8vo,	3 50
Part III. A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents.	8vo,	2 50

Wood's (De V.) Treatise on the Resistance of Materials and an Appendix on the Preservation of Timber.	8vo,	2 00
Elements of Analytical Mechanics.	8vo,	3 00
Wood's (M. P.) Rustless Coatings: Corrosion and Electrolysis of Iron and Steel.	8vo,	4 00

STEAM-ENGINES AND BOILERS.

Berry's Temperature-entropy Diagram.	12mo,	1 25
Carnot's Reflections on the Motive Power of Heat. (Thurston.)	12mo,	1 50
Creighton's Steam-engine and other Heat-motors.	8vo,	5 00
Dawson's "Engineering" and Electric Traction Pocket-book.	16mo, mor.,	5 00
Ford's Boiler Making for Boiler Makers.	18mo,	1 00
Goss's Locomotive Sparks.	8vo,	2 00
Locomotive Performance.	8vo,	5 00
Hemenway's Indicator Practice and Steam-engine Economy.	12mo,	2 00
Hutton's Mechanical Engineering of Power Plants.	8vo,	5 00
Heat and Heat-engines.	8vo,	5 00
Kent's Steam boiler Economy.	8vo,	4 00
Kneass's Practice and Theory of the Injector.	8vo,	1 50
MacCord's Slide-valves.	8vo,	2 00
Meyer's Modern Locomotive Construction.	4to,	10 00
Peabody's Manual of the Steam-engine Indicator.	12mo,	1 50
Tables of the Properties of Saturated Steam and Other Vapors.	8vo,	1 00
Thermodynamics of the Steam-engine and Other Heat-engines.	8vo,	5 00
Valve-gears for Steam-engines.	8vo,	2 50
Peabody and Miller's Steam-boilers.	8vo,	4 00
Pray's Twenty Years with the Indicator.	Large 8vo,	2 50
Pupin's Thermodynamics of Reversible Cycles in Gases and Saturated Vapors. (Osterberg.)	12mo,	1 25
Reagan's Locomotives: Simple, Compound, and Electric. New Edition.	Large 12mo,	3 50
Sinclair's Locomotive Engine Running and Management.	12mo,	2 00
Smart's Handbook of Engineering Laboratory Practice.	12mo,	2 50
Snow's Steam-boiler Practice.	8vo,	3 00
Spangler's Valve-gears.	8vo,	2 50
Notes on Thermodynamics.	12mo,	1 00
Spangler, Greene, and Marshall's Elements of Steam-engineing.	8vo,	3 00
Thomas's Steam-turbines.	8vo,	3 50
Thurston's Handy Tables.	8vo,	1 50
Manual of the Steam-engine.	2 vols., 8vo,	10 00
Part I. History, Structure, and Theory.	8vo,	6 00
Part II. Design, Construction, and Operation.	8vo,	6 00
Handbook of Engine and Boiler Trials, and the Use of the Indicator and the Prony Brake.	8vo,	5 00
Stationary Steam-engines.	8vo,	2 50
Steam-boiler Explosions in Theory and in Practice.	12mo,	1 50
Manual of Steam-boilers, their Designs, Construction, and Operation.	8vo,	5 00
Wehrenfenning's Analysis and Softening of Boiler Feed-water (Patterson)	8vo,	4 00
Weisbach's Heat, Steam, and Steam-engines. (Du Bois.)	8vo,	5 00
Whitham's Steam-engine Design.	8vo,	5 00
Wood's Thermodynamics, Heat Motors, and Refrigerating Machines.	8vo,	4 00

MECHANICS AND MACHINERY.

Barr's Kinematics of Machinery.	8vo,	2 50
* Bovey's Strength of Materials and Theory of Structures.	8vo,	7 50
Chase's The Art of Pattern-making.	12mo,	2 50

Church's Mechanics of Engineering.	8vo,	6 00
Notes and Examples in Mechanics.	8vo,	2 00
Compton's First Lessons in Metal-working.	12mo,	1 50
Compton and De Groodt's The Speed Lathe	12mo,	1 50
Cromwell's Treatise on Toothed Gearing.	12mo,	1 50
Treatise on Belts and Pulleys.	12mo,	1 50
Dana's Text-book of Elementary Mechanics for Colleges and Schools.	12mo,	1 50
Dingey's Machinery Pattern Making	12mo,	2 00
Dredge's Record of the Transportation Exhibits Building of the World's Columbian Exposition of 1893.	4to half morocco,	5 00
Du Bois's Elementary Principles of Mechanics:		
Vol. I. Kinematics.	8vo,	3 50
Vol. II. Statics.	8vo,	4 00
Mechanics of Engineering. Vol. I.	Small 4to,	7 50
Vol. II.	Small 4to,	10 00
Durley's Kinematics of Machines.	8vo,	4 00
Fitzgerald's Boston Machinist.	16mo,	1 00
Flather's Dynamometers, and the Measurement of Power.	12mo,	3 00
Rope Driving.	12mo,	2 00
Goss's Locomotive Sparks.	8vo,	2 00
Locomotive Performance.	8vo,	5 00
* Greene's Structural Mechanics.	8vo,	2 50
Hall's Car Lubrication.	12mo,	1 00
Hobart and Ellis's High-speed Dynamo Electric Machinery. (In Press.)		
Holly's Art of Saw Filing.	18mo,	75
James's Kinematics of a Point and the Rational Mechanics of a Particle.		
	Small 8vo,	2 00
* Johnson's (W. W.) Theoretical Mechanics.	12mo,	3 00
Johnson's (L. J.) Statics by Graphic and Algebraic Methods.	8vo,	2 00
Jones's Machine Design:		
Part I. Kinematics of Machinery.	8vo,	1 50
Part II. Form, Strength, and Proportions of Parts.	8vo,	3 00
Kerr's Power and Power Transmission.	8vo,	2 00
Lanza's Applied Mechanics.	8vo,	7 50
Leonard's Machine Shop, Tools, and Methods.	8vo,	4 00
* Lorenz's Modern Refrigerating Machinery. (Pope, Haven, and Dean.)	8vo,	4 00
MacCord's Kinematics; or, Practical Mechanism.	8vo,	5 00
Velocity Diagrams.	8vo,	1 50
* Martin's Text Book on Mechanics, Vol. I, Statics.	12mo,	1 25
* Vol. 2, Kinematics and Kinetics.	12mo,	1 50
Maurer's Technical Mechanics.	8vo,	4 00
Merriman's Mechanics of Materials.	8vo,	5 00
* Elements of Mechanics.	12mo,	1 00
* Michie's Elements of Analytical Mechanics.	8vo,	4 00
* Parshall and Hobart's Electric Machine Design.	4to, half morocco,	12 50
Reagan's Locomotives: Simple, Compound, and Electric. New Edition.		
	Large 12mo,	3 50
Reid's Course in Mechanical Drawing.	8vo,	2 00
Text-book of Mechanical Drawing and Elementary Machine Design.	8vo,	3 00
Richards's Compressed Air.	12mo,	1 50
Robinson's Principles of Mechanism.	8vo,	3 00
Ryan, Norris, and Hoxie's Electrical Machinery. Vol. I.	8vo,	2 50
Sanborn's Mechanics: Problems.	Large 12mo,	1 50
Schwamb and Merrill's Elements of Mechanism.	8vo,	3 00
Sinclair's Locomotive-engine Running and Management.	12mo,	2 00
Smith's (O.) Press-working of Metals	8vo,	3 00
Smith's (A. W.) Materials of Machines.	12mo,	1 00
Smith (A. W.) and Marx's Machine Design.	8vo,	3 00
Sorel's Carbureting and Combustion of Alcohol Engines. (Woodward and Preston.)	Large 8vo,	3 00

Spangler Greene and Marshall's Elements of Steam-engineering.	8vo,	3 00
Thurston's Treatise on Friction and Lost Work in Machinery and Mill Work.	8vo,	3 00
Animal as a Machine and Prime Motor, and the Laws of Energetics.	12mo,	1 00
Tillson's Complete Automobile Instructor.	16mo,	1 50
	Morocco,	2 00
Warren's Elements of Machine Construction and Drawing.	8vo,	7 50
Weisbach's Kinematics and Power of Transmission. (Herrmann—Klein.)	8vo,	5 00
Machinery of Transmission and Governors. (Herrmann—Klein.)	8vo,	5 00
Wood's Elements of Analytical Mechanics.	8vo,	3 00
Principles of Elementary Mechanics.	12mo,	1 25
Turbines.	8vo,	2 50
The World's Columbian Exposition of 1893.	4to,	1 00

MEDICAL.

* Bolduan's Immune Sera.	12mo,	1 50
De Fursac's Manual of Psychiatry. (Rosanoff and Collins.)	Large 12mo,	2 50
Ehrlich's Collected Studies on Immunity. (Bolduan.)	8vo,	6 00
* Fischer's Physiology of Alimentation.	Large 12mo, cloth,	2 00
Hammarsten's Text-book on Physiological Chemistry. (Mandel.)	8vo,	4 00
Lassar-Cohn's Practical Urinary Analysis. (Lorenz.)	12mo,	1 00
* Pauli's Physical Chemistry in the Service of Medicine. (Fischer.)	12mo,	1 25
* Pozzi-Escot's The Toxins and Venoms and their Antibodies. (Cohn.)	12mo,	1 00
Rostoski's Serum Diagnosis. (Bolduan.)	12mo,	1 00
Salkowski's Physiological and Pathological Chemistry. (Orndorff.)	8vo,	2 50
* Satterlee's Outlines of Human Embryology.	12mo,	1 25
Steel's Treatise on the Diseases of the Dog.	8vo,	3 50
Von Behring's Suppression of Tuberculosis. (Bolduan.)	12mo,	1 00
Woodhull's Notes on Military Hygiene.	16mo,	1 50
* Personal Hygiene.	12mo,	1 00
Willing's An Elementary Course in Inorganic Pharmaceutical and Medical Chemistry.	12mo,	2 00

METALLURGY.

Betts's Lead Refining by Electrolysis. (In Press.)		
Egleston's Metallurgy of Silver, Gold, and Mercury:		
Vol. I. Silver.	8vo,	7 50
Vol. II. Gold and Mercury.	8vo,	7 50
Goessel's Minerals and Metals: A Reference Book.	16mo, mor,	3 00
* Iles's Lead-smelting.	12mo,	2 50
Keep's Cast Iron.	8vo,	2 50
Kunhardt's Practice of Ore Dressing in Europe.	8vo,	1 50
Le Chatelier's High-temperature Measurements. (Boudouard—Burgess.)	12mo,	3 00
Metcalf's Steel. A Manual for Steel-users.	12mo,	2 00
Miller's Cyanide Process.	12mo,	1 00
Minet's Production of Aluminum and its Industrial Use. (Waldo.)	12mo,	2 50
Robine and Lenglen's Cyanide Industry. (Le Clerc.)	8vo,	4 00
Smith's Materials of Machines.	12mo,	1 00
Thurston's Materials of Engineering. In Three Parts.	8vo,	8 00
Part II. Iron and Steel.	8vo,	3 50
Part III. A Treatise on Brasses, Bronzes, and Other Alloys and their Constituents.	8vo,	2 50
Ulke's Modern Electrolytic Copper Refining.	8vo,	3 00

MINERALOGY.

Barringer's Description of Minerals of Commercial Value. Oblong, morocco,	2 50
Boyd's Resources of Southwest Virginia.	8vo, 3 00

Boyd's Map of Southwest Virginia.....	Pocket-book form.	2 00
* Browning's Introduction to the Rarer Elements.....	8vo,	1 50
Brush's Manual of Determinative Mineralogy. (Penfield.).....	8vo,	4 00
Chester's Catalogue of Minerals.....	8vo, paper,	1 00
	Cloth,	1 25
Dictionary of the Names of Minerals.....	8vo,	3 50
Dana's System of Mineralogy.....	Large 8vo, half leather,	12 50
First Appendix to Dana's New "System of Mineralogy."	Large 8vo,	1 00
Text-book of Mineralogy.....	8vo,	4 00
Minerals and How to Study Them.....	12mo,	1 50
Catalogue of American Localities of Minerals.....	Large 8vo,	1 00
Manual of Mineralogy and Petrography.....	12mo	2 00
Douglas's Untechnical Addresses on Technical Subjects.....	12mo,	1 00
Eakle's Mineral Tables.....	8vo,	1 25
Egleston's Catalogue of Minerals and Synonyms.....	8vo,	2 50
Goessel's Minerals and Metals: A Reference Book.....	16mo, mor.	3 00
Groth's Introduction to Chemical Crystallography (Marshall).....	12mo,	1 25
Iddings's Rock Minerals.....	8vo,	5 00
Johannsen's Key for the Determination of Rock-forming Minerals in Thin Sections. (In Press.)		
* Martin's Laboratory Guide to Qualitative Analysis with the Blowpipe.....	12mo,	60
Merrill's Non-metallic Minerals: Their Occurrence and Uses.....	8vo,	4 00
Stones for Building and Decoration.....	8vo,	5 00
* Penfield's Notes on Determinative Mineralogy and Record of Mineral Tests.		
	8vo, paper,	50
Tables of Minerals.....	8vo,	1 00
* Richards's Synopsis of Mineral Characters.....	12mo, morocco,	1 25
* Ries's Clays: Their Occurrence, Properties, and Uses.....	8vo,	5 00
Rosenbusch's Microscopical Physiography of the Rock-making Minerals. (Iddings.).....	8vo,	5 00
* Tillman's Text-book of Important Minerals and Rocks.....	8vo,	2 00

MINING.

Beard's Mine Gases and Explosions. (In Press.)		
Boyd's Resources of Southwest Virginia.....	8vo,	3 00
Map of Southwest Virginia.....	Pocket-book form,	2 00
Douglas's Untechnical Addresses on Technical Subjects.....	12mo,	1 00
Eissler's Modern High Explosives.....	8vo,	4 00
Goessel's Minerals and Metals: A Reference Book.....	16mo, mor.	3 00
Goodyear's Coal-mines of the Western Coast of the United States.....	12mo,	2 50
Itzeng's Manual of Mining.....	8vo,	5 00
* Iles's Lead-smelting.....	12mo,	2 50
Kunhardt's Practice of Ore Dressing in Europe.....	8vo,	1 50
Miller's Cyanide Process.....	12mo,	1 00
O'Driscoll's Notes on the Treatment of Gold Ores.....	8vo,	2 00
Robine and Lenglen's Cyanide Industry. (Le Clerc.).....	8vo,	4 00
Weaver's Military Explosives.....	8vo,	3 00
Wilson's Cyanide Processes.....	12mo,	1 50
Chlorination Process.....	12mo,	1 50
Hydraulic and Placer Mining. 2d edition, rewritten.....	12mo,	2 50
Treatise on Practical and Theoretical Mine Ventilation.....	12mo,	1 25

SANITARY SCIENCE.

Bashore's Sanitation of a Country House.....	12mo,	1 00
* Outlines of Practical Sanitation.....	12mo,	1 25
Folwell's Sewerage. (Designing, Construction, and Maintenance.)....	8vo,	3 00
Water-supply Engineering.....	8vo,	4 00

Fowler's Sewage Works Analyses.	12mo,	2 00
Fuertes's Water and Public Health.	12mo,	1 50
Water-filtration Works.	12mo,	2 50
Gerhard's Guide to Sanitary House-inspection	16mo,	1 00
Sanitation of Public Buildings.	12mo,	1 50
Hazen's Filtration of Public Water-supplies.	8vo,	3 00
Leach's The Inspection and Analysis of Food with Special Reference to State Control.	8vo,	7 50
Mason's Water-supply. (Considered principally from a Sanitary Standpoint) 8vo,		4 00
Examination of Water. (Chemical and Bacteriological).	12mo,	1 25
* Merriman's Elements of Sanitary Engineering.	8vo,	2 00
Ogden's Sewer Design.	12mo,	2 00
Prescott and Winslow's Elements of Water Bacteriology, with Special Reference to Sanitary Water Analysis.	12mo,	1 25
* Price's Handbook on Sanitation.	12mo,	1 50
Richards's Cost of Food. A Study in Dietaries.	12mo,	1 00
Cost of Living as Modified by Sanitary Science.	12mo,	1 00
Cost of Shelter.	12mo,	1 00
Richards and Woodman's Air, Water, and Food from a Sanitary Standpoint.	8vo,	2 00
* Richards and Williams's The Dietary Computer.	8vo,	1 50
Rideal's S wage and Bacterial Purification of Sewage.	8vo,	4 00
Disinfection and the Preservation of Food.	8vo,	4 00
Turneure and Russell's Public Water-supplies.	8vo,	5 00
Von Behring's Suppression of Tuberculosis. (Bolduan.)	12mo,	1 00
Whipple's Microscopy of Drinking-water.	8vo,	3 50
Wilson's Air Conditioning. (In Press.)		
Winton's Microscopy of Vegetable Foods.	8vo,	7 50
Woodhull's Notes on Military Hygiene.	16mo,	1 50
* Personal Hygiene.	12mo,	1 00

MISCELLANEOUS.

Association of State and National Food and Dairy Departments (Interstate Pure Food Commission):		
Tenth Annual Convention Held at Hartford, July 17-20, 1906.	8vo,	3 00
Eleventh Annual Convention, Held at Jamestown Tri-Centennial Exposition, July 16-19, 1907. (In Press.)		
Emmons's Geological Guide-book of the Rocky Mountain Excursion of the International Congress of Geologists.	Large 8vo,	1 50
Ferrel's Popular Treatise on the Winds.	8vo,	4 00
Gannett's Statistical Abstract of the World.	24mo,	75
Gerhard's The Modern Bath and Bath-houses. (In Press.)		
Haines's American Railway Management.	12mo,	2 50
Ricketts's History of Rensselaer Polytechnic Institute, 1824-1894. Small 8vo,		3 00
Rotherham's Emphasized New Testament.	Large 8vo,	2 00
Standage's Decorative Treatment of Wood, Glass, Metal, etc. (In Press.)		
The World's Columbian Exposition of 1893	4to,	1 00
Winslow's Elements of Applied Microscopy.	12mo,	1 50

HEBREW AND CHALDEE TEXT-BOOKS.

Green's Elementary Hebrew Grammar.	12mo,	1 25
Hebrew Chrestomathy.	8vo,	2 00
Gesenius's Hebrew and Chaldee Lexicon to the Old Testament Scriptures. (Tregelles.)	Small 4to, half morocco,	5 00
Letteris's Hebrew Bible.	8vo,	2 25

Central Archaeological Library,

NEW DELHI.

Acc. No. 20302

Call No. *721.975011/Ty/Mau*

Author *Turner & Maurer, R. E. & Maurer, E. R.*

Title *Principles of Reinforced Concrete Construction*

"A book that is shut is but a block"

CENTRAL ARCHAEOLOGICAL LIBRARY
GOVT. OF INDIA
Department of Archaeology
NEW DELHI.

Please help us to keep the book
clean and moving.